COUNTY	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
COWETA	CSSTP-0007-00(307)	9	138

REV. 12-28-05

SUMMARY OF QUANTITIES - SIGNING AND MARKING

STATION	INSTAL. NO.	SIGN CODE	HIGHWAY SIGNS: TY 1 MATL. REFL. SHEETING TYPE 6 SIZE (IN.)	QUANTITY	SQUARE FEET	TY 2 MATL. REFL. SHEETING TYPE 3 SIZE (IN.)	QUANTITY	SQUARE FEET	TY 2 MATL. REFL. SHEETING TYPE 6 SIZE (IN)	QUANTITY	SQUARE FEET	SQUARE TUBE POST: TYPE 7 LENGTH (FT)	QUANTITY	TOTAL LENGTH	TYPE 8 LENGTH (FT)	QUANTITY	TOTAL LENGTH	BREAKWAY SIGN SUPORT (EACH)
234+10 RT		R1-2 (36)	36 X 36	1	9								1	14				
245+00 RT		W3-3 (36)	36 X 36	1	9													
245+00 RT		D3-2 (24)																
246+50 RT		R1-2 (36)	36 X 36	1	9				60 X 24	1	10		2	30				
247+00 LT		R1-2 (36)	36 X 36	1	9								1	14				
247+00 LT		R-560 (18)	24 X 18	1	3								1	14				
248+00 LT		R-560 (18)	24 X 18	1	3								1	14				
250+30 LT		W3-3 (36)	36 X 36	1	9								1	14				
250+30 LT		D3-2 (24)																
247+00		D SPEC*1				80X12	1(DOUBLE SIDED)	14	60 X 24	1	10		2	30				
248+00		D SPEC*1				80X12	1(DOUBLE SIDED)	14										
NEWNAN CROSSING BLVD																		
051+80 RT		R-560 (18)	24 X 18	1	3								1	14				
045+49 LT		R-560 (18)	24 X 18	1	3								1	14				
054+70 LT		W3-3 (36)	36 X 36	1	9									14				
054+70 LT		D3-2 (24)							60 X 24	1	10		2	30				
051+80 RT		W3-3 (36)	36 X 36	1	9													
051+80 RT		D3-2 (24)							60 x 24	1	10		2	30				
052+05		D SPEC*2				132X18	1(DOUBLE SIDED)	33										
053+60		D SPEC*2				132X18	1(DPUBLE SIDED)	33										
TOTAL				11	75		4	94		6	40		15	232				

KISINGER CAMPO & ASSOCIATES CORP.
1720 PEACHTREE ST., N.W., SUITE 1048
ATLANTA, GA 30309

REVISION DATES
12/28/05

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE:
SUMMARY OF QUANTITIES

DRAWING No. 06-03

GPLN