REV. 12-28-05

ITEM NO.	DESCRIPTION	UNITS	QUANTITY
	SR 34@NEWNAN CROSSING BLVD		
	ROADWAY		
150-1000	TRAFFIC CONTROL - CSSTP-0007-00(307)	LS	1
210-0100	GRADING COMPLETE - CSSTP-0007-00(307)	LS	1
310-1101	GR AGGR BASE CRS, INCL MATL	TN	3300
402-1812	RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	TN	190
402-3121	RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM	TN	2150
402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM	TN	540
402-4510	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	TN	600
413-1000	BITUM TACK COAT	GL	680
432-5010	MILL ASPH CONC PVMT, VARIABLE DEPTH	SY	100
441-0104	CONC SIDEWALK, 4 IN	SY	170
441-0754	CONCRETE MEDIAN, 7 1/2 IN	SY	140
441-6222	CONC CURB & GUTTER, 8 IN X 30 IN, TP 2	LF	340
444-1000	SAWED JOINTS IN EXIST PAVEMENTS - PCC	LF	100
500-9999	CLASS B CONC, BASE OR PVMT WIDENING	CY	25
550-1150	STORM DRAIN PIPE, 15 IN, H 1-10	LF	16
550-1180	STORM DRAIN PIPE, 18 IN, H 1-10	LF	8
550-1240	STORM DRAIN PIPE, 24 IN, H 1-10	LF	16
550-4215	FLARED END SECTION 15 IN, STORM DRAIN	EA	1
550-4224	FLARED END SECTION 24 IN, STORM DRAIN	EA	1
610-6605	REM LIGHTING STANDARD	EA	1
611-4001	RECONSTR MINOR DRAINAGE STR	EA	3
611-5480	RESET LIGHTING STANDARD	EA	1
611-9000	CAPPING MINOR STRUCTURE	EA	3
668-2100	DROP INLET, GP 1	EA	3
668-2110	DROP INLET, GP 1, ADDL DEPTH	LF	13
	TRAFFIC SIGNS & MARKINGS		
636-1029	HIGHWAY SIGNS, TP 2 MATL, REFL SHEETING, TP 3	SF	94
636-1031	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 6	SF	75
636-1032	HIGHWAY SIGNS, TP 2 MATL, REFL SHEETING, TP 6	SF	40
636-2070	GALV STEEL POSTS, TP 7	LF	232
652-5452	SOLID TRAFFIC STRIPE, 5 IN, YELLOW	LF	2126
653-0110	THERMOPLASTIC PVMT MARKING, ARROW, TP 1	EA	2
653-0120	THERMOPLASTIC PVMT MARKING, ARROW, TP 2	EA	19
653-0130	THERMOPLASTIC PVMT MARKING, ARROW, TP 3	EA	1
653-0210	THERMOPLASTIC PVMT MARKING, WORD, TP 1	EA	8
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	2958
653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	LF	137
653-1804	THERMOPLASTIC SOLID TRAF STRIPE, 8 IN, WHITE	LF	312
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	804
653-6004	THERMOPLASTIC TRAF STRIPING, WHITE	SY	2753
653-6006	THERMOPLASTIC TRAF STRIPING, YELLOW	SY	6
654-1003	RAISED PVMT MARKERS TP 3	EA	99
656-3600	REMOVE EXIST TRAF STRIPE, ALL KINDS & TYPES	SY	1000

ITEM NO.	DESCRIPTION	UNITS	QUANTITY
	EROSION CONTROL		
163-0232	TEMPORARY GRASSING	AC	5
163-0240	MULCH	TN	130
163-0300	CONSTRUCTION EXIT	EA	2
163-0503	CONSTRUCT AND REMOVE SILT CONTROL GATE, TP 3	EA	1
163-0530	CONSTRUCT AND REMOVE BALED STRAW EROSION CHECK	LF	320
163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EA	4
165-0010	MAINTENANCE OF TEMPORARY SILT FENCE, TP A	LF	1050
165-0070	MAINTENANCE OF BALED STRAW EROSION CHECK	LF	160
165-0087	MAINTENANCE OF SILT CONTROL GATE, TP 3	EA	1
165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	EA	4
167-1000	WATER QUALITY MONITORING AND SAMPLING	EA	2
167-1500	WATER QUALITY INSPECTIONS	MO	12
171-0010	TEMPORARY SILT FENCE, TYPE A	LF	2100
441-0204	PLAIN CONC DITCH PAVING, 4 IN	SY	2400
603-2182	STN DUMPED RIP RAP, TP 3, 24 IN	SY	50
603-7000	PLASTIC FILTER FABRIC	SY	50
700-6910	PERMANENT GRASSING	AC	10
700-7000	AGRICULTURAL LIME	TN	30
700-7010	LIQUID LIME	GL	34
700-8000	FERTILIZER MIXED GRADE	TN	20
700-8100	FERTILIZER NITROGEN CONTENT	LB	900
710-9000	PERMANENT SOIL REINFORCING MAT	SY	1000
716-2000	EROSION CONTROL MATS, SLOPES	SY	1000
	SIGNAL		
639-4004	STRAIN POLE, TP IV	EA	4
647-1000	TRAFFIC SIGNAL INSTALLATION NO - 1	LS	1
647-2140	PULL BOX, PB-4	EA	2
DELETE ~~656-3600~~	~~REMOVE EXIST TRAF STRIPE, ALL KINDS & TYPES~~	~~SY~~	~~0~~
682-6222	CONDUIT, NONMETL, TP 2, 2 IN	LF	200
687-1000	TRAFFIC SIGNAL TIMING NO -1	LS	1
935-1113	OUTSIDE PLANT FIBER OPTIC CABLE, LOOSE TUBE, SINGLE	LF	200
935-1511	OUTSIDE PLANT FIBER OPTIC CABLE, DROP, SINGLE MODE,	LF	200
935-3403	FIBER OPTIC CLOSURE, FDC (RACK MOUNTED), 24 FIBER	EA	1
935-4010	FIBER OPTIC SPLICE, FUSION	EA	1
936-1001	CCTV SYSTEM, TYPE B	EA	1
936-8000	TESTING	LS	1
939-1190	VIDEO ENCODER, TYPE A	EA	1
939-1195	VIDEO DECODER, TYPE A	EA	1
939-1375	PUBLIC NETWORK DIAL-UP MODEM	EA	1
939-2300	FIELD SWITCH, TYPE A	EA	1
939-4050	TYPE E CABINET	EA	1
939-8000	TESTING	LS	1

KISINGER CAMPO & ASSOCIATES CORP.
1720 PEACHTREE ST., N.W., SUITE 1048
ATLANTA, GA 30309

REVISION DATES
12/28/05

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION

OFFICE:

DETAILED ESTIMATE

DRAWING No. 9-01

GPLN