ITEM NO.	DESCRIPTION	UNITS	QUANTITY
	ROADWAY ITEMS		
150-1000	TRAFFIC CONTROL - STP00-0007-00(339)	LS	LUMP
210-0100	GRADING COMPLETE - STP00-0007-00(339)	LS	LUMP
310-1101	GR AGGR BASE CRS, INCL MATL	TN	2350
318-3000	AGGR SURF CRS	TN	240
402-1812	RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	TN	300
402-3121	RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	1300
402-3130	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	635
402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	450
413-1000	BITUM TACK COAT	GL	665
441-0016	DRIVEWAY CONCRETE, 6 IN TK	SY	500
441-0108	CONCRETE SIDEWALK, 8 IN	SY	30
441-0754	CONCRETE MEDIAN, 7½IN	SY	90
444-1000	SAWED JOINTS IN EXIST PAVEMENTS - PCC	LF	185
446-1100	PVMT REINF FABRIC STRIPS, TP 2, 18 INCH WIDTH	LF	2300
500-3800	CLASS A CONCRETE, INCL REINF STEEL	CY	6
550-1180	STORM DRAIN PIPE, 18 IN, H 1-10	LF	604
550-1240	STORM DRAIN PIPE, 24 IN, H 1-10	LF	164
550-1300	STORM DRAIN PIPE, 30 IN, H 1-10	LF	32
550-2180	SIDE DRAIN PIPE, 18 IN, H 1-10	LF	196
550-3324	SAFETY END SECTION 24 IN, STORM DRAIN, 4:1 SLOPE	EA	2
550-3618	SAFETY END SECTION 18 IN, SIDE DRAIN, 6:1 SLOPE	EA	17
550-4118	FLARED END SECTION 18 IN, SIDE DRAIN	EA	5
603-2180	STN DUMPED RIP RAP, TP 3, 12 IN	SY	65
603-7000	PLASTIC FILTER FABRIC	SY	65
610-0209	REM CHAIN LINK FENCE, 4 FT	LF	150
634-1200	RIGHT OF WAY MARKERS	EA	21
643-1132	CH LK FENCE, ZC COAT, 4 FT, 9 GA	LF	112
643-8200	BARRIER FENCE (ORANGE), 4 FT	LF	40
668-5000	JUNCTION BOX	EA	3
668-7018	DRAIN INLET, 18 IN	EA	1
668-8012	SAFETY GRATE, TP 2	SF	60
	EROSION CONTROL ITEMS		
163-0232	TEMPORARY GRASSING	AC	1
163-0240	MULCH	TN	45
163-0300	CONSTRUCTION EXIT	EA	2
163-0503	CONSTRUCT AND REMOVE SILT CONTROL GATE, TP 3	EA	5
163-0528	CONSTRUCT AND REMOVE FABRIC CHECK DAM - TYPE C SILT FENCE	LF	700
163-0529	CONSTRUCT AND REMOVE TEMPORARY SEDIMENT BARRIER OR BALED STRAW CHECK DAM	LF	200
163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EA	4
165-0010	MAINTENANCE OF TEMPORARY SILT FENCE, TP A	LF	570
165-0041	MAINTENANCE OF CHECKDAMS - ALL TYPES	LF	350
165-0071	MAINTENANCE OF SEDIMENT BARRIER - BALED STRAW	LF	100
165-0087	MAINTENANCE OF SILT CONTROL GATE, TP 3	EA	5
165-0101	MAINTENANCE OF CONSTRUCTION EXIT	EA	2
165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	EA	4
167-1000	WATER QUALITY MONITORING AND SAMPLING	EA	2
167-1500	WATER QUALITY INSPECTIONS	MO	9
171-0010	TEMPORARY SILT FENCE, TYPE A	LF	1140
700-6910	PERMANENT GRASSING	AC	2
700-7000	AGRICULTURAL LIME	TN	6
700-7010	LIQUID LIME	GL	5
700-8000	FERTILIZER MIXED GRADE	TN	2
700-8100	FERTILIZER NITROGEN CONTENT	LB	100
716-2000	EROSION CONTROL MATS, SLOPES	SY	2100
	SIGNING AND MARKING ITEMS		
636-1020	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 3	SF	50
636-1033	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 9	SF	45
636-2070	GALV STEEL POSTS, TP 7	LF	180
636-2090	GALV STEEL POSTS, TP 9	LF	35
636-5100	WILEPOST SIGNS	EA	1
653-0120	THERMOPLASTIC PVMT MARKING, ARROW, TP 2	EA	8
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	3400
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	3730
653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	LF	65
653-1804	THERMOPLASTIC SOLID TRAF STRIPE, 8 IN, WHITE	LF	475
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	320
653-6004	THERMOPLASTIC TRAF STRIPING, WHITE	SY	240
653-6006	THERMOPLASTIC TRAF STRIPING, YELLOW	SY	480
654-1001	RAISED PVMT MARKERS TP 1	EA	36
654-1003	RAISED PVMT MARKERS TP 3	EA	52
	TRAFFIC SIGNAL ITEMS		
615-1200	DIRECTIONAL BORE - 3 IN	LF	380
636-1041	HIGHWAY SIGNS, TP 2 MATL-REFL SHEETING, TP 9	SF	33
639-5000	PRESTRESSED CONC STRAIN POLE, TP IV	EA	4
647-1000	TRAFFIC SIGNAL INSTALLATION NO - 1	LS	LUMP
682-6233	CONDUIT, NONMETAL, TP 3, 2 IN	LF	400
	ATMS ITEMS		
935-1113	OUTSIDE PLANT FIBER OPTIC, LOOSE TUBE, SINGLE MODE, 24 FIBER	LF	2400
935-1511	OUTSIDE PLANT FIBER OPTIC CABLE, DROP, SINGLE MODE, 6 FIBER	LF	200
935-3205	FIBER OPTIC CLOSURE, AERIAL (SEALED), 48 FIBER	EA	2
935-3401	FIBER OPTIC CLOSURE, FDC (RACK MOUNTED), 6 FIBER	EA	2
935-4010	FIBER OPTIC SPLICE, FUSION	EA	4
935-5050	FIBER OPTIC PATCH CORD, SM	EA	2
935-6562	EXTERNAL TRANSCEIVER, DROP AND REPEAT, 1310 SINGLE MODE, (SIGNAL JOBS)	EA	2
935-8000	TESTING	LS	LUMP

URS
400 NORTHPARK TOWN CENTER
1000 ABERNATHY ROAD, N.E., SUITE 900
ATLANTA, GEORGIA 30328
TEL: (678) 808-8800 FAX: (678) 808-8400

REVISION DATES

8/7/08		

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION

DISTRICT TWO

DETAILED ESTIMATE

SMITH STORE ROAD / SALEM ROAD
INTERSECTION IMPROVEMENTS

DRAWING No.
9-01