STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA	CSSTP-0007-00(359)	38	87

VOID

332 CABINET INPUT ASSIGNMENT

SLOT	1	2	3	4	5	6	7	8	9	10	11	12	13	14

UPPER INPUT FILE

	TYPE	DET	DET	DET	DET	DET	DET	DET	DET	DET	TBA	TBA	DC	DC	DC
	CARD		2-CH										DC ISO	DC ISO	DC ISO
CHANNEL 1	CI PIN	56	39	63	47	58	41	65	49	60		80	67	68	81
	FUNCTION		L2A									ADVANCE	Ø2 PED	Ø6 PED	FLASH
	FIELD TERM	TB2 1,2	TB2 5,6	TB2 9,10	TB4 1,2	TB4 5,6	TB4 9,10	TB6 1,2	TB6 5,6	TB6 9,10			TB8 4,6	TB8 7,9	N/C
ACTRA/SEPAC	DETECTOR	1	3	5	7	9	11	13	15	17				PED 6	
ACTRA/SEPAC	ASSIGNED	1	2	2	2	3	4	4	4	1				Ø6	

CHANNEL 2	CI PIN	56	43	76	47	58	45	78	49	62		53	69	70	82
	FUNCTION		L2B									ENABLE	Ø4 PED	Ø8 PED	STOP TIME
	FIELD TERM	TB2 3,4	TB2 7,8	TB2 11,12	TB4 3,4	TB4 7,8	TB4 11,12	TB6 3,4	TB6 7,8	TB6 11,12			TB8 5,6	TB8 8,9	N/C
ACTRA/SEPAC	DETECTOR	1	4	6	7	9	12	14	15	18			PED 4	PED 8	
ACTRA/SEPAC	ASSIGNED	1	2	2	2	3	4	4	4	3			Ø4		

LOWER INPUT FILE

	TYPE	DET	DET	DET	DET	DET	DET	DET	DET	DET	TBA	TBA	DC	DC	DC
	CARD	2-CH	2-CH				2-CH								
CHANNEL 1	CI PIN	55	40	64	48	57	42	66	50	59		54	71	72	51
	FUNCTION	L5	L6				L8A						EVA	EVB	RR 1
	FIELD TERM	TB3 1,2	TB3 5,6	TB3 9,10	TB5 1,2	TB5 5,6	TB5 9,10	TB7 1,2	TB7 5,6	TB7 9,10			TB9 4,6	TB9 7,9	TB9 10,12
ACTRA/SEPAC	DETECTOR	19	21	23	25	29	31	33	35	37		SPARE 2			
ACTRA/SEPAC	ASSIGNED	5	6	6	6	7	8	8	8	5					

CHANNEL 2	CI PIN	55	44	77	48	57	46	79	50	61		75	73	74	52
	FUNCTION						L8B					SPARE 3	EVC	EVD	RR 2
	FIELD TERM	TB3 3,4	TB3 7,8	TB3 11,12	TB5 3,4	TB5 7,8	TB5 11,12	TB7 3,4	TB7 7,8	TB7 11,12			TB9 5,6	TB9 8,9	TB9 11,12
ACTRA/SEPAC	DETECTOR	19	22	24	25	29	32	34	36	38					
ACTRA/SEPAC	ASSIGNED	5	6	6	6	7	8	8	8	7					

LIST OF MATERIALS

FOR INFORMATIONAL PURPOSES ONLY

MATERIALS	UNIT	QUANTITY
CABINET CONTROLLER ASSEMBLIES		
A. CONTROLLER UNIT, MODEL 2070L	EA	1
D. CABINET ASSEMBLY, MODEL 332A	EA	1
E. SWITCH PACK	EA	7
F. DC ISOLATOR	EA	3
G. LOOP DETECTOR, 2-CHANNEL	EA	4
J. 2010 CONFLICT MONITOR, EXTENDED FEATURES	EA	1
332A PREFABRICATED CONTROLLER CABINET BASE	EA	1
LOOP/PED LEAD-IN WIRE (SHIELDED, TWISTED/1000 FT) A. 3 PAIR, 18 AWG	REEL	3
SIGNAL CABLE (14AWG) B. 7 CONDUCTOR, PER 1000 FT.	REEL	3
LOOP DETECTOR WIRE (14 AWG. STRANDED/1000 FT)	REEL	3
3-SECTION 12" LED SIGNAL HEAD W/INCANDESCENT VIEW LED'S SIGNAL HEAD PLASTIC	EA	10
1-SECTION 18" LED COUNTDOWN PEDESTRIAN SIGNAL HEAD, FULL HANDMAN OVERLAP	EA	6
PEDESTRIAN PUSH STATION ASSEMBLY (9"X15")	EA	6
PEDESTRIAN PUSHBUTTON STATION W/BUTTONS AND SIGNS: 9"X15"	EA	6
PLASTIC LOUVERED BACK PLATE FOR ONE-WAY, 3-SECTION, 12" SIGNAL HEAD	EA	10
HARDWARE FOR SPAN WIRE MOUNTING	EA	10
HARDWARE FOR PEDESTAL POLE, TOP POST MOUNTING, ONE-WAY BRACKET ASSEMBLY	EA	6
PEDESTAL POLE & SQUARE BASE	EA	6
PULL BOX, PB-2	EA	18
PULL BOX, PB-3	EA	6
LOOP SAW CUT	LF	600
CONDUIT, 1"	LF	150
CONDUIT, 2"	LF	1400
R560-5 SIGN W/ TYPE 7 POST	EA	2
R10-5 SIGN	EA	1
MISC MATL TO COMPLETE INSTALLATION	LS	LS

• Engineering
• Architecture
• Planning
• Construction Management
3169 Holcomb Bridge Road
Suite 455
Norcross, Georgia 30071
(404) 329-5900

GEORGIA
DEPARTMENT
OF
TRANSPORTATION

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION

OFFICE: PROGRAM DELIVERY

SIGNAL INSTALLATION PLANS
US 301/SR 73 @ SR 21

INTERSECTION NO. 7

DRAWING No.
27-29