ITEM DESCRIPTION	UNIT	LOCATION						TOTAL
		INT. NO 1	INT. NO 2	INT. NO 3	INT. NO 4	INT. NO 5	INT. NO 6	
CONC SIDEWALK, 6 IN	SY	140	83	158	104	227	74	786
CONCRETE HEADER CURB, 6 IN, TP 2	LF				15	197		212
CONC CURB & GUTTER, 8 IN X 30 IN, TP 2	LF	134	88	355	146	290	144	1157
DIRECTIONAL BORE - 3 IN	LF	240		500	364	524	556	2184
DIRECTIONAL BORE - 5 IN	LF	250	170	204	218	199	222	1263
RIGHT OF WAY MARKERS	EA		6	9		6		21
HIGHWAY SIGNS, TP 2 MATL, REFL SHEETING, TP 9	SF	8	27	30	57	24	27	173
STEEL STRAIN POLE, TP IV, INCL 30 FT MAST ARM	EA		1					1
STEEL STRAIN POLE, TP IV, INCL 35 FT MAST ARM	EA				1			1
STEEL STRAIN POLE, TP IV, INCL 40 FT MAST ARM	EA			2			1	3
STEEL STRAIN POLE, TP IV, INCL COMB 35 FT/55 FT MAST ARMS	EA		1					1
STEEL STRAIN POLE, TP IV, W/ 35 FT MAST ARM, INCL LUMINAIRE ARM	EA	1					1	2
STEEL STRAIN POLE, TP IV, W/ 40 FT MAST ARM, INCL LUMINAIRE ARM	EA		1					1
STEEL STRAIN POLE, TP IV, W/ 55 FT MAST ARM, INCL LUMINAIRE ARM	EA				1			1
STEEL STRAIN POLE, TP IV, INCL COMB 35 FT/50 FT MAST ARMS, INCL LUMINAIRE ARM	EA			1	1			2
STEEL STRAIN POLE, TP IV, INCL TWIN 40 FT MAST ARMS, INCL LUMINAIRE ARM	EA						1	1
STEEL STRAIN POLE, TP IV, INCL COMB 40 FT/45 FT MAST ARMS, INCL LUMINAIRE ARM	EA					1		1
STEEL STRAIN POLE, TP IV, INCL TWIN 45 FT MAST ARMS, INCL LUMINAIRE ARM	EA					1		1
STEEL STRAIN POLE, TP IV, INCL COMB 55 FT/60 FT MAST ARMS, INCL LUMINAIRE ARM	EA	1						1
TRAFFIC SIGNAL INSTALLATION NO. 1	LUMP	LUMP						LUMP
TRAFFIC SIGNAL INSTALLATION NO. 2	LUMP		LUMP					LUMP
TRAFFIC SIGNAL INSTALLATION NO. 3	LUMP			LUMP				LUMP
TRAFFIC SIGNAL INSTALLATION NO. 4	LUMP				LUMP			LUMP
TRAFFIC SIGNAL INSTALLATION NO. 5	LUMP					LUMP		LUMP
TRAFFIC SIGNAL INSTALLATION NO. 6	LUMP						LUMP	LUMP
PULL BOX, PB-2	EA	9	6	4	6	5	6	36
PULL BOX, PB-3	EA	3	3	3	3	3	3	18
PEDESTAL POLE 10 FT	EA	5	3	1	1	2	2	14
THERMOPLASTIC PVMT MARKING, ARROW, TP 1	EA						1	1
THERMOPLASTIC PVMT MARKING, ARROW, TP 2	EA		8	4	4		3	19
THERMOPLASTIC PVMT MARKING, ARROW, TP 3	EA	1					2	3
THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 IN, WHITE	LF	1806	1759	910	1665	1497	1240	8877
THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 IN, YELLOW	LF	1882	1504	1372	1352	1328	1326	8764
THERMOPLASTIC SOLID TRAFFIC STRIPE, 24 IN, WHITE	LF	66	89	112	98	58	100	523
THERMOPLASTIC SOLID TRAFFIC STRIPE, 8 IN, WHITE	LF	1246	788	744	752	686	871	5087
THERMOPLASTIC SKIP TRAFFIC STRIPE, 5 IN, WHITE	GLF	1410	570	1120	65		458	3623
THERMOPLASTIC SKIP TRAFFIC STRIPE, 5 IN, YELLOW	GLF						220	220
THERMOPLASTIC TRAF STRIPING, YELLOW	SY	132						132
RAISED PVMT MARKERS TP1	EA	125	12	20	18	18	18	211
RAISED PVMT MARKERS TP3	EA	20	24	27	12		22	105
CONDUIT, RIGID, 1 IN	LF	100	45	10	60	30	75	320
CONDUIT, NONMETAL, TP 2, 1 IN	LF	87	99	45	65	35	95	426
CONDUIT, NONMETAL, TP 2, 2 IN	LF	607	386	85	274	55	185	1592
CONDUIT, NONMETAL, TP 3, 2 IN	LF	740	370	923	800	922	996	4751

CLASS B CONCRETE BASE OR PAVEMENT WIDENING	
UNIT	QUANTITY
CY	10

TRAFFIC CONTROL CSSTP-0007-00(366)	
UNIT	QUANTITY
LUMP	LUMP

GRADING COMPLETE CSSTP-0007-00(366)	
UNIT	QUANTITY
LUMP	LUMP

TEMPORARY SILT FENCE TP A	
UNIT	QUANTITY
LF	250

MAINT. SILT FENCE TP A	
UNIT	QUANTITY
LF	125

AGRICULTURAL LIME	
UNIT	QUANTITY
TN	1

MAINTENANCE OF SEDIMENT BARRIER - BALED STRAW.	
UNIT	QUANTITY
LF	50

FERTILIZER MIXED GRADE	
UNIT	QUANTITY
TN	1

CONSTRUCT AND REMOVE TEMPORARY BALED STRAW CHECK DAM	
UNIT	QUANTITY
LF	100

LIQUID LIME	
UNIT	QUANTITY
GAL	3

FERTILIZER NITROGEN CONTENT	
UNIT	QUANTITY
LBS	50

PERMANENT GRASSING	
UNIT	QUANTITY
AC	1

TEMPORARY GRASSING	
UNIT	QUANTITY
AC	1

SOD	
UNIT	QUANTITY
SY	100

MULCH	
UNIT	QUANTITY
TN	1

RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE I, GP 1 OR BLEND 1, INCL BITUM MATL & H LIME	
UNIT	QUANTITY
TN	10

$DESIGNED BY$	$CHECKED BY$	$DATE 1$
	$REVIEWED BY$	$DATE 2$

ITERIS

REVISION DATES		
6/3/2010		
6/9/2010		

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: TRAFFIC OPERATIONS

SUMMARY OF QUANTITIES

DRAWING No. 6-1