SUMMARY OF QUANTITIES

SUMMARY TRAFFIC SIGNAL ITEMS

LOCATION	INSTL. NO.	STEEL STRAIN POLE TYPE IV W/ 30 FT MAST ARM, (EA) QUANTITY	STEEL STRAIN POLE TYPE IV W/ 35 FT MAST ARM, (EA) QUANTITY	STEEL STRAIN POLE TYPE IV W/ 40 FT MAST ARM, (EA) QUANTITY	STEEL STRAIN POLE TYPE IV W/ 50 FT MAST ARM, (EA) QUANTITY	STEEL STRAIN POLE TYPE IV W/ DUAL 35 FT/55 FT MAST ARMS, (EA) QUANTITY	STEEL STRAIN POLE TYPE IV W/ DUAL 40 FT/45 FT MAST ARMS, (EA) QUANTITY	STEEL STRAIN POLE TYPE IV W/ DUAL 40 FT/55 FT MAST ARMS, (EA) QUANTITY	STEEL STRAIN POLE TYPE IV W/ DUAL 40 FT/65 FT MAST ARMS, (EA) QUANTITY	STEEL STRAIN POLE TYPE IV W/ DUAL 50 FT/55 FT MAST ARMS, (EA) QUANTITY	STRAIN POLE TYPE IV (EA) QUANTITY	STRAIN POLE TYPE IV, INCLUDING LUMINAIRE ARM, (EA) QUANTITY	LUMINAIRE BRACKET ARM, 10 FT ARM	TRAFFIC SIGNAL INSTALLATION
SR 3/US 41/S WALL ST @ W C BRYANT PKWY	1											2		1
SR 3/US 41/S WALL ST @ MAY ST	2											2		1
SR 3/US 41/S WALL ST @ PETERS ST/RICHARDS ST	3										3			1
SR 53 @ S RIVER ST	4										2	1	1	1
SR 3/US 41/S WALL ST @ PIEDMONT ST	5				1		1							1
SR 3/US 41/S WALL ST @ HICKS ST	6						1	1						1
SR 3/US 41/WALL ST @ SR 53 SPUR/COURT ST	7			1						1				1
SR 3/US 41/N WALL ST @ E LINE ST	8	1			1				1					1
SR 136 CONN./RIVER ST @ LINE ST	9											2	2	1
SR 136 CONN./RIVER ST @ SR 53 SPUR/COURT ST	10		1		1	1								1
SR 3/US 41/N WALL ST @ SR 156/RED BUD RD	11	1		1				1						1
TOTALS		2	1	2	3	1	2	2	1	1	5	7	3	11

Wolverton & Associates
Consulting Engineers + Land Surveyors
6745 Sugarloaf Parkway · Suite 100 · Duluth, Georgia 30097
Phone: (770) 447-8999 · Fax: (770) 447-9070
www.wolverton-assoc.com

GEORGIA
DEPARTMENT
OF
TRANSPORTATION

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DRAWING No.
06-01