SUMMARY OF QUANTITIES

ROADWAY ITEMS

150-1000 TRAFFIC CONTROL CSSTP-0007-00(372)	
UNIT	QUANTITY
LS	LS

210-0100 GRADING COMPLETE CCSSTP-0007-00(372)	
UNIT	QUANTITY
LS	LS

441-0108 CONCRETE SIDEWALK, 8 IN.	
UNIT	QUANTITY
SY	250

402-3130 1½IN RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP1 OR 2	
UNIT	QUANTITY
TN	1

413-1000 BITUM TACK COAT	
UNIT	QUANTITY
GL	1

441-0748 CONCRETE MEDIAN, 6 IN	
UNIT	QUANTITY
SY	90

441-5002 CONCRETE HEADER CURB 6 IN, TP 2	
UNIT	QUANTITY
LF	40

441-6222 CONCRETE CURB & GUTTER, 8 IN X 30 IN, TP 2	
UNIT	QUANTITY
LF	80

441-6740 CONCRETE CURB & GUTTER, 8 IN X 30 IN, TP 7	
UNIT	QUANTITY
LF	85

500-9999 CLASS B CONC, BASE OR PVMT WIDENING	
UNIT	QUANTITY
CY	4

611-8040 ADJUST DROP INLET TO GRADE	
UNIT	QUANTITY
EA	1

634-1200 RIGHT OF WAY MARKERS	
UNIT	QUANTITY
EA	4

EROSION CONTROL ITEMS

163-0240 TEMPORARY GRASSING	
UNIT	QUANTITY
AC	1

163-0240 MULCH	
UNIT	QUANTITY
TN	1

165-0010 MAINTENANCE OF TEMPORARY SILT FENCE, TYPE A	
UNIT	QUANTITY
LF	840

171-0010 TEMPORARY SILT FENCE, TYPE A	
UNIT	QUANTITY
LF	1680

700-6910 PERMANENT GRASSING	
UNIT	QUANTITY
AC	1

700-7000 AGRICULTURAL LIME	
UNIT	QUANTITY
TN	1

700-7010 LIQUID LIME	
UNIT	QUANTITY
GL	3

700-8000 FERTILIZER MIXED GRADE	
UNIT	QUANTITY
TN	1

700-8100 FERTILIZER NITROGEN CONTENT	
UNIT	QUANTITY
LB	10

SIGNING & MARKING/ SIGNAL ITEMS

615-1200 DIRECTIONAL BORE, 3 IN.	
UNIT	QUANTITY
LF	102

615-1200 DIRECTIONAL BORE, 5 IN.	
UNIT	QUANTITY
LF	156

615-1200 DIRECTIONAL BORE, 7 IN.	
UNIT	QUANTITY
LF	170

647-1000 TRAFFIC SIGNAL INSTALLATION NO. 1	
UNIT	QUANTITY
LS	LS

647-1000 TRAFFIC SIGNAL INSTALLATION NO. 2	
UNIT	QUANTITY
LS	LS

647-1000 TRAFFIC SIGNAL INSTALLATION NO. 3	
UNIT	QUANTITY
LS	LS

653-0120 THERMOPLASTIC PVMT MARKING, ARROW, TP 2	
UNIT	QUANTITY
EA	6

653-1501 THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	
UNIT	QUANTITY
LF	320

653-1502 THERMOPLASTIC SOLID TRAF TRAF STRIPE, 5 IN, YELLOW	
UNIT	QUANTITY
LF	1100

653-1704 THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	
UNIT	QUANTITY
LF	280

653-1804 THERMOPLASTIC SOLID TRAFFIC STRIPE, 8 IN, WHITE	
UNIT	QUANTITY
LF	3880

653-6004 THERMOPLASTIC TRAF STRIPING, WHITE	
UNIT	QUANTITY
SY	380

654-1001 RAISED PAVEMENT MARKERS, TP 1	
UNIT	QUANTITY
EA	44

654-1003 RAISED PAVEMENT MARKERS, TP 3	
UNIT	QUANTITY
EA	40

682-6233 CONDUIT, NON METL, TYPE 3, 2 IN	
UNIT	QUANTITY
LN	910

687-1000 TRAFFIC SIGNAL TIMING CSSTP-0007-00(372)	
UNIT	QUANTITY
LS	LS

937-6050 VIDEO DETECTION SYSTEM ASSEMBLY, TYPE A	
UNIT	QUANTITY
EA	4

937-6150 PROGRAMMING MONITOR, TYPE A	
UNIT	QUANTITY
EA	1

937-8030 TESTING - INTERSECTION VIDEO DETECTION CSSTP-0007-00(372)	
UNIT	QUANTITY
LS	LS

937-8530 TRAINING - INTERSECTION VIDEO DETECTION CSSTP-0007-00(372)	
UNIT	QUANTITY
LS	LS

QK4
• Engineering
• Architecture
• Planning
• Construction Management
3169 Holcomb Bridge Road
Suite 455
Norcross, Georgia 30071
(404) 329-5900

GEORGIA
DEPARTMENT
OF
TRANSPORTATION

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: TRAFFIC SAFETY AND DESIGN
SUMMARY OF QUANTITIES

DRAWING No.
06-02