



ITEM	DESCRIPTION	QTY
1	CABLE-MOUNT NIPPLE CLAMP	1
2	NIPPLE, ALUMINUM, 1/2 INCH X 24 INCH, THREAD BOTH ENDS (LENGTH OTHER THAN 24 INCH IF SHOWN IN PLANS)	1
3	U-BOLT, 3/8 INCH COARSE, SS OR GLV, MINIMUM 2 3/4 INCH VERTICAL SEPERATION BETWEEN U-BOLTS	2
4	PIPE SADDLE, ALUMINUM	2
5	BACKING PLATE, 0.125-INCH 5052 ALUMINUM, 5 INCH X 5 INCH	1
6	VIDEO CAMERA SENSOR JUNCTION BOX	1
7	FENDERWASHER, 3/8 INCH, SS	4
8	LOCKWASHER, 3/8 INCH, SS	4
9	NUT, HEX, 3/8 INCH COARSE, SS	4

SS-STAINLESS STEEL
GLV-HOT-DIPPED GALVANIZED STEEL

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
DETAILS

IVDS DETAILS
VIDEO CAMERA SENSOR MOUNTING/JUNCTION BOX