

SUMMARY OF QUANTITIES - SIGNAL, COMMUNICATIONS AND, SIGNING

SIGNAL QUANTITIES

DESCRIPTION	UNIT	TOTAL
DIRECTIONAL BORE, 3 IN	LF	1660
DIRECTIONAL BORE, 5 IN	LF	660
DIRECTIONAL BORE, 7 IN	LF	225

DESCRIPTION	UNIT	TOTAL
STEEL WIRE STRAND CABLE, 1/4 IN	LF	5700

DESCRIPTION	UNIT	TOTAL
PRESTRESSED CONCRETE STRAIN POLE, TP-IV	EA	12
STEEL STRAIN POLE, TP IV, WITH 65' MAST ARM, INCL LUMINAIRE ARM	EA	1
STEEL STRAIN POLE, TP IV, WITH 50' AND 60' TANDEM MAST ARMS	EA	1
STEEL STRAIN POLE, TP IV, WITH 50' AND 65' TANDEM MAST ARMS	EA	1
25FT HIGH STEEL STRAIN POLE, TP IV, WITH 55' MAST ARM	EA	1
25FT HIGH STEEL STRAIN POLE, TP IV, WITH 60' MAST ARM	EA	1
25FT HIGH STEEL STRAIN POLE, TP IV, WITH 65' MAST ARM	EA	2

DESCRIPTION	UNIT	TOTAL
TRAFFIC SIGNAL INSTALLATION NO.1	LS	LS
TRAFFIC SIGNAL INSTALLATION NO.2	LS	LS
TRAFFIC SIGNAL INSTALLATION NO.3	LS	LS
TRAFFIC SIGNAL INSTALLATION NO.4	LS	LS
TRAFFIC SIGNAL INSTALLATION NO.5	LS	LS
TRAFFIC SIGNAL INSTALLATION NO.6	LS	LS

DESCRIPTION	UNIT	TOTAL
CONDUIT, NONMETL, TP 3, 2 IN	LF	3655

DESCRIPTION	UNIT	TOTAL
INTERSECTION VIDEO DETECTION SYSTEM ASSEMBLY, TYPE A	EA	2
PROGRAMMING MONITOR, TYPE A	EA	1
TESTING (VIDEO DETECTION)	LS	1
TRAINING (VIDEO DETECTION)	LS	1

COMMUNICATION QUANTITIES

DESCRIPTION	UNIT	TOTAL
OUTSIDE PLANT FIBER OPTIC CABLE, LOOSE TUBE, SINGLE MODE, 24 FIBER	LF	6500
OUTSIDE PLANT FIBER OPTIC CABLE, DROP, SINGLE MODE, 6 FIBER	LF	900
FIBER OPTIC CLOSURE, AERIAL (SEALED), 24 FIBER	EA	3
FIBER OPTIC SPLICE, FUSION	EA	12
FIBER OPTIC SNOWSHOE	EA	15
TESTING (FIBER OPTIC SYSTEM)	LS	1
TRAINING (FIBER OPTIC SYSTEM)	LS	1

DESCRIPTION	UNIT	TOTAL
EXTERNAL TRANSCEIVER, DROP AND REPEAT, 1310 SINGLE	EA	3

SIGNING QUANTITIES

DESCRIPTION; GALV STEEL POST, TYPE 7	UNIT	TOTAL
R9 3A/3B: 1-14.5FT POST/SIGNS COMBINED, TOTAL 2	LF	29
RI-2 : TWO-14,5FT POST/SIGN, TOTAL 4	LF	116
R5-1: ONE-14FT POST/SIGN, TOTAL 4	LF	56
TOTAL=	LF	201

DESCRIPTION	UNIT	TOTAL
GALV STEEL POST, TYPE 8, TWO POSTS PER SIGN JUNCTION	LF	166.0

DESCRIPTION	UNIT	TOTAL
BREAKWAY SIGN SUPPORT	EA	8

DESCRIPTION	UNIT	TOTAL
PULL BOX, PB-6	EA	3

DESCRIPTION	UNIT	TOTAL
HIGHWAY SIGNS, TP 1MATL, REFL SHEETING, TP 9 (RI-2 & R5-1)	SF	50.00

DESCRIPTION	UNIT	TOTAL
HIGHWAY SIGNS, TP 1MATL, REFL SHEETING, TP 3	SF	148.50
ROUTE MARKER SIGNS, R9 3B/3A , RIO-11A		



GEORGIA
DEPARTMENT
OF
TRANSPORTATION

DESIGNED BY: SM

CHECKED BY: AK

DATE:

REVIEWED BY: DT

DATE:

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE : TRAFFIC OPERATIONS

SUMMARY QUANTITIES

DRAWING No.
6-003