332 DEFAULT INPUT FILES ASSIGNMENT

UPPER INPUT FILE (I)	SLOT		1	2	3	4	5	6	7	8	9	10	11	12	13	14
	TYPE		DET	DET				DET						DC	DC	DC
	CHANNEL 1	CI PIN	56	39	63	47	58	41	65	49	60		80	67	68	81
		FUNCTION	L5	L2A				L4					INT ADV	PH 2 PED		FLASH
		FIELD TERM	TB-2 1,2	TB-2 5,6	TB-2 9,10	TB-4 1,2	TB-4 5,6	TB-4 9,10	TB-6 1,2	TB-6 5,6	TB-6 9,10		NC	TB-8 4,6	TB-8 7,9	NC
	CHANNEL 2	CI PIN	56	43	76	47	58	45	78	49	62		53	69	70	82
		FUNCTION		L2B									MCE	PH 4 PED	PH 3 PED	STOP TIME
		FIELD TERM	TB-2 3,4	TB-2 7,8	TB-2 11,12	TB-4 3,4	TB-4 7,8	TB-4 11,12	TB-6 3,4	TB-6 7,8	TB-6 11,12		NC	TB-8 4,6	TB-8 7,9	NC
LOWER INPUT FILE (J)	SLOT		1	2	3	4	5	6	7	8	9	10	11	12	13	14
	TYPE			VIDEO PROC												
	CHANNEL 1	CI PIN	55	40	64	48	57	42	66	50	59		54	71	72	51
		FUNCTION		V6A												
		FIELD TERM	TB-3 1,2	TB-3 5,6	TB-3 9,10	TB-5 1,2	TB-5 5,6	TB-5 9,10	TB-7 1,2	TB-7 5,6	TB-7 9,10			TB-9 4,6	TB-9 7,9	TB-9 10,12
	CHANNEL 2	CI PIN	55	44	77	48	57	46	79	50	61		75	73	74	52
		FUNCTION		V6B												
		FIELD TERM	TB-3 3,4	TB-3 7,8	TB-3 11,12	TB-5 3,4	TB-5 7,8	TB-5 11,12	TB-7 3,4	TB-7 7,8	TB-7 11,12			TB-9 4,6	TB-9 7,9	TB-9 11,12

LIST OF MATERIALS	UNIT	QUANTITY
CONTROLLER CABINET ASSEMBLIES		
A. CONTROLLER UNIT, MODEL 2070L	EA	1
D. CABINET ASSEMBLY, MODEL 332A	EA	1
E. SWITCH PACK	EA	7
F. DC ISOLATOR	EA	3
G. LOOP DETECTOR, 2 CHANNEL	EA	3
J. 2010 CONFLICT MONITOR, EXTENDED FEATURES	EA	1
332A PREFABRICATED CONTROLLER CABINET BASE	EA	1
LOOP/PED LEAD-IN WIRE (SHIELDED, TWISTED/1000 FT); 3 PAIR, 18 AWG	REEL	2
SIGNAL CABLE (14 AWG); 7 CONDUCTOR, PER 1000 FT.	REEL	2
LOOP DETECTOR WIRE (14 AWG, STRANDED/1000 FT)	REEL	1
3-SECTION, 12" SIGNAL HEAD w/(5mm) LED - 'INCANDESCENT LOOK' - , PLASTIC	EA	6
4-SECTION, 12" SIGNAL HEAD w/ (5mm) LED - 'INCANDESCENT LOOK' - SIGNAL HEAD, PLASTIC	EA	1
1-SECTION, 18" LED COUNTDOWN PEDESTRIAN SIGNAL HEAD, FULL HAND/MAN OVERLAP		
9" HIGH, Numbers & 12" Symbols	EA	6
PEDESTRIAN PUSHBUTTON STATION ADAPTERS (ONLY)		
9" x 15", Double Push Button Station Adapter for 4" Dia Pedestrian Pole, Adjustable	EA	1
PEDESTRIAN PUSHBUTTONS STATIONS, w/BUTTONS and SIGNS:		
9" x 15", R10-3e, (L)eft or (R)ight, Countdown	EA	6
BACK PLATE FOR ONE-WAY, 3-SECTION, 12" SIGNAL HEAD, ABS PLASTIC, BLACK	EA	6
BACK PLATE FOR ONE-WAY, 4-SECTION, 12" SIGNAL HEAD, ABS PLASTIC, BLACK	EA	1
HARDWARE FOR MAST ARM MOUNTING	EA	7
HARDWARE FOR PEDESTAL POLE, TOP POST MOUNTING, ONE-WAY BRACKET ASSEMBLY	EA	4
HARDWARE FOR PEDESTAL POLE, TOP POST MOUNTING, TWO-WAY BRACKET ASSEMBLY	EA	1
PEDESTAL POLE & SQUARE BASE	EA	5
PULL BOX, PB-2	EA	9
PULL BOX, PB-3	EA	3
LOOP SAW CUT	LF	457
CONDUIT, 1"	LF	38
CONDUIT, 2"	LF	192
R560-5 W/ POST	EA	1
R-SPEC *1, LEFT TURN YIELD ON FLASHING YELLOW ARROW SIGN	EA	1
R1-2, YIELD SIGN W/ POST	EA	1
MISCELLANEOUS MATERIALS NEEDED TO COMPLETE INSTALLATION	LUMP	LUMP

INTERSECTION #3
SR 3 (DALTON BYPASS)
@
WILLOWDALE RD

Stantec

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: Program Delivery
SIGNAL PLANS
SIGNAL QUANTITIES

DRAWING No. 27-010