

RESOURCE: NAME AND TYPE	LOCATION:		SIDE	CONSTRUCTION ACTIVITY:	PERMITTED ACTIVITY:	CONTROLLING CRITERIA	SPECIAL PROVISIONS	COMMENTS: INCLUDING ANY PERMIT EXPIRATION DATES
	BEGINNING STA.	ENDING STA.						
ENVIRONMENTALLY SENSITIVE AREA: RIVERFRONT PARK/ RAY CHARLES PLAZA - PARK	12+65	16+64	BOTH	GENERAL ACTIVITIES ASSOCIATED WITH ROADWAY CONSTRUCTION INCLUDING GRADING, INSTALLATION OF DRAINAGE STRUCTURES, ROADWAY PAVING AND MEDIAN CONSTRUCTION AND CONSTRUCTION OF DRIVEWAYS AND DEMOLITION OF OLD BRIDGE AND CONSTRUCTION OF NEW BRIDGE	ACTIVITIES WITHIN EXISTING RIGHT-OF-WAY	SECTION 4(f)	N/A	SEE PLAN SHEET 13-01 & 13-02 FOR PARK LOCATION. USERS OF THE PARK AREA ON THE WEST SIDE OF THE FLINT RIVER SHALL BE NOTIFIED AT LEAST 30 DAYS BEFORE SIDEWALK CLOSURE. CITY OF ALBANY WILL HANDLE SIGNAGE.
ENVIRONMENTALLY SENSITIVE AREA: 25' STREAM BUFFER STREAM #1	15+85	19+80	BOTH	DEMOLITION OF OLD BRIDGE AND CONSTRUCTION OF NEW BRIDGE	ACTIVITIES WITHIN 100 FT OF THE PROPOSED BRIDGE ARE EXEMPT.	NPDES	N/A	SEE PLAN SHEET 13-01 TO 13-03 FOR 25' STREAM BUFFER AREA DELINEATION WORK BEYOND 100 FT OF THE PROPOSED BRIDGE WILL REQUIRE A BUFFER VARIANCE OR WRITTEN PERMISSION FROM EPD PRIOR TO COMMENCEMENT OF THE ACTIVITY.
STREAM #1 (FLINT RIVER)	16+12	19+50	BOTH	DEMOLITION OF OLD BRIDGE AND CONSTRUCTION OF NEW BRIDGE	REFER TO NWP 33 PRECONSTRUCTION NOTIFICATION	SECTION 404 OF CWA NWP 33	N/A	ANY ADDITIONAL FILL OTHER THAN WHAT IS SHOWN ON PLANS WILL REQUIRE A PERMIT MODIFICATION OR A NEW PERMIT PRIOR TO COMMENCEMENT OF THE ACTIVITY. PERMIT NOT AUTHORIZED YET
ENVIRONMENTALLY SENSITIVE AREA: RESOURCE 1	19+25	22+50	BOTH	DEMOLITION OF OLD BRIDGE AND CONSTRUCTION OF NEW BRIDGE	NONE	NEPA DOCUMENT	N/A	SEE PLAN SHEET 13-02 AND 13-03 FOR ESA AREA DELINEATION CONTRACTOR SHALL DIRECT QUESTIONS TO THE ENGINEER, AND THE ENGINEER SHALL CONTACT ENVIRONMENTAL SERVICES IF NECESSARY FOR RESOLUTION.
MIGRATORY BIRDS (BARN SWALLOWS)	14+55	22+39	BOTH	DEMOLITION OF OLD BRIDGE AND CONSTRUCTION OF NEW BRIDGE	REFER TO SPECIAL PROVISION 107.23 G	MIGRATORY BIRD TREATY ACT	107.23	THE OFFICE OF ENVIRONMENTAL SERVICES SHALL BE CONTACTED PRIOR TO INSTALLATION OF EXCLUSIONARY DEVICES. CONTRACTOR SHALL DIRECT QUESTIONS TO THE ENGINEER, AND THE ENGINEER SHALL CONTACT ENVIRONMENTAL SERVICES IF NECESSARY FOR RESOLUTION.
PROTECTED SPECIES (PURPLE BANK CLIMBER MUSSEL) (FAT THREE-RIDGE MUSSEL) (SHINY-RAYED POCKETBOOK MUSSEL) (GULF MOCCASINSHELL MUSSEL) (OVAL PIGTOE MUSSEL)	16+12	19+47	BOTH	DEMOLITION OF OLD BRIDGE AND CONSTRUCTION OF NEW BRIDGE	REFER TO SPECIAL PROVISION 107.23 G	ENDANGERED SPECIES ACT	107.23	SEE PLAN SHEET 13-02 FOR ESA AREA DELINEATION CONTRACTOR SHALL DIRECT QUESTIONS TO THE ENGINEER, AND THE ENGINEER SHALL CONTACT ENVIRONMENTAL SERVICES IF NECESSARY FOR RESOLUTION.
ELIGIBLE HISTORIC RESOURCE - BROAD AVENUE BRIDGE	-	-	-	DEMOLITION OF OLD BRIDGE	DEMOLITION OF OLD BRIDGE REFER TO SPECIAL PROVISION 107.23 I & J	SECTION 106 AND SECTION 4(f)	105.03 107.23	SEE PLAN SHEET 13-01 TO 13-03 CONTRACTOR SHALL DIRECT QUESTIONS TO THE ENGINEER, AND THE ENGINEER SHALL CONTACT ENVIRONMENTAL SERVICES IF NECESSARY FOR RESOLUTION.