VOID

STRAIN POLE, TP III	
TOTAL	2 EACH

SUMMARY OF STRIPING QUANTITIES

	THERMOPLASTIC PAVEMENT MARKING													
	SOLID STRIPE					SKIP STRIPE	HATCHING					RAISED PVMNT MARKERS		
	WHITE	WHITE	WHITE	WHITE	YELLOW	WHITE	WHITE	YELLOW	ARROW	ARROW	WORD			
	5 INCH	8 INCH	10 INCH	24 INCH	5 INCH	5 INCH			TYPE 1	TYPE 2	TYPE 1	TYPE 1	TYPE 3	TYPE 10
LOCATION	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	GLF	SQ. YDS.	SQ. YDS.	EACH	EACH	EACH	EACH	EACH	EACH
PROJECT TOTAL:	5230	0	0	14	4000	3051	0	1568	0	15	10	91	84	8

SUMMARY OF SIGNING QUANTITIES

		HIGHWAY SIGNS						POSTS		
		TYPE 3 SHEETING			TYPE 9 SHEETING					
		TYPE 1 (0.080 ±.005 IN.)			TYPE 1 (0.080 ±.005 IN.)			TYPE 7 (2" 14GA)		
								LENGTH		
LOCATION	CODE	SIZE	QTY	SQ. FT.	SIZE	QTY	SQ. FT.	LIN. FT.	QTY	LIN. FT.
SR 16										
STA. 26+05 LT.	M4-5	24"x12"	1	2.0				14.3	1	14.3
	M1-124	24"x24"	1	2.0						
	M5-1L	21"x15"	1	2.19						
STA. 26+28 RT.	M3-2	24"x12"	1	2.0				13.0	1	13.0
	M1-5	24"x24"	1	4.0						
STA. 27+36 LT.	M2-1	21"x15"	1	2.19				13.3	1	13.3
	M1-4	24"x24"	1	4.0						
	M4-1A	24"x12"	1	2.0						
	M1-4	24"x24"	1	4.0						
STA. 29+82 RT.	W3-1				36"X36"	1	9.0	15.0	2	30.0
	W16-8	54"X24"	1	9.0						
STA. 32+94 RT.	R3-7	36"X36"	1	9.0				13.0	1	13.0
STA. 37+03 RT.	D3-1	60"x12"	1	5.0				14.0	2	28.0
	R1-1				36"X36"	1	9.0			
STA. 37+76 RT.	D3-1	30"x12"	1	2.5				14.0	1	14.0
	R1-1				36"X36"	1	9.0			
STA. 38+10 LT.	D3-1	60"X12"	1	5.0				14.0	2	28.0
	R1-1				36"X36"	1	9.0			
STA. 38+76 LT.	R1-1a (SPECIAL)	30"x36"	1	7.5				13.0	1	13.0
STA. 43+83 LT.	W3-1				36"X36"	1	9.0	15.0	2	30.0
	W16-8	54"x24"	1	9.0						
SUBTOTAL				71.4			45.0			196.6

SUMMARY OF OVERHEAD SIGNING QUANTITIES

		TYPE 9 SHEETING		
		TYPE 1 (0.080 ±.005 IN.)		
LOCATION	CODE	SIZE	QTY	SQ. FT.
SR 16				
STA. 25+90.00	R3-5L	30"X36"	1	7.5
	R3-5L	30"X36"	1	7.5
	R3-5A	30"X36"	1	7.5
	R3-5R	30"X36"	1	7.5
SUBTOTAL				30.0

DRY SWALE EDGE DRAINS

TOTAL	1330 LF

PERMANENT EROSION CONTROL

ITEM	UNIT	TOTAL
PERMANENT GRASSING	AC	5
AGRICULTURAL LIME	TN	15
FERTILIZER MIXED GRADE	TN	5
FERTILIZER NITROGEN CONTENT	LB	250
STN DUMPED RIP RAP, TP 3, 18 IN	SY	56
PLASTIC FILTER FABRIC	SY	56
EROSION CONTROL MATS, SLOPES	SY	3150
EROSION CONTROL CHECK DAM, RIP RAP	EA	17

TEMPORARY EROSION CONTROL

ITEM	UNIT	TOTAL
TEMPORARY GRASSING	AC	6
MULCH	TN	98
CONSTRUCTION EXIT	EA	4
CONSTRUCT AND REMOVE SILT CONTROL GATE, TP 3	EA	5
CONSTRUCT AND REMOVE TEMPORARY PIPE SLOPE DRAIN	LF	430
CONSTRUCT AND REMOVE RIP RAP CHECK DAMS, STONE PLAIN RIP RAP/SAND BAGS	EA	49
CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EA	2
CONSTRUCT AND REMOVE STONE FILTER RING	EA	1
MAINTENANCE OF TEMPORARY SILT FENCE, TP C	LF	2373
MAINTENANCE OF CHECK DAMS - ALL TYPES	LF	660
MAINTENANCE OF SILT CONTROL GATE, TP 3	EA	5
MAINTENANCE OF CONSTRUCTION EXIT	EA	4
MAINTENANCE OF INLET SEDIMENT TRAP	EA	2
MAINTENANCE OF STONE FILTER RING	EA	1
WATER QUALITY MONITORING AND SAMPLING	EA	2
WATER QUALITY INSPECTIONS	MO	24
TEMPORARY SILT FENCE, TYPE C	LF	4745

CHA
270 Peachtree St. NW, Suite 1500 • Atlanta, GA 30303-1283
Main: (678) 954-5000 • www.chacompanies.com

REVISION DATES
3/28/14
4/07/14

GEORGIA
DEPARTMENT OF TRANSPORTATION

SUMMARY QUANTITIES
(PI 0006877)

SE / NEWNAN BYPASS FROM
S.R. 16 TO TURKEY CREEK ROAD

DRAWING No. 6-002

GPLN