GRADING COMPLETE CSMSL-0007-00(956)	
1	LUMP SUM

TRAFFIC CONTROL CSMSL-0007-00(956)	
1	LUMP SUM

AGGREGATE SURFACE COURSE	
100	TN

4" CONCRETE SIDEWALK		
	UNIT	QUANTITY
PARKING LOT	SY	803
INTERSECTION	SY	95
TOTAL	SY	898

8" CONCRETE SIDEWALK		
	UNIT	QUANTITY
PARKING LOT – RAMPS	SY	35
INTERSECTION – LANDINGS	SY	3
TOTAL	SY	38

CURB & GUTTER		
ITEMS	UNIT	QUANTITY
CONCRETE CURB & GUTTER, 6" X 24", TP 2	LF	7300
CONCRETE CURB & GUTTER, 6" X 30", TP 2	LF	60

PAVING		
ITEMS	UNIT	QUANTITY
FOUND BKFILL MATL, TP 2, # 57 STONE (UNDER PERVIOUS PAVEMENT)	CY	960
GR AGGR BASE CRS, INCL MATL	TN	12400
PERVIOUS CONCRETE, 6 IN THK	SY	2870
RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	820
RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	2630
RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TP 2, BLEND 1, INCL BITUM MATL & H LIME	TN	1620
RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	5
BITUMINOUS TACK COAT	GA	1580
PLASTIC FILTER FABRIC, NON-WOVEN (FOR PERVIOUS PAVEMENT AND UNDERGROUND STORAGE SYSTEMS)	SY	4280
SAWED JOINTS IN EXISTING PAVEMENTS – PCC	LF	260

TRAFFIC SIGNAL INSTALLATION CSMSL-0007-00(956)		
ITEMS	UNIT	QTY
TRAFFIC SIGNAL INSTALLATION	LUMP SUM	1
DIRECTIONAL BORE – 5 IN	LF	190
CONCRETE STRAIN POLE, TP IV	EA	4
HIGHWAY SIGNS, TP 2 MATL – REFL SHEETING, TP 9	SF	24
PULL BOX, PB-4S	EA	1
CONDUIT, NONMETAL, TP 3, 2 IN	LF	370
2070 MOUNT SPREAD SPECTRUM WIRELESS TRANSCEIVER WITH RS 232 CONNECTION	EA	1
DIRECTIONAL RADIO ANTENNA AND CONNECTING CABLE	EA	1

UNDERGROUND STONE ENCASED STORAGE SYSTEMS	
1	LUMP SUM

RIGHT-OF-WAY		
ITEMS	UNIT	QUANTITY
RIGHT-OF-WAY MARKERS	EA	11

CLASS A CONCRETE		
ITEMS	UNIT	QUANTITY
HEADER CURB AT PERVIOUS PAVEMENT AREAS	CY	45

CLASS B CONCRETE		
ITEMS	UNIT	QUANTITY
BASE OF PAVEMENT WIDENING	CY	11

TEMPORARY EROSION CONTROL		
ITEMS	UNIT	QUANTITY
CONSTRUCTION EXIT	EA	1
CONSTRUCT AND REMOVE TEMPORARY PIPE SLOPE DRAIN	LF	250
CONSTRUCT AND REMOVE SEDIMENT BASIN, TP 1	EA	1
CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EA	16
MAINTENANCE OF TEMPORARY SILT FENCE, TYPE C	LF	2122
MAINTENANCE OF TEMPORARY SEDIMENT BASIN	EA	1
MAINTENANCE OF CONSTRUCTION EXIT	EA	1
MAINTENANCE OF INLET SEDIMENT TRAP	EA	16
MULCH	TN	100
TEMPORARY GRASSING	AC	9
WATER QUALITY MONITORING AND SAMPLING	EA	1
WATER QUALITY INSPECTIONS	MO	12
TEMPORARY SILT FENCE, TYPE C	LF	4243

PERMANENT EROSION CONTROL		
ITEMS	UNIT	QUANTITY
EROSION CONTROL MATS, SLOPES	SY	8151
AGRICULTURAL LIME	TN	27
FERTILIZER MIXED GRADE	TN	9
FERTILIZER NITROGEN CONTENT	LB	450
LIQUID LIME	GL	23
SOD	SY	6381

WATER LINE		
ITEMS	UNIT	QUANTITY
WATER SERVICE LINE, 3/4 IN	LF	450

FENCE		
ITEMS	UNIT	QUANTITY
CHAIN LINK, ZC COAT, 6 FT, 9 GA	LF	2160
ORNAMENTAL FENCE	LF	152

HARDSCAPE ITEMS		
ITEMS	UNIT	QUANTITY
PRECAST BUMPER BLOCK	EA	14
BUS PAVILLION – INCLUDES TWO STRUCTURES	LS	1
FARE SYSTEMS SHELTER BUILDING	LS	1

SUMMARY OF SIGN QUANTITIES

VOID

LOCATION	CODE	SIGNS – TYPE IX REFLECTIVE SHEETING (SQUARE FEET) TYPE 1 (.08 IN) SIZE IN×IN	FT2	QUANTITY	TOTAL FT2	POSTS (LINEAR FEET) TYPE 7 LENGTH EACH	QUANTITY	TOTAL FT
PARKING LOT	R1-1	18"X18"	2.25	3	6.75	15	3	45
PARKING LOT	R1-1	36"X36"	9	1	9	15	1	15
PARKING LOT	R5-1	18"X18"	2.25	2	4.5	15	2	30
PARKING LOT	R3-10A	24"X30"	5	2	10	15	2	30
PARKING LOT	R5-2A	24"X24"	4	1	4	15	1	15
PARKING LOT	R7-8-GA	12"X18"	1.5	14	21	15	14	210
PARKING LOT	R7-8P5	12"X9"	.75	14	1.5		0	0
INTERSECTION	R560-5	18"X24"	3	4	12	15	4	60
INTERSECTION	R5-1	30"X30"	6.25	2	12.5	15	2	30
INTERSECTION	R1-2	36"	9	1	9	15	1	15
INTERSECTION	R5-1a	36"X24"	6	2	12	15	2	30
TOTAL					102.25			480
		SIGNS – TYPE III REFLECTIVE SHEETING (SQUARE FEET)						
INTERSECTION	R6-1R	36"X12"	3	2	6	15	3	45
INTERSECTION	R6-1L	36"X12"	3	2	6			
INTERSECTION	R4-7	24"X30"	5	2	10	15	2	30
TOTAL					22			75
		TYPE III BARRICADE "DEAD END ROADWAY" STRIPE ORIENTATION				TYPE III BARRICADE POSTS		
		SIZE LF		QUANTITY	TOTAL LF	TYPE	QUANTITY	TOTAL POSTS
ROADWAY		10		4	40	B	3	12

COMMUNICATION CONDUITS		
ITEMS	UNIT	QUANTITY
CONDUIT, NONMETL, TP 2, 2 IN	LF	2850
CONDUIT, NONMETL, TP 2, 4 IN	LF	50
CONDUIT, ENCASED, TP 1, 4 IN 2-WAY	LF	620
ELECTRICAL JUNCTION BOX, REINFORCED PLASTIC MORTAR	EA	29

LIGHTING		
ITEMS	UNIT	QUANTITY
LIGHTING STD, 30 FT MH, POST TOP	EA	22
LUMINAIRE, TP3, 400W, METAL HALIDE	EA	19
LUMINAIRE, TP4, 400W, METAL HALIDE	EA	18
CABLE, TP XHHW, AWG NO 10	LF	15520
CABLE, TP XHHW, AWG NO 8	LF	5740
CABLE, TP XHHW, AWG NO 6	LF	3380
CABLE, TP XHHW, AWG NO 4/0	LF	1500
CONDUIT, RIGID, 4 IN	LF	500
CONDUIT, NONMETL, TP 2, 1 IN	LF	1490
CONDUIT, NONMETL, TP 2, 1 1/2 IN	LF	1460
CONDUIT, NONMETL, TP 2, 4 IN	LF	500
MAIN SERVICE PICK UP POINT	LS	1
ELECTRICAL JUNCTION BOX, REINFORCED PLASTIC MORTAR	EA	30

URS
400 Northpark Town Center
1000 Abernathy Road N.E., Suite 900
Atlanta, Georgia 30328
Tel: (678) 808-8800, Fax: (678) 808-8400

REVISIONS

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE OF INNOVATIVE PROGRAM DELIVERY

SUMMARY OF QUANTITIES

NEWNAN SR 34 AND HOLLZ PKWY
PARK AND RIDE LOT

6-01
DRAWING No.