COUNTY	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
COWETA	CSMSL-0007-00(956)	8	106

STORM DRAIN QUANTITIES

STRUCTURE NUMBER	PIPES: SEE ALLOWABLE PIPE MATERIALS CHART ON GENERAL NOTES SHEET 15 IN	18 IN	24 IN	30 IN	36 IN	42 IN	48 IN	HEIGHT OF FILL FT	FLARED END SECTION GA STD 1120 EACH: 15 IN	18 IN	24 IN	30 IN	36 IN	42 IN	SAFETY END SECTION 4:1 SLOPE EA	SIZE IN
A1													1			
A2					17			10.53								
A4			10					8.12								
A5			46					6.48								
A6		283						5.67								
A8.1		124						5.09								
A2.1		58						5.80								
A3.1					102			9.38								
A4.B		118						4.83								
A4.A			62					7.65								
A7.1		68						8.15								
B1											1					
B2			16					9.84								
B3		29						6.98								
B4		28						4.5								
C1										1						
C2		18						8.6								
D1								5.72								
D2		118						5.67								
D3		67						4.83								
TOTAL		911	134		109					1	1		1			
1 FT – 10 FT		911	134													
10 FT – 15 FT					109											
15 FT – 20 FT																
20 FT – 25 FT																

STRUCTURE NUMBER	TOE WALL-GA STD 1120 CLASS "A" CONCRETE CY	HEADWALL STD 1125 INLET EA	HEADWALL STD 1125 OUTLET EA	CLASS "A" CONCRETE (HEADWALL-GA STD 1125) CY	CATCH BASIN, GP 1 EA	CATCH BASIN, GP 1 ADDITIONAL DEPTH LF	CATCH BASIN, GP 2 EA	CATCH BASIN, GP 2 ADDITIONAL DEPTH LF	CAPPING MINOR STRUCTURE (AS REQ'D) EA	ADJUST CATCH BASIN TO GRADE EA	RECONST. MINOR STR. EA	ADJUST MANHOLE TO GRADE EA	ADJUST SOTRM SEWER MANHOLE TO GRADE EA	CONCRETE COLLAR GA STD 9031-U EA	FOUNDATION BACKFILL MATERIAL TYPE II CY	STORM SEWER MANHOLE, TP1 EA	STORM SEWER MANHOLE, TP 1 ADDITIONAL DEPTH, CL 1 LF	STORM SEWER MANHOLE, TP 1 ADDITIONAL DEPTH, CL 2 LF	STONE DUMPED RIP-RAP, TYPE 3, 18 IN THICK SY	PLASTIC FILTER FABRIC SY	IMPERMEABLE MEMBRANE FOR SUBGRADES, BASINS, DITCHES, AND CANALS SY	REMARKS
A1															1				52	52		
A2															1	1	4.53					
A4															1	1	2.12					
A5					1	0.48									1							
A6					1										1							
A8.1					1										1							
A2.1					1										1							
A3.1					1	3.38									1							
A4.B					1										1							
A4.A					1	1.65									1							
A7.1					1	2.15									1							
B1															1				37	37		
B2					1	3.84									1						37	
B3					1	0.98									1							
B4					1										1							
C1															1				37	37		
C2					1	2.6									1						37	
D1															1	1						
D2					1										1							
D3					1										1							
TOTAL					14	15.08									22	3	6.65		130	130	74	

SUMMARY OF PAVEMENT MARKING QUANTITES

LOCATION	STRIPE: SOLID TRAF STRIPE, 5 IN, WHITE LF	SOLID TRAF STRIPE, 5 IN, YELLOW LF	SOLID TRAF STRIPE, 8 IN WHITE LF	SOLID TRAF STRIPE, 24 IN WHITE LF	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE LF	THERMOPLASTIC SOLID TRAF STRIPE, 8 IN, WHITE LF	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE LF	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE GLF	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW LF	TRAF. STRIPING, YELLOW SY	TRAF. STRIPING, WHITE SY	REMOVE EXISTING TRAFFIC STRIPE, ALL KINDS & TYPES SY	REMOVEEXISTING SOLID TRAFFIC STRIPE, 24 IN, THERMOPLASTIC LF	REMOVE EXISTING SOLID TRAFFIC MARKINGS EA	ARROWS: PAVEMENT MARKING, ARROW TP 1 EA	PAVEMENT MARKING, ARROW TP 2 EA	THERMOPLASTIC PVMT MARKING, ARROW TP 2 EA	THERMOPLASTIC PVMT MARKING, ARROW TP 4 EA	WORDS: PAVEMENT MARKING, WORD TP 1 EA	PAVEMENT MARKING, WORD TP 6 EA	SYMBOLS: HANDICAP SYMBOL EA
PARKING LOT	15700	60	300	175						405	87				2	5			3	1	14
INTERSECTION					125	1690	135	145	1000			55	24	4			4	5			

URS
400 Northpark Town Center
1000 Abernathy Road N.E., Suite 900
Atlanta, Georgia 30328
Tel: (678) 808-8800, Fax: (678) 808-8400

REVISIONS		
09/02/2010		
03/22/2011		

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE OF INNOVATIVE PROGRAM DELIVERY

SUMMARY OF QUANTITIES

NEWNAN SR 34 AND HOLLZ PKWY
PARK AND RIDE LOT

6-02
DRAWING No.