STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	CSNHS-0008-00(232)	613	839

LOCATION	NO. OF LOC.	MARK	LENGTH FT. IN.	NO. BARS REQ'D.	TYPE	A	G	B FT. IN.	C FT. IN.	D FT. IN.	E FT. IN.	F FT. IN.	H FT. IN.	J FT. IN.	K FT. IN.	N	θ
END BENT 1	1																
		410	6- 9	44	32	5	5	2- 8	1- 8	1- 8							
		411	9- 5	90	25	4	4	2- 8	1- 8								
		412	5- 0	20	1												
		413	4- 8	60	2			2- 8	1- 0	1- 0							
		510	8- 8	32	1												
		511	6- 0	40	1												
		610	6- 4	6	1												
		1010A	55-10	2	3			52-10	3- 0								
		1010B	51- 8	4	3			48- 8	3- 0								
		1010C	47- 6	2	3			44- 6	3- 0								
BENT 2 LT	2	BENT 3 LEFT SAME															
		420	7- 0	24	32	5	5	2- 11	1- 8	1- 8							
		421	9- 11	44	25	4	4	2- 11	1- 8								
		422	5- 0	10	1												
		423	4- 11	30	2			2- 11	1- 0	1- 0							
		1020A	45- 4	4	1												
BENT 2 RT	2	BENT 3 RIGHT SAME															
		420	7- 0	20	32	5	5	2- 11	1- 8	1- 8							
		421	9- 11	36	25	4	4	2- 11	1- 8								
		422	5- 0	10	1												
		423	4- 11	30	2			2- 11	1- 0	1- 0							
		1020B	37- 0	4	1												
BENT 4 LT	1																
		440	12- 2	23	33			1- 6	1- 8 3/8								
		441	5- 0	20	1												
		442A	3- 7	30	2			1- 7	1- 0	1- 0							
		442B	5- 8	30	2			3- 8	1- 0	1- 0							
		443A	47- 2	12	1												
		540	15- 8	57	25	4	4	3- 8	3- 8								
		541	7- 7	49	2			1- 7	3- 0	3- 0							
		542	47- 2	2	1												
		1040	47- 2	7	1												
		1041	50- 0	6	10	1	1	47- 2									
		1042	23- 3	10	9	1		21-10									
		1140A	14- 4	12	1												
		1140B	13- 3	12	1												
BENT 4 RT	1																
		440	12- 2	19	33			1- 6	1- 8 3/8								
		441	5- 0	20	1												
		442A	3- 7	30	2			1- 7	1- 0	1- 0							
		442B	5- 8	30	2			3- 8	1- 0	1- 0							
		443B	37-11	12	1												
		540	15- 8	48	25	4	4	3- 8	3- 8								
		541	7- 7	39	2			1- 7	3- 0	3- 0							
		543	37-11	2	1												
		1043	37-11	6	1												
		1044	40- 9	9	10	1	1	37-11									
		1140C	12- 2	12	1												
		1140D	11- 0	12	1												
BENT 5 LT	1																
		440	12- 2	21	33			1- 6	1- 8 3/8								
		443A	47- 2	12	1												
		540	15- 8	57	25	4	4	3- 8	3- 8								
		541	7- 7	49	2			1- 7	3- 0	3- 0							
		542	47- 2	2	1												
		1040	47- 2	7	1												
		1041	50- 0	6	10	1	1	47- 2									
		1042	23- 3	10	9	1		21-10									
		1140A	13- 1	12	1												
		1140B	12- 7	12	1												

LOCATION	NO. OF LOC.	MARK	LENGTH FT. IN.	NO. BARS REQ'D.	TYPE	A	G	B FT. IN.	C FT. IN.	D FT. IN.	E FT. IN.	F FT. IN.	H FT. IN.	J FT. IN.	K FT. IN.	N	θ
BENT 5 RT	1																
		440	12- 2	19	33			1- 6	1- 8 3/8								
		443B	37-11	12	1												
		540	15- 8	48	25	4	4	3- 8	3- 8								
		541	7- 7	39	2			1- 7	3- 0	3- 0							
		543	37-11	2	1												
		1043	37-11	6	1												
		1044	40- 9	9	10	1	1	37-11									
		1140C	12- 1	12	1												
		1140D	11- 5	12	1												
BENT 6 LT	1																
		420	7- 0	24	32	5	5	2- 11	1- 8	1- 8							
		421	9- 11	44	25	4	4	2- 11	1- 8								
		1020A	45- 4	4	1												
BENT 6 RT	1																
		420	7- 0	20	32	5	5	2- 11	1- 8	1- 8							
		421	9- 11	36	25	4	4	2- 11	1- 8								
		1020B	37- 0	4	1												
END BENT 7	1																
		470	6- 9	44	32	5	5	2- 8	1- 8	1- 8							
		471	9- 5	90	25	4	4	2- 8	1- 8								
		570	8- 8	28	1												
		571	5- 11	40	1												
		670	6- 4	6	1												
		1070A	47- 6	2	3			44- 6	3- 0								
		1070B	51- 8	4	3			48- 8	3- 0								
		1070C	55-10	2	3			52-10	3- 0								

AS-BUILT

APPROVED FOR CONSTRUCTION 10/4/07

BRIDGE NO. 2

ARCADIS
2849 PACES FERRY ROAD, SUITE 400
ATLANTA, GEORGIA 30339
TEL: 770/431-8666 FAX: 770/435-2666

GEORGIA
DEPARTMENT OF TRANSPORTATION
PRECONSTRUCTION DIVISION-OFFICE OF BRIDGE DESIGN

SUBSTRUCTURE
REINFORCEMENT SCHEDULE
KIA PARKWAY OVER LONG CANE CK.

TROUP COUNTY CSNHS-0008-00(232)

SCALE: NO SCALE JULY 2007

DESIGNED	RHC	CHECKED	JPT	REVIEWED	WMD
DRAWN	MLF	DESIGN GROUP	SWW	APPROVED	PVL

REVISIONS | BY | DATE

BRIDGE SHEET 20 OF 21

PLAN DATE: 01-25-08

Filename: g:\tro\63732-kia\bridge\final\bridge 2\63732b2-rs.dgn Date: 1/24/2008 Time: 8:28:00 AM User Name: MLF