

GENERAL NOTES

1. THE CONTRACTOR SHALL LOCATE ALL UTILITIES BEFORE DIGGING TO ELIMINATE ANY CONFLICTS. TO OBTAIN HIGHWAY LIGHTING PLANS, THE CONTRACTOR SHALL CONTACT THE DEPARTMENT AT (404) 656-5396. FOR GDOT ATMS / ITS FACILITIES THAT MAY BE IMPACTED, THE CONTRACTOR SHALL CONTACT THE GDOT ITS MANAGER AT (404) 624-7819.
2. THE CONTRACTOR SHALL CONTACT THE ITS MANAGER AT (404) 624-7819 TO LOCATE GDOT ITS INFRASTRUCTURE AT LEAST 48 HOURS IN ADVANCE.
3. WITHIN 24 HOURS, THE CONTRACTOR SHALL REPAIR ANY EXISTING CONDUIT, CABLE, OR PIPE THAT IS DAMAGED BY ANY WORK PERFORMED AS PART OF THIS PROJECT AT NO ADDITIONAL COST TO THE DEPARTMENT.
4. THE CONTRACTOR SHALL REPLACE IN LIKE KIND AND SIZE, AT NO ADDITIONAL COST TO THE DEPARTMENT, ANY PAVEMENT MARKINGS, BARRIER WALL, FENCE, DITCH PAVING, CURBING, SIDEWALK, GUTTER, SLOPE PAVEMENT, SIGNS, GUARDRAIL, LANDSCAPING (IN ACCORDANCE WITH GEORGIA SPECIFICATIONS SECTION 702), GRASSING (IN ACCORDANCE WITH GEORGIA SPECIFICATIONS SECTION 700), UTILITY SERVICE LINES, STORM DRAIN PIPES, RUMBLE STRIPS, ROADWAY, AND ANY RETAINING WALLS THAT ARE DAMAGED OR DESTROYED BY ANY WORK PERFORMED AS PART OF THIS PROJECT. THE CONTRACTOR WILL NOT BE REQUIRED TO MAINTAIN LANDSCAPING AS SPECIFIED IN SECTION 702.3.07 OF THE GEORGIA SPECIFICATIONS.
5. FIBERGLASS OR RIGID STEEL CONDUIT SHALL BE USED AT ALL EXPOSED CONDUIT LOCATIONS.
6. THE CONTRACTOR SHALL REMOVE PAVEMENT BY SAW CUT TO PROVIDE A NEAT LINE. WHERE CONDUIT IS INSTALLED, THE CONTRACTOR SHALL INLAY TO MATCH EXISTING SURFACE TYPE AFTER CONDUIT IS INSTALLED. PAVEMENT REMOVAL AND PAVEMENT INLAY SHALL BE INCLUDED IN THE BID PRICE FOR CONDUIT DUCT BANK OR CONDUIT.
7. ANY REQUIRED EROSION CONTROL DEVICES WILL NOT BE MEASURED SEPARATELY AND SHALL BE INCLUDED IN THE COST OF THE OVERALL BID.
8. THE ELECTRIC POWER SERVICE ASSEMBLY POINTS SHOWN ON THE PLANS ARE FOR THE CONTRACTOR'S USE IN DETERMINING POWER ROUTING TO EACH DEVICE. THE CONTRACTOR SHALL COORDINATE WITH THE LOCAL ELECTRICAL UTILITY COMPANIES TO PROVIDE POWER TO THE SERVICE RISER POINTS. POWER SERVICE SHALL BE LOCATED AS SHOWN ON PLANS OR AT THE BACK OF THE RIGHT-OF-WAY LINE, IF A NEW LOCATION IS PROPOSED.
9. ALL PROPOSED STRAIN POLES SHALL BE INSTALLED A MINIMUM OF 6 FEET BEHIND EXISTING OR PROPOSED GUARDRAIL WHERE SHOWN ON THE PLANS.

10. MINOR TREE TRIMMING AND REMOVAL MAY BE REQUIRED. HOWEVER, LOCATIONS MAY BE REQUIRED AS DIRECTED BY THE ENGINEER TO OBTAIN CAMERA VISIBILITY OF 2/3 OF A MILE AND TO MEET MINIMUM SIGHT DISTANCES FOR TRAFFIC SIGNALS AS PER MUTCD. PAYMENT FOR THIS WORK SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR THIS PROJECT.
11. THE EXISTING VMS SIGN AT STATION 952+00 TO BE REMOVED AS PART OF THIS PROJECT SHALL BE RETURNED TO THE GDOT. TRAFFIC SIGNALS AND ELECTRICAL FACILITIES BUILDING AT 935 EAST CONFEDERATE AVENUE, BUILDING 5, ATLANTA, GA 30316 AT NO ADDITIONAL COST TO THE DEPARTMENT. THE CONTRACTOR SHALL CALL THE ASSISTANT STATE TRAFFIC SAFETY AND DESIGN ENGINEER AT (404-635-8129) AT LEAST 72 HOURS IN ADVANCE TO ARRANGE DELIVERY OF THESE COMPONENTS.
12. CONDUIT UNDER BRIDGES SHALL BE INSTALLED BY DIRECTIONAL BORING, UNLESS NOTED OTHERWISE ON THE PLANS.
13. THE CONTRACTOR SHALL DIRECT BURY SERVICE WIRE TO THE DEVICES. THE COST OF THE SERVICE WIRE, AND ANY OTHER MATERIALS REQUIRED TO PROVIDE POWER SERVICE TO THE DEVICES SHALL BE INCLUDED IN THE BID PRICE FOR ELECTRICAL POWER SERVICE ASSEMBLY, AERIAL SERVICE POINT.
14. THE CONTRACTOR SHALL SALVAGE EXISTING CAMERAS AND ASSOCIATED EQUIPMENT FOR USE ON NEW POLES. IF EXISTING EQUIPMENT IS DAMAGED, THE CONTRACTOR SHALL REPLACE IT WITH IN KIND EQUIPMENT.
15. ALL EXISTING NAV NUMBERS SHALL BE RELOCATED TO NEW POLES. CONTRACTOR TO UPGRADE NAV NUMBERS AS NECESSARY BASED ON NEW POLE LOCATIONS.
16. ITS SYSTEM WITHIN PROJECT LIMITS SHALL NOT BE OFFLINE FOR MORE THAN 30 CONSECUTIVE DAYS.
17. THE CONTRACTOR SHALL CONFIRM EACH POWER SERVICE POINT WITH THE POWER COMPANY PRIOR TO INSTALLATION.
18. A NOTICE OF INTENT IS REQUIRED FOR THIS PROJECT

UTILITY OWNERS

WATER SEWER: HENRY COUNTY WATER AND SEWERAGE AUTHORITY DOUG BAILEY, PLAN REVIEW COORDINATOR 1695 HIGHWAY 20 WEST MCDONOUGH, GA 30253 770 914 3688	WATER / SEWER CLAYTON COUNTY WATER AUTHORITY DON CONNER, FIELD ENGINEER 1600 BATTLE CREEK ROAD MORROW, GA 30260 678 873 4981	GAS: ATLANTA GAS LIGHT COMPANY DEMETRIUS WARD, GIS / MAPPING ENGINEER P. O. BOX 4569 ATLANTA, GA 30302 404 584 4338
GAS: ATLANTA GAS LIGHT COMPANY JEFF HARVILLE, PROJECT COORDINATOR 508 GEORGIA HIGHWAY 138, SW RIVERDALE, GA 30274 770 909 5772	GAS: ATLANTA GAS LIGHT COMPANY FLETCHER HARRIS, DAMAGE PREVENTION SPECIALIST 576 NORTHSIDE DRIVE ATLANTA, GA 30318 404 230 6529	GAS: ATLANTA GAS LIGHT COMPANY EDDIE ARRINGTON, OPERATIONS FOREMAN 508 GEORGIA HIGHWAY 138, SW RIVERDALE, GA 30274 770 909 5847
POWER: GEORGIA POWER COMPANY - TRANSMISSION BRYAN PRINCE, FIELD ENGINEER 241 RALPH MCGILL BOULEVARD NE ATLANTA, GA 30308 770 506 3882	POWER: GEORGIA POWER COMPANY - DISTRIBUTION BEN GAY, FIELD ENGINEER 241 RALPH MCGILL BOULEVARD NE ATLANTA, GA 30308 770 603 5441	POWER: GEORGIA POWER COMPANY - DISTRIBUTION RANDY JONES BIN 20025, 241 RALPH MCGILL BOULEVARD NE ATLANTA, GA 30308 678 432 2069
TELEPHONE / CABLE: AT&T COMMUNICATIONS JOHN OWENS, DESIGNER 675 WEST PEACHTREE ROAD ATLANTA, GA 30308 404 209 3967	TELEPHONE / CABLE: CHARTER COMMUNICATIONS JASON JOHNSON, FIELD ENGINEER 1920 BRANNAN ROAD MCDONOUGH, GA 30253 404 732 4786	GDOT DARTY MCGUIRE, ITS FIELD COORDINATOR 935 EAST CONFEDERATE AVENUE BUILDING *5 ATLANTA, GA 30316 404 624 7819



Know what's below
Call before you dig



A&R Engineering, Inc.
 2160 Kingston Court, Suite 0
 Marietta, GA 30067
 Tel: (770) 690-9255 Fax: (770)
 690-9210
 www.aareng.com

REVISION DATES

STATE OF GEORGIA
 DEPARTMENT OF TRANSPORTATION
 OFFICE OF TRAFFIC OPERATIONS

GENERAL NOTES

PROJECT - CSNHS-0008-00(274)
 COUNTY - HENRY
 DATE - 2/28/08