SUMMARY OF QUANTITIES

VOID

SUMMARY OF QUANTITIES–STANDARD SIGNS

STATION	INSTL. NO.	SIGN CODE	TP 1 MATL, REFL SHEETING TP 3			TP 2 MATL, REFL SHEETING TP 3			TP 2 MATL, REFL SHEETING TP 9			SQUARE TUBE POST TYPE 7		
			SIZE	QUANTITY	SQUARE FEET	SIZE	QUANTITY	SQUARE FEET	SIZE	QUANTITY	SQUARE FEET	LENGTH (FEET)	QUANTITY	TOTAL LENGTH
103+00.00 RT	1	W3-3							36" X 36"	1	9.00	15	1	15
		W16-8a							48" X 12"	1	4.00			
		W16-8a							48" X 12"	1	4.00			
103+49.00 LT	2	D3-1	30" X 12"	1	2.50							12	1	12
		D3-1	54" X 12"	1	4.50									
103+82.00 RT	3	R8-3a	24" X 24"	1	4.00									
104+91.00 LT		MARTA	12" X 18"	1	1.50							12	1	12
105+37.00 RT		MARTA	12" X 18"	1	1.50							12	1	12
105+58.00 LT	4	R1-1							36" X 36"	1	9.00	15	1	15
		D3-1	30" X 12"	1	2.50									
		D3-1	48" X 12"	1	4.00									
105+61.00 RT	5	R1-2							36" TRI	1	4.00	13	1	13
105+95.00 LT	6	W14-2							36" X 36"	1	9.00	13	1	13
105+97.00 RT	7	R1-1							36" X 36"	1	9.00	15	1	15
		D3-1	30" X 12"	1	2.50									
		D3-1	54" X 12"	1	4.50									
106+25.00 RT	8	W11-1							36" X 36"	1	9.00	15	1	15
		W16-8a							18" X 24"	1	3.00			
106+70.00 LT	9	R1-1							36" X 36"	1	9.00	15	1	15
			30" X 12"	1	2.50									
			36" X 12"	1	3.00									
107+05.00 LT	10	R5-2	24" X 24"	1	4.00							12	1	12
107+25.00 RT	11	R4-7	24" X 30"	1	5.00							13	1	13
108+00.00 LT	12	R2-1	24" X 30"	1	5.00							13	1	13
108+10.00	13	R6-2R	24" X 30"	1	5.00							13	1	13
109+50.00 LT	14	M3-4	24" X 12"	1	2.00							15	1	15
		M1-5	30" X 24"	1	5.00									
109+50.00 RT	15	D3-1				60" X 24"	1	10.00				12	2	12
109+74.00 LT	16	R1-2							36" TRI	1	4.00	13	1	13
109+88.00 LT	17	R3-5	30" X 36"	1	7.50							13	1	13
110+07.00 LT	18	R5-1							36" X 36"	1	9.00	13	1	13
110+13.00 RT	19	R560-5	18" X 24"	1	3.00							12	1	12
110+37.00 LT	20	R1-2							36" TRI	1	4.00	13	1	13
110+96.00 RT	21	R10-11A	24" X 30"	1	5.00							13	1	13
111+95.00 LT	22	R1-2							36" TRI	1	4.00	13	1	13
112+00.00 RT	23	R560-5	18" X 24"	1	3.00							12	1	12
112+09.00 LT	24	R560-5	18" X 24"	1	3.00							12	1	12
112+78.00 RT	25	R3-2	24" X 24"	1	4.00							12	1	12
112+92.00 RT	26	R1-1							36" X 36"	1	9.00	13	1	13
113+40.00 RT	27	R2-1	24" X 30"	1	5.00							13	1	13
113+54.00 RT	28	M3-2	24" X 12"	1	2.00							15	1	15
		M1-5	30" X 24"	1	5.00									
113+81.00 LT	29	R6-2R	24" X 30"	1	5.00							13	1	13
113+87.00 LT	30	D3-1				60" X 24"	1	10.00				12	2	12
114+35.00 LT		MARTA	12" X 18"	1	1.50							12	1	12
114+40.00	31	R4-7	24" X 30"	1	5.00							13	1	13
114+84.00 RT	32	R560-5	18" X 24"	1	3.00							12	1	12
115+14.00 RT	33	R1-2							36" TRI	1	4.00	13	1	13
115+15.00 LT	34	W11-1							36" X 36"	1	9.00	15	1	15
		W16-8a							18" X 24"	1	3.00			
117+10.00 LT	35	W3-3							36" X 36"	1	9.00	15	1	15
		W16-8a							48" X 12"	1	4.00			
		W16-8a							48" X 12"	1	4.00			
200+67.00 RT	36	W3-3							36" X 36"	1	9.00	15	1	15
		W16-6a							42" X 12"	1	3.50			
201+86.00 LT	37	R2-1	24" X 30"	1	5.00							13	1	13
208+17.00 RT	38	R2-1	24" X 30"	1	5.00							13	1	13
209+00.00 LT	39	W3-3							36" X 36"	1	6.25	15	1	15
		W16-8a							42" X 12"	1	3.50			
TOTAL					122			20			155		43	571

TRAFFIC STRIPE

DESCRIPTION	UNIT	QUANTITY THERMOPLASTIC
5 IN WHITE	LF	4455
5 IN YELLOW	LF	3265
24 IN WHITE	LF	306
8 IN WHITE	LF	3340
SKIP, 5 IN WHITE	GLF	500
SKIP, 5 IN YELLOW	GLF	510
YIELD BAR	LF	34

ARROWS (EACH)

DESCRIPTION	QUANTITY THERMOPLASTIC
TYPE 2	29

WORDS (EACH)

DESCRIPTION	QUANTITY THERMOPLASTIC
TYPE 1	1

REFLECTIVE PAVEMENT MARKERS TP 1

EACH	50

REFLECTIVE PVMNT MARKERS TP 3

EACH	81

SUMMARY OF TRAFFIC SIGNAL ITEMS

DESCRIPTION	UNIT	QUANTITY
TRAFFIC SIGNAL INST. NO. 1	LUMP	LUMP
TRAFFIC SIGNAL INSTALLATION, TEMPORARY	LUMP	LUMP
CONDUIT, NONMETAL, TP3, 2"	LF	1400
DIRECTIONAL BORE – 6 IN	LF	225
DIRECTIONAL BORE – 5 IN	LF	35
DIRECTIONAL BORE – 3 IN	LF	110
PULL BOX, TYPE 3	EA	2
HIGHWAY SIGNS, TP 2, REFL. SHEETING TP 9	SF	57
STEEL STRIAN POLE TP IV W/35' MAST ARM	EA	2
STEEL STRIAN POLE TP IV W/40' MAST ARM	EA	1
STEEL STRIAN POLE TP IV W/45' MAST ARM	EA	1

THERMO TRAF STRIPE (WHITE), (SY)

DETAIL A	259
DETAIL B	0
DETAIL C	307

THERMO TRAF STRIPE (YELLOW), (SY)

DETAIL A	33
DETAIL B	251
DETAIL C	0

LOCATION — OVERHEAD STREET NAME SIGN (USE CLEARVIEW 3-W)

LOCATION	CODE	SIZE	SQUARE FEET	QUANTITY
LAVISTA RD	D-SPEC #1	60" x 18"	7.50	2
OAK GROVE RD	D-SPEC #2	84" x 18"	10.5	1
OAK GROVE DR	D-SPEC #3	84" x 18"	10.5	1
OAK GROVE DR	D-SPEC #4	84" x 18"	10.5	1
OAK GROVE RD	D-SPEC #5	84" x 18"	10.5	1
TOTALS			57.0	6

104+91.00 LT 27'
105+37.00 RT 29'
114+35.00 RT 29'

POND
Responsive People. Real Partners
3500 Parkway Lane
Suite 600
Norcross, Ga. 30092
Phone 678-336-7740
Fax 678-336-7744
Web www.pondco.com
Project No. . . .

REVISION DATES
08/05/13

DEKALB COUNTY PUBLIC WORKS
TRANSPORTATION DIVISION
OFFICE:
SUMMARY OF QUANTITIES
INTERSECTION IMPROVEMENTS
LAVISTA RD AT OAK GROVE RD

DRAWING No. 6-03

GPLN: $$SEF01A $$SEF01B $$SEF01C $$SEF01D $$SEF01E