

DATE##	TIME##	PRJ##	SDGN#	STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
USER#		PENTABLE#		GA	CSSTP-0008-0013741	83	107

MONITORING SAMPLING METHODS AND PROCEDURES (CONTINUED)

(3). For infrastructure construction projects, when the permittee determines that some receiving water(s) will not be sampled due to representative sampling, the design professional making this determination and preparing the Plan must include and sign the following certification in the Plan:

"I certify that the permittee's Erosion, Sedimentation and Pollution Control Plan provides for the monitoring of: (a) all perennial and intermittent streams and other water bodies shown on the USGS topographic map and all other field verified perennial and intermittent streams and other water bodies, or (b) where any such specific identified perennial or intermittent stream and other water body is not proposed to be sampled, I have determined in my professional judgment, utilizing the factors required in the General NPDES Permit No. GAR 100002, that the increase in the turbidity of each specific identified sampled receiving water will be representative of the increase in the turbidity of a specific identified un-sampled receiving water."

(4). For infrastructure construction projects, if at any time during the life of the project a selected receiving water no longer represents another receiving water, then the permittee shall sample the latter receiving water until selection of an alternative representative receiving water.

(5). For infrastructure construction projects, if at any time during the life of the project a receiving water is determined not to be represented as certified in the Plan, the permittee shall sample that receiving water until a Notice of Termination is submitted or until the applicable phase is stabilized in accordance with this permit.

(6). For infrastructure construction projects, monitoring obligations shall cease for any phase of the project that has been stabilized in accordance with Part IV.0.6.c.(1),(g).

d. Sampling Frequency.

(1). The primary permittee must sample in accordance with the Plan at least once for each rainfall event described below. For a qualifying event the permittee shall sample at the beginning of any storm water discharge to a monitored receiving water and/or from a monitored outfall location within forty-five (45) minutes or as soon as possible.

(2). However, where manual and automatic sampling are impossible (as defined in this permit), or are beyond the permittee's control, the permittee shall take samples as soon as possible, but in no case more than twelve (12) hours after the beginning of the storm water discharge.

(3). Sampling by the permittee shall occur for the following qualifying events:

(a). For each area of the site that discharges to a receiving water or from an outfall, the first rain event that reaches or exceeds 0.5 inch with a storm water discharge that occurs during normal business hours as defined in this permit, after all clearing and grubbing operations have been completed, but prior to completion of mass grading operations, in the drainage area of the location selected as the representative sampling location;

(b). In addition to (a) above, for each area of the site that discharges to a receiving water or from an outfall, the first rain event that reaches or exceeds 0.5 inch with a storm water discharge that occurs during normal business hours as defined in this permit either 90 days after the first sampling event or after all mass grading operations have been completed, but prior to submittal of a NOT, in the drainage area of the location selected as the representative sampling location, whichever comes first.

(c). At the time of sampling performed pursuant to (a) and (b) above, if BMPs in any area of the site that discharges to a receiving water or from an outfall are not properly designed, installed and maintained, corrective action shall be defined and implemented within two (2) business days, and turbidity samples shall be taken from discharges from that area of the site for each subsequent rain event that reaches or exceeds 0.5 inch during normal business hours until the selected turbidity standard is attained, or until post-storm event inspections determine that BMPs are properly designed, installed and maintained;

(d). Where sampling pursuant to (a), (b) or (c) above is required but not possible (or not required because there was no discharge), the permittee, in accordance with Part IV.D.4.a.(6), must include a written justification in the inspection report of why sampling was not performed. Providing this justification does not relieve the permittee of any subsequent sampling obligations under (a), (b) or (c) above; and

(e). Existing construction activities, i.e., those that are occurring on or before the effective date of this permit, that have met the sampling required by (a) above shall sample in accordance with (b). Those existing construction activities that have met the sampling required by (b) above shall not be required to conduct additional sampling other than as required by (c) above.

REF 1/4
REF 1/4
REF 1/4

REF 1/4
REF 1/4
REF 1/4

USE ON CONSTRUCTION

PREPARED BY: 
Level II Certification #: 0000017138

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE:
ESPC GENERAL NOTES
INTERSECTION IMPROVEMENTS
LAVISTA ROD. AT OAK GROVE RD.

REVISION DATES	
10/09/13	

POND
Architects-Engineers-Planners
3500 Parkway Lane
Suite 600 •
Norcross, Ga. 30092
Phone 678-336-7740
Fax 678-336-7744
Web www.pondco.com

DRAWING No.
51-03