

ENVIRONMENTAL RESOURCES IMPACT TABLE

RESOURCE NAME / TYPE	LOCATION		SIDE	CONSTRUCTION ACTIVITY	PERMITTED ACTIVITY	CONTROLLING CRITERIA	SPECIAL PROVISION	COMMENTS
	STATION	STATION						
STREAM 1 - MIDDLE OCONEE RIVER	GALILEE CHURCH RD. STA. 16+83	GALILEE CHURCH RD. STA. 19+73	BOTH	BRIDGE CONSTRUCTION & DEMOLITION	EXEMPT BECAUSE BRIDGE SPANS STREAM	SECTION 404 OF THE CWA (PERMIT NOT NECESSARY B/C OF EXEMPTION)	NO	NONE
STREAM 1 BUFFER - WATERS OF THE U.S. - MIDDLE OCONEE RIVER	GALILEE CHURCH RD. STA. 16+51	GALILEE CHURCH RD. STA. 18+98	BOTH	BRIDGE CONSTRUCTION & DEMOLITION, RIP RAP PLACEMENT & ENDROLL FILL	ACTIVITIES WITHIN 100' OF BRIDGE ARE EXEMPT	EPD STREAM BUFFER VARIANCE GUIDANCE	NO	NONE
HISTORIC RESOURCE 1 - JOHNSON FARM	GALILEE CHURCH RD. STA. 13+35	GALILEE CHURCH RD. STA. 17+95	RT	PLACEMENT OF FILL FOR DRIVEWAY CONSTRUCTION	REFER TO SPEC 107.23F	SECTION 106	107.23F	THE CONTRACTOR SHALL ENSURE THAT NO CONSTRUCTION RELATED ACTIVITIES (EASEMENT, STAGING, VEHICULAR USE, BORROW OR WASTE ACTIVITIES, OR CONSTRUCTION TRAILERS), EXCEPT DRIVEWAY CONSTRUCTION, SHALL TAKE PLACE INSIDE THE DELINEATED HISTORIC PROPERTY BOUNDARIES.
HISTORIC RESOURCE 2 - GALILEE CHURCH CEMETARY	250' BEYOND PROJECT LIMIT AT GALILEE CHURCH RD. STA. 25+72		RT	NONE	NONE	SECTION 106	NO	RESOURCE IS OUTSIDE OF PROJECT LIMITS, BUT WAS INCLUDED IN ENVIRONMENTAL DOCUMENT BECAUSE IT IS WITHIN VIEW PAN OF PROJECT
WILDLIFE & HABITAT (MIGRATORY BIRDS)	GALILEE CHURCH RD. STA. 16+87	GALILEE CHURCH RD. STA. 19+50	BOTH	DEMOLITION OF EXISTING BRIDGE	REFER TO SPEC 107.23G	MIGRATORY BIRD TREATY ACT	107.23G	<ol style="list-style-type: none"> REMOVAL OF EXISTING BRIDGE SHALL TAKE PLACE OUTSIDE OF THE NESTING SEASON OF THE BARN SWALLOW AND CLIFF SWALLOW, WHICH BEGINS APRIL 1ST AND EXTENDS THROUGH AUGUST 31ST, UNLESS EXCLUSIONARY BARRIERS ARE PUT IN PLACE TO PREVENT NESTING FROM OCCURING ON THE BRIDGE STRUCTURE. EXCLUSIONARY BARRIERS, CONSTRUCTED ON NETTING, PLASTIC SHEETING OR OTHER MATERIALS PROPOSED BY THE CONTRACTOR MAY BE INSTALLED ON THE BRIDGE PRIOR TO MARCH 1ST OR AFTER AUGUST 31ST, BUT IN NO TIME IN BETWEEN THIS PERIOD. THE OFFICE OF ENVIRONMENTAL SERVICES SHALL BE CONTACTED PRIOR TO INSTALLATION OF EXCLUSIONARY DEVICES. CONTRACTOR SHALL DIRECT QUESTIONS TO THE ENGINEER, AND THE ENGINEER SHALL CONTACT ENVIRONMENTAL SERVICES IF NECESSARY FOR RESOLUTION.



REVISION DATES

STATE OF GEORGIA
 DEPARTMENT OF TRANSPORTATION
 OFFICE: DISTRICT 1

GENERAL NOTES

GALILEE CHURCH ROAD

DRAWING No.
4-03