RAISED PAVEMENT MARKERS (EACH)

LOCATION	REFLECTIVE (RAISED)			REFLECTIVE (RECESSED)			OPAQUE		JIGGLE BAR		CHANNEL MKR	
	YELLOW	CLEAR	CL/RED	YELLOW	CLEAR	CL/RED	WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW
	TYPE 1	TYPE 2	TYPE 3	TYPE 1	TYPE 2	TYPE 3	TYPE 5	TYPE 6	TYPE 7	TYPE 8	TYPE 9	TYPE 10
S.R. 96												
LANE LINES			435									
TURN BAYS			271									
CENTER LINE	30											
ROBERT BRYSON SMITH PARKWAY												
TURN BAY			11									
CENTER LINE	20											
OLD PERRY ROAD												
TURN BAYS			57									
CENTER LINE	40											
U.S. 129/S.R. 247												
LANE LINES			76									
TURN BAYS			88									
CENTER LINE	36											
TWO-WAY-LEFT-TURN LANE	51											
OLD HAWKINSVILLE ROAD												
TURN BAYS			90									
CENTER LINE	148											
THOMPSON MILL ROAD												
TURN BAYS			21									
CENTER LINE	30											
OLD S.R. 96												
TURN BAYS			84									
CENTER LINE	106											
RAMP "A"												
GORE AREA			53									
TURN BAYS			16									
RAMP "B"												
GORE AREA			18									
LANE LINE			5									
RAMP "C"												
GORE AREA			46									
TURN BAYS			19									
RAMP "D"												
GORE AREA			24									
LANE LINE			5									
TOTALS	461		1319									

TYPE 1, 2, AND 3 RAISED PAVEMENT MARKERS SHALL BE SPACED AS SPECIFIED ON THE RAISED PAVEMENT MARKERS LOCATION DETAILS.

TRAFFIC STRIPE

DESCRIPTION	UNIT	QUANTITY		
		PAINT	THERMOPLASTIC	PREFORMED PLASTIC
5" SOLID WHITE	LIN. FEET			
5" SOLID YELLOW	LIN. FEET			
8" SOLID WHITE	LIN. MILE		1.78	
10" SOLID WHITE	LIN. FEET		1100	
24" SOLID WHITE	LIN. FEET		700	
5" SOLID WHITE	LIN. MILE	2.35	12.71	
5" SOLID YELLOW	LIN. MILE		10.55	
6" SOLID WHITE	LIN. MILE	2.35		
5" SKIP WHITE	GR. LIN. FT	900		
5" SKIP YELLOW	GR. LIN. FT.		4000	
6" SKIP WHITE	GR. LIN. FT	900		
10" SKIP WHITE	GR. LIN. FT.			
5" SKIP WHITE	GR. MILE		8.53	
5" SKIP YELLOW	GR. MILE			
8" SOLID CONTRAST-WHITE	LIN. FEET			900
8" SOLID CONTRAST-YELLOW	LIN. FEET			900
13" SOLID CONTRAST-WHITE	LIN. FEET			175
8" SKIP CONTRAST-WHITE	GR. LIN. FT.			1150

ARROWS (EACH)

DESCRIPTION	QUANTITY	
	PAINT	THERMOPLASTIC
TYPE 1	6	
TYPE 2		155
TYPE 3		1
TYPE 4		
TYPE 7		16

ALL ARROWS SHALL BE WHITE UNLESS OTHERWISE SPECIFIED.
SEE PLANS FOR LOCATION.

WORDS (EACH)

DESCRIPTION	QUANTITY	
	PAINT	THERMOPLASTIC
TYPE 1		3
TYPE 2		
TYPE 3A		
TYPE 3B		

ALL WORDS SHALL BE WHITE UNLESS OTHERWISE SPECIFIED.
SEE PLANS FOR LOCATION.

SYMBOLS (EACH)

DESCRIPTION	QUANTITY	
	PAINT	THERMOPLASTIC
TYPE 1		
TYPE 4	6	
RR/HWY		3

ALL SYMBOLS SHALL BE WHITE UNLESS OTHERWISE SPECIFIED.
SEE PLANS FOR LOCATION.

PAVEMENT ARROW, THERMOPLASTIC, W/RAISED REFLECTORS (EACH)

LOCATION	QUANTITY
U.S. 129/S.R. 247	
RAMP "A"	1
RAMP "C"	1
TOTAL	2

THERMOPLASTIC TRAF STRIPE (SQ. YD.)

QUANTITY	
WHITE	YELLOW
1900	4000

SEE PLANS FOR LOCATION AND DETAIL REFERENCE.

ATKINS

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

SUMMARY QUANTITIES

PAVEMENT MARKINGS
SR 96 WIDENING

DRAWING No. 6-033