

RELEASED FOR CONSTRUCTION 11/04/09

TRAFFIC SIGNAL GENERAL NOTES

- | | | |
|--|---|---|
| <p>1. THE COMPLETE SIGNAL INSTALLATION SHALL CONFORM TO ALL APPROPRIATE PARTS OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES CURRENT EDITION.</p> <p>2. SIGNAL HEADS SHALL BE ERECTED TO PROVIDE AT LEAST 17 FEET BUT NO MORE THAN 19 FEET CLEARANCE FROM BOTTOM OF SIGNAL HEADS TO TOP OF ROAD SURFACE AND A MINIMUM OF 8 FEET MEASURED HORIZONTALLY BETWEEN CENTERS OF SIGNAL FACES.</p> <p>3. SHIELDED CABLE WILL BE USED FOR DETECTOR RUNS AS SHOWN ON THE DETAIL SHEET. DETECTORS SHALL HAVE SEPERATE LEAD-INS TO THE CONTROL CABINET.</p> <p>4. THE CONTRACTOR SHALL LOCATE UNDERGROUND UTILITIES IN VICINITY OF NEW TRAFFIC SIGNAL POLES BEFORE INSTALLATION. AT THE DISCRETION OF THE ENGINEER, MINOR SHIFTS, (UP TO A MAXIMUM OF 5 FEET), IN LOCATION OF NEW SIGNAL POLES, ARE ACCEPTABLE TO AVOID UNDERGROUND UTILITIES. MINIMUM CLEARANCES FROM EDGE OF PAVEMENT SHALL BE MAINTAINED. PLACEMENT OF THE SIGNAL HEADS SHALL BE RETAINED AS SHOWN ON THE PLANS.</p> <p>5. THE CONTRACTOR SHALL MAINTAIN EXISTING TRAFFIC SIGNALS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TRAFFIC SIGNAL AND/OR CONTROL SYSTEM ADJUSTMENTS, INCLUDING TEMPORARY SUPPORT POLE LOCATIONS(S) REQUIRED BY THE PROJECT DURING THE INTERIM PERIOD THROUGH INSTALLATION OF NEW SIGNAL EQUIPMENT. AT NO TIME SHALL THE CONTRACTOR CAUSE ANY PART OF THE SIGNAL OPERATION TO BE INOPERABLE.</p> | <p>6. THE CONTRACTOR WILL BE RESPONSIBLE FOR ALL NEW GUYS ON EXISTING UTILITY TIMBER POLES WHEN ATTACHING SPAN WIRE OR INTERCONNECT CABLE TO THE POLES UNLESS OTHERWISE DIRECTED BY THE ENGINEER.</p> <p>7. INSTALLATION IS TO BE CHECKED AND ACCEPTED BY THE DISTRICT TRAFFIC ENGINEER PRIOR TO FINAL ACCEPTANCE.</p> <p>8. WHEN REMOVED, EXISTING EQUIPMENT SHALL BE DELIVERED AND UNLOADED BY THE CONTRACTOR TO THE DEPARTMENT OF TRANSPORTATION OFFICE OF TRAFFIC OPERATIONS, 5025 NEW PEACHTREE RD, CHAMBLEE, GA 30341. CONTACT THE DISTRICT SIGNAL ENGINEER AT 404-651-8982.</p> <p>9. FOR STRAIN POLE FOUNDATION SIZE AND REINFORCEMENT, SEE STRAIN POLE AND MAST ARM POLE FOUNDATION SHEET.</p> <p>10. MATERIAL CERTIFICATION IS REQUIRED PRIOR TO BEGINNING ANY SIGNAL INSTALLATION WORK. THE CONTRACTOR SHALL FOLLOW PROCEDURES OUTLINED IN THE DOT SPECIFICATION.</p> <p>11. THE INSTALLATIONS SHALL BE CAPABLE OF "CLOSED LOOP" ISOLATED MONITORING OVER TELEPHONE LINES FROM EXISTING CENTRAL COMPUTERS LOCATED AT BOTH THE LOCAL DOT DISTRICT OFFICE, TRAFFIC ENGINEERING SECTION, AND THE DOT OFFICE OF TRAFFIC SIGNAL ELECTRICAL FACILITIES, 935 E. CONFEDERATE AVENUE BLDG. 5 ATLANTA, GEORGIA 30316. CLOSED LOOP SYSTEM DEMONSTRATION IS REQUIRED AT BOTH CENTRAL SITES, NOTED PRIOR TO FINAL ACCEPTANCE.</p> | <p>12. PROPOSED SIGNAL SUPPORT WIRE ATTACHMENT HEIGHTS ON POLES ARE PROVIDED AS GENERAL GUIDELINES TO INSTALLER, ACTUAL ATTACHMENT HEIGHTS SHALL BE FIELD DETERMINED BY INSTALLER TO PROVIDE REQUIRED SIGNAL HEAD MOUNTING HEIGHTS AND CLEARANCE FROM EXISTING UTILITIES.</p> <p>13. SAWCUTS AND REMOVAL OF ALL CONCRETE ASSOCIATED WITH CURB CUT RAMPS SHALL BE INCLUDED IN THE SIDEWALK PAY ITEM.</p> |
|--|---|---|



**Know what's below
Call before you dig**

NOTES:

UTILITY DISCLAIMER: EXISTING UTILITY LINES SHOWN ARE APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR/INSTALLER SHALL FIELD VERIFY ALL EXISTING UTILITY LINE LOCATIONS PRIOR TO ANY CONSTRUCTION. DAMAGE TO EXISTING UTILITY LINES RESULTING FROM THE CONTRACTORS/INSTALLERS NEGLIGENCE SHALL BE REPAIRED AT THE CONTRACTORS/INSTALLERS EXPENSE.

CONTRACTOR/INSTALLER SHALL CONTACT UTILITY LOCATOR SERVICE, 1-800-282-7411, & COUNTY OF FULTON AT 770-623-4344 PRIOR TO ANY CONSTRUCTION.

EXISTING POLE ATTACHMENT DATA IS APPROXIMATE AND IS PROVIDED AS A GENERAL GUIDELINE TO THE CONTRACTOR/INSTALLER TO AID IN IDENTIFYING POTENTIAL INSTALLATION CONFLICTS, THE CONTRACTOR/INSTALLER SHALL PROVIDE APPROPRIATE CLEARANCES FROM UTILITIES.

UTILITY OWNER	SERVICE	CONTACT NUMBERS
AGL NETWORKS	GAS	404-584-4628
AGL RESOURCES	GAS	404-584-4318
AT&T BELLSOUTH	TELECOMMUNICATIONS	770-493-3722
CITY OF ATLANTA	WATER/SEWER	404-982-1446
COMCAST	CABLE	770-559-6884
FIBERLIGHT, LLC	TELECOMMUNICATIONS	678-347-9271
FULTON CO PUBLIC WORKS	WATER/SEWER	404-612-7537
GEORGIA POWER DISTRIBUTION	ELECTRICITY	770-216-1433
GEORGIA POWER NETWORK UG	ELECTRICITY	404-506-4426
LEVEL 3 COMMUNICATIONS	TELECOMMUNICATIONS	678-534-2478
TIME WARNER TELECOM/XSPEDIOUS	TELECOMMUNICATIONS	678-526-3767
CITY OF SANDY SPRINGS	FIBER OPTICS	770-206-2534
VERIZON BUSINESS	TELECOMMUNICATIONS	478-471-1042
XO COMMUNICATIONS	TELECOMMUNICATIONS	673-431-5358



REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: INNOVATIVE PROGRAM DELIVERY
GENERAL NOTES