RELEASED FOR CONSTRUCTION 11/04/09

GENERAL NOTES

1. THE CONTRACTOR SHALL LOCATE ALL UTILITIES BEFORE DIGGING TO ELIMINATE ANY CONFLICTS. TO OBTAIN HIGHWAY LIGHTING PLANS, THE CONTRACTOR SHALL CONTACT THE DEPARTMENT AT (404) 631-1534. FOR GDOT ATMS / ITS FACILITIES THAT MAY BE IMPACTED, THE CONTRACTOR SHALL CONTACT THE GDOT ITS MANAGER AT (404) 694-6613.

2. THE CONTRACTOR SHALL CONTACT THE ITS MANAGER AT (404) 694-6613 TO LOCATE GDOT ITS INFRASTRUCTURE AT LEAST 48 HOURS IN ADVANCE.

3. WITHIN 24 HOURS, THE CONTRACTOR SHALL REPAIR ANY EXISTING CONDUIT, CABLE, OR PIPE THAT IS DAMAGED BY ANY WORK PERFORMED AS PART OF THIS PROJECT AT NO ADDITIONAL COST TO THE DEPARTMENT.

4. THE CONTRACTOR SHALL REPLACE IN LIKE KIND AND SIZE, AT NO ADDITIONAL COST TO THE DEPARTMENT, ANY PAVEMENT MARKINGS, BARRIER WALL, FENCE, DITCH PAVING, CURBING, SIDEWALK, GUTTER, SLOPE PAVEMENT, SIGNS, GUARDRAIL, LANDSCAPING (IN ACCORDANCE WITH GEORGIA SPECIFICATIONS SECTION 702), GRASSING (IN ACCORDANCE WITH GEORGIA SPECIFICATIONS SECTION 700), UTILITY SERVICE LINES, STORM DRAIN PIPES, RUMBLE STRIPS, ROADWAY, AND ANY RETAINING WALLS THAT ARE DAMAGED OR DESTROYED BY ANY WORK PERFORMED AS PART OF THIS PROJECT. THE CONTRACTOR WILL NOT BE REQUIRED TO MAINTAIN LANDSCAPING AS SPECIFIED IN SECTION 702.3.07 OF THE GEORGIA SPECIFICATIONS.

5. FIBERGLASS OR RIGID STEEL CONDUIT SHALL BE USED AT ALL EXPOSED CONDUIT LOCATIONS.

6. THE CONTRACTOR SHALL REMOVE PAVEMENT BY SAW CUT TO PROVIDE A NEAT LINE. WHERE CONDUIT IS INSTALLED, THE CONTRACTOR SHALL INLAY TO MATCH EXISTING SURFACE TYPE AFTER CONDUIT IS INSTALLED. PAVEMENT REMOVAL AND PAVEMENT INLAY SHALL BE INCLUDED IN THE BID PRICE FOR CONDUIT DUCT BANK OR CONDUIT.

7. ANY REQUIRED EROSION CONTROL DEVICES WILL NOT BE MEASURED SEPARATELY AND SHALL BE INCLUDED IN THE COST OF THE OVERALL BID.

8. THE ELECTRIC POWER SERVICE ASSEMBLY POINTS SHOWN ON THE PLANS ARE FOR THE CONTRACTOR'S USE IN DETERMINING POWER ROUTING TO EACH DEVICE. THE CONTRACTOR SHALL COORDINATE WITH THE LOCAL ELECTRICAL UTILITY COMPANIES TO PROVIDE POWER TO THE SERVICE RISER POINTS. POWER SERVICE SHALL BE LOCATED AS SHOWN ON PLANS OR AT THE BACK OF THE RIGHT-OF-WAY LINE, IF A NEW LOCATION IS PROPOSED.

9. ALL PROPOSED STRAIN POLES SHALL BE INSTALLED A MINIMUM OF 6 FEET BEHIND EXISTING OR PROPOSED GUARDRAIL WHERE SHOWN ON THE PLANS.

10. MINOR TREE TRIMMING AND REMOVAL MAY BE REQUIRED. HOWEVER, LOCATIONS MAY BE REQUIRED AS DIRECTED BY THE ENGINEER TO OBTAIN CAMERA VISIBILITY OF 2/3 OF A MILE AND TO MEET MINIMUM SIGHT DISTANCES FOR TRAFFIC SIGNALS AS PER MUTCD. PAYMENT FOR THIS WORK SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR THIS PROJECT.

11. CONDUIT UNDER BRIDGES SHALL BE INSTALLED BY DIRECTIONAL BORING, UNLESS NOTED OTHERWISE ON THE PLANS.

12. THE CONTRACTOR SHALL DIRECT BURY SERVICE WIRE TO THE DEVICES. THE COST OF THE SERVICE WIRE, AND ANY OTHER MATERIALS REQUIRED TO PROVIDE POWER SERVICE TO THE DEVICES SHALL BE INCLUDED IN THE BID PRICE FOR ELECTRICAL POWER SERVICE ASSEMBLY, AERIAL SERVICE POINT.

13. THE CONTRACTOR SHALL SALVAGE ALL EXISTING EQUIPMENT AND RETURN TO GDOT AT 935 EAST CONFEDERATE AVENUE, BUILDING 5.

14. ALL EXISTING NAV NUMBERS SHALL BE RELOCATED TO NEW POLES. CONTRACTOR TO UPGRADE NAV NUMBERS AS NECESSARY BASED ON NEW POLE LOCATIONS.

15. ITS SYSTEM WITHIN PROJECT LIMITS SHALL NOT BE OFFLINE FOR MORE THAN 72 HOURS

16. THE CONTRACTOR SHALL CONFIRM EACH POWER SERVICE POINT WITH THE POWER COMPANY PRIOR TO INSTALLATION.

UTILITY OWNERS		
AGL NETWORKS L.P. 404 584 4268	AGL RESOURCES, INC 404 584 4318	AT&T BELLSOUTH 770 493 3722
CITY OF ATLANTA 404 982 1446	COMCAST 770 559 6884	FIBERLIGHT, LLC 678 347 9271
FULTON COUNTY DEPARTMENT OF PUBLIC WORKS 404 612 7537	GEORGIA POWER COMPANY DISTRIBUTION 770 216 1433	GEORGIA POWER COMPANY NETWORK UNDERGROUND 404 506 4426
LEVEL 3 COMMUNICATION 678 534 2478	TIME WARNET TELECOM INC 678 526 3767	CITY OF SANDY SPRINGS 770 206 2534
VERIZON BUSINESS 478 471 1042	XO COMMUNICATIONS 673 431 5358	

811
Know what's below
Call before you dig

REQUIRED R/W LINE
CONSTRUCTION LIMITS
EASEMENT FOR CONSTR & MAINTENANCE OF SLOPES
EASEMENT FOR CONSTR OF SLOPES
EASEMENT FOR CONSTR OF DRIVES

PROPERTY AND EXISTING R/W LINE
BEGIN LIMIT OF ACCESS.....BLA
END LIMIT OF ACCESS.....ELA
LIMIT OF ACCESS
R/W AND LIMIT OF ACCESS
HISTORICAL BOUNDARY

A&R Engineering, Inc.
2160 Kingston Court, Suite O
Marietta, GA 30067
Tel: (770) 690-9255 Fax: (770) 690-9210
www.arengineering.com

REVISION DATES		

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: INNOVATIVE PROGRAM DELIVERY

GENERAL NOTES
PROJECT - CSNHS-0008-00(415)
COUNTY - FULTON
DATE - 04/15/09

DRAWING No. 28-0C