SUMMARY OF QUANTITIES

CONCRETE SIDEWALK, 8 IN	
UNIT	QUANTITY
SY	17

CONCRETE MEDIAN, 4 IN	
UNIT	QUANTITY
SY	130

GRADING COMPLETE-CSSFT-0008-00(533)	
UNIT	QUANTITY
LUMP	LUMP

RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	
UNIT	QUANTITY
TN	2

RECYCLED ASPHALTIC CONC, 12.5 SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME	
UNIT	QUANTITY
TN	227

BITUMINOUS TACK COAT	
UNIT	QUANTITY
GL	96

MILL ASPH CONC PVMT, 1.5" DEPTH	
UNIT	QUANTITY
SY	2879

TRAFFIC CONTROL	
UNIT	QUANTITY
LUMP	LUMP

DIRECTIONAL BORE, 5 IN	
UNIT	QUANTITY
LF	95

STEEL WIRE CABLE, 3/8"	
UNIT	QUANTITY
LF	610

STRAIN POLE, TP IV	
UNIT	QUANTITY
EA	4

TRAFFIC SIGNAL INSTALLATION	
UNIT	QUANTITY
LUMP	LUMP

NON-METAL CONDUIT, TYPE 3, 2 IN	
UNIT	QUANTITY
LF	155

INTERSECTION VIDEO DETECTION SYSTEM ASSEMBLY, TYPE A	
UNIT	QUANTITY
EA	2

VIDEO DETECTION SYSTEM TESTING CSSTP-0008-00(533)	
UNIT	QUANTITY
LUMP	LUMP

VIDEO DETECTION SYSTEM TRAINING CSSTP-0008-00(533)	
UNIT	QUANTITY
LUMP	LUMP

USE ON CONSTRUCTION

EROSION CONTROL ITEMS

TEMPORARY GRASSING			
UNIT	QUANTITY	QUANTITY (AS DIRECTED BY ENGINEER)	TOTAL
AC	0.05	0.95	1.0

SOD			
UNIT	QUANTITY	QUANTITY (AS DIRECTED BY ENGINEER)	TOTAL
SY	0.45	0.55	1.0

FERTILIZER NITROGEN CONTENT			
UNIT	QUANTITY	QUANTITY (AS DIRECTED BY ENGINEER)	TOTAL
LBS	7.5	0.5	8.0

MULCH			
UNIT	QUANTITY	QUANTITY (AS DIRECTED BY ENGINEER)	TOTAL
TON	0.145	0.855	1.0

AGRICULTURAL LIME			
UNIT	QUANTITY	QUANTITY (AS DIRECTED BY ENGINEER)	TOTAL
TON	0.45	0.55	1.0

WOOD FIBER BLANKET, TPI, SHOULDERS	
UNIT	QUANTITY
SY	50

PERMENANT GRASSING			
UNIT	QUANTITY	QUANTITY (AS DIRECTED BY ENGINEER)	TOTAL
AC	0.10	0.90	1.0

FERTILIZER MIXED GRADE			
UNIT	QUANTITY	QUANTITY (AS DIRECTED BY ENGINEER)	TOTAL
TON	0.09	0.91	1.0

SILT FENCE TYPE A (AS DIRECTED BY ENGINEER)	
UNIT	QUANTITY
LF	150

GRESHAM SMITH AND PARTNERS

REVISION DATES
5/10/12
6/13/12

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

SUMMARY OF QUANTITIES
SR 1/US 27 AT SR 140/TURKEY MOUNTAIN RD
PROJECT: CSSFT-0008-00(533)
COUNTY: FLOYD

DRAWING No. 06-001