SURFACING QUANTITIES

ITEMS	UNIT	MAINLINE	SIDE ROADS	TEMPORARY PVMT FOR STAGING	TOTALS
RECYCLED ASHP. CONC. 12.5mm SUPERPAVE	TN	314	826	0	1140
RECYCLED ASPH. CONC. 19mm SUPERPAVE	TN	132	588	74	794
RECYCLED ASPH. CONC. 25mm SUPERPAVE	TN	197	881	111	1189
GRADED AGGREGATE BASE COURSE	TN	993	3304	232	4529
ASPH. CONC. LEVELING	TN	200	978	638	1816
BITUM TACK COAT	GAL	258	863	132	1253
PLAIN PC CONC. PAVEMENT, STAMPED & COLORED, 10"	SY	532	0	0	532
4" CONCRETE SIDEWALK	SY	371	0	0	371
30" CURB AND GUTTER TP 2	LF	1173	1182	0	2355
4" HEADER CURB TP 9	LF	365	0	0	365
7½" CONCRETE MEDIAN	SY	515	303	0	818
VARIABLE DEPTH MILLING	SY	816	364	0	1180

PAVEMENT REINFORCEMENT FABRIC STRIPS - TYPE 2

TOTAL 4850 LF

NOTE: PLACEMENT OF REINFORCEMENT FABRIC STRIPS AS DIRECTED BY ENGINEER.

AGGREGATE SURFACE COURSE

AS REQUIRED 2100 TN

FOR USE IN INCLEMENT WEATHER TO FACILITATE THE MOVEMENT OF LOCAL TRAFFIC ALONG ROADWAY CONSTRUCTION AND TO PERMIT INGRESS & EGRESS AT DRIVES. WHEN USED FOR THIS PURPOSE, SECTION 318 OF GEORGIA STANDARD SPECIFICATIONS IS MODIFIED TO PERMIT TRUCK DUMPING ON UNPAVED AND MUDDY SUBGRADE.

THE CONTRACTOR WILL HAVE THE CHOICE OF THE FOLLOWING MATERIALS.
GRADED AGGREGATE - ART. 815.01
COARSE AGGREGATE - SIZE - 467 - ART. 800.01
STABILIZER AGGREGATE - TYPE 1 OR 2 - SECT. 803
ALL MATERIALS TO BE USED AS DIRECTED BY THE ENGINEER.

CLASS "B" CONC., BASE OR PVMT WIDENING

TOTAL 10 CY

CONCRETE RIGHT- OF- WAY MARKERS - GA. STD. 9003

TOTAL 49 EA

GRADING COMPLETE

CSSFT-0008-00(534) LUMP SUM

TRAFFIC CONTROL

CSSFT-0008-00(534) LUMP SUM

SAWED JOINTS IN EXIST PAVEMENTS - PCC

AS REQUIRED 30 LF

CHANGEABLE MESSAGE SIGN - PORTABLE, TYPE 3

TOTAL 2 EACH

WOOD FENCE - 6 FT

TOTAL 20 FT

SUMMARY OF DRIVEWAY QUANTITIES

LOCATION		ASPH. CONC. 12.5mm SUPERPAVE - 165LB/SY	ASPH. CONC. 19mm SUPERPAVE - 220 LB/SY	BITUM TACK COAT	6" G.A.B.	6" DRIVEWAY CONCRETE	8" DRIVEWAY CONCRETE	6" VALLEY GUTTER	8" VALLEY GUTTER	DRIVE TYPE
STATION & SIDE	ROAD	TN	TN	GAL	TN	SY	SY	SY	SY	
STA. 16+99, RT	SR 247C	5	7	2	22					COMMERCIAL ASPHALT
STA. 22+17, RT	SR 247C	12	16	5	50				55	COMMERCIAL ASPHALT
STA. 23+94, RT	SR 247C	16	22	7	69					COMMERCIAL ASPHALT
STA. 23+95, LT	SR 247C	19	26	8	80					COMMERCIAL ASPHALT
STA. 25+56, LT	SR 247C	20	26	8	82					COMMERCIAL ASPHALT
STA. 41+05, RT	SULLIVAN RD	6	8	3	26					COMMERCIAL ASPHALT
STA. 43+02, LT	SULLIVAN RD	5	6	2	20				76	RESIDENTIAL ASPHALT
STA. 44+05, RT	SULLIVAN RD	13	18	6	56				29	COMMERCIAL ASPHALT
STA. 44+88, LT	WALKER RD	5	6	2	20			29		RESIDENTIAL ASPHALT
STA. 48+10, LT	WALKER RD	5	6	2	19					COMMERCIAL ASPHALT
STA. 49+80, RT	WALKER RD	5	6	2	20					COMMERCIAL ASPHALT
STA. 50+71, LT	WALKER RD	5	7	2	20					RESIDENTIAL ASPHALT
STA. 55+20, RT	WALKER RD					62				RESIDENTIAL CONCRETE
STA. 56+28, RT	WALKER RD					53				RESIDENTIAL CONCRETE
STA. 58+55, RT	WALKER RD					56				RESIDENTIAL CONCRETE
AS DIRECTED							100			
TOTAL		116	155	49	485	171	100	29	160	

OVEREXCAVATION OF CONTAMINATED SOILS

AS REQUIRED 100 CY

USE ON CONSTRUCTION

Wolverton & Associates
Consulting Engineers + Land Surveyors
6145 Sugarloaf Parkway Suite 100 Duluth, Georgia 30097
Phone: (770) 447-9999 Fax: (770) 447-9070
www.wolverton-assoc.com

REVISION DATES
01-09-14

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: TRAFFIC OPERATIONS
SUMMARY QUANTITIES

DRAWING No. 6-01

GPLN