ITEM NO.	DESCRIPTION	UNITS	QUANTITY	QUANTITY REQUIRED ON CONSTRUCTION	ITEM NO.	DESCRIPTION	UNITS	QUANTITY	QUANTITY REQUIRED ON CONSTRUCTION
	WALL ITEMS								
457-1005	GEOGRID REINFORCEMENT, TP A	SY	40000						
457-1010	GEOGRID REINFORCEMENT, TP B	SY	1300						
621-4082	CONCRETE SIDE BARRIER, TYPE 7T	LF	30						
626-0320	MSE WALL BACKFILL MATERIAL	CY	9000						
627-1010	MSE WALL FACE, 10 - 20 FT HT, WALL NO - 1	SF	6380						
627-1010	MSE WALL FACE, 10 - 20 FT HT, WALL NO - 2	SF	1580						
627-1100	COPING A, WALL NO - 1	LF	26						
627-1120	COPING B, WALL NO - 1	LF	412						
627-1120	COPING B, WALL NO - 2	LF	181						
	BRIDGE ITEMS								
211-0300	BRIDGE EXCAVATION, STREAM CROSSING	CY	48						
500-0100	GROOVED CONCRETE	SY	8640						
500-1006	SUPERSTR CONCRETE, CL AA, BR NO - 1 (2210)	LS	LS						
500-1008	SUPERSTR CONCRETE, CL AA-1, BR NO -1 (970)	LS	LS						
500-2100	CONCRETE BARRIER	LF	4315						
500-3002	CLASS AA CONCRETE	CY	7735						
507-9035	PSC BEAMS, BULB TEE, 78 IN, BR NO - 1	LF	7735						
507-9036	PSC BEAM, BULB TEE, 78 (144) IN HAUNCHED	LF	3000						
511-1000	BAR REINF STEEL	LB	618223						
511-3000	SUPERSTR REINF STEEL, BR NO - 1 (668042)	LS	LS						
515-2020	GALV STEEL PIPE HANDRAIL, 2 IN, ROUND	LF	4320						
520-2215	PILING, PSC, 18 IN SQ	LF	264						
520-2224	PILING, PSC, 24 IN SQ	LF	2113						
520-2236	PILING, PSC, 36 IN SQ	LF	3816						
520-3224	TEST PILE, PSC, 24 IN SQ	EA	1						
520-3236	TEST PILE, PSC, 36 IN SQ	EA	1						
520-4224	LOAD TEST, PSC, 24 IN SQ (IF REQD)	EA	1						
520-4236	LOAD TEST, PSC, 36 IN SQ (IF REQD)	EA	1						
529-1000	NAVIGATION LIGHTING, BR NO - 1	LS	LS						
540-1102	REMOVAL OF EXISTING BR, BR NO - 1	LS	LS						
544-1000	DECK DRAIN SYSTEM, BR NO - 1	LS	LS						
603-2024	STN DUMPED RIP RAP, TP 1, 24 IN	SY	2082						
603-7000	PLASTIC FILTER FABRIC	SY	2082						

THE LPA GROUP
TRANSPORTATION CONSULTANTS
3595 ENGINEERING DRIVE
NORCROSS, GEORGIA 30092
(770) 263-9118

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: INNOVATIVE PROGRAM DELIVERY

DETAILED ESTIMATE

DRAWING No. 9-02