

BEGIN PROJECT
CSSTP-0008-00(651)
STA. 274+00
N 710846.3085
E 995074.2357
M. P. = 5.63

285+00
S. R. 204 SPUR
STA. 284+00.00 =
BOAT RAMP DRIVEWAY
STA. 10+00.00


BEGIN CONSTRUCTION STA. 278+00.00
MATCH EXIST. PAVEMENT WIDTH
MATCH EXIST. PAVEMENT S.E.
BEGIN OVERLAY & LEVELING

- STAGE 1 PHASE 1
1. INSTALL ADVANCE WARNING SIGNS IN ACCORDANCE WITH GDOT SPECIAL PROVISION SECTION 150 AND MOST CURRENT EDITION OF MUTCD.
 2. REDUCE SPEED LIMIT TO 40 MPH FOR DURATION OF CONSTRUCTION PERIOD.
 3. CONSTRUCT TEMPORARY PAVEMENT, STRIPE TEMPORARY TRAFFIC LANES, INSTALL TEMPORARY BARRIER ON SR 204 SPUR AND SHIFT TRAFFIC TO ACCOMMODATE STAGE 1 CONSTRUCTION AS SHOWN IN THE PLANS.
 4. CONSTRUCT BRIDGE NORTH OF EXISTING SR 204 SPUR.
- STAGE 1 PHASE 2
1. CONSTRUCT TEMPORARY WALLS BETWEEN PROPOSED LANES AND THE EXISTING TRAFFIC AS SHOWN IN THE PLANS.
 2. CONSTRUCT PROPOSED PAVEMENT UP TO BINDER COURSE ON THE NORTH SIDE OF EXISTING SR 204 SPUR AS SHOWN IN THE PLANS.
 3. CONSTRUCT RELOCATED BOAT RAMP DRIVEWAY. CONSTRUCT ENHANCED SWALE AT BOAT RAMP DRIVEWAY FROM STA. 11+00 TO STA. 12+65 LT.

CONSTRUCTION STAGING	
CURRENT STAGE CONSTRUCTION	
TRAFFIC FLOW ARROW	
TEMPORARY BARRIER	
TEMPORARY PAVEMENT	
MILL AND LEVEL PAVEMENT	

STAGE 1

THE LPA GROUP
TRANSPORTATION CONSULTANTS
3595 ENGINEERING DRIVE
NORCROSS, GEORGIA 30092
(770) 263-9118



REVISION DATES	

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: INNOVATIVE PROGRAM DELIVERY

CONSTRUCTION STAGING PLAN

SR204 SPUR/DIAMOND CAUSEWAY
BEGIN PROJECT TO STA. 286+00

DRAWING No. **19-01**