VOID

RELEASED FOR CONSTRUCTION: 08/02/2013

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	CSMSL-0008-00(690)	524	730

LOCATION	NO. OF LOC.	MARK	LENGTH FT.	LENGTH IN.	NO. BARS REQ'D.	TYPE	A	G	B FT.	B IN.	C FT.	C IN.	D FT.	D IN.	E FT.	E IN.	F FT.	F IN.	H FT.	H IN.	J FT.	J IN.	K FT.	K IN.	N	θ
SUBSTRUCTURE	1	410	6	9	40	32	5	5	2	8	1	8	1	8												
BENT 1		411	9	5	113	25	4	4	2	8	1	8														
		411A	11	1	2	25	4	4	3	6	1	8														
		411B	10	7	2	25	4	4	3	3	1	8														
		411C	10	1	2	25	4	4	3	0	1	8														
		412	9	5	6	25	4	4	2	2	2	2														
		413	1	8	8	1																				
		510A	7	7	34	1																				
		510B	7	4	34	1																				
		511A	15	11	18	1																				
		610A	5	8	3	1																				
		610B	9	3	3	1																				
		1010A	39	3	4	6			36	11	0	6	1	10	0	0									0	41
		1010B	60	0	4	1																				
		1010C	38	9	4	4			36	11	1	10														50
SUBSTRUCTURE	2	520	10	5	72	32	5	5	4	2	2	8	2	8												
BENTS 2 & 3		521	14	8	195	25	4	4	4	2	2	8														
		1020A	43	8	20	9	1		42	1																
		1020B	60	0	10	1																				
SUBSTRUCTURE	1	440	6	9	40	32	5	5	2	8	1	8	1	8												
BENT 4		441	9	5	126	25	4	4	2	8	1	8														
		441A	11	11	2	25	4	4	3	11	1	8														
		441B	11	1	2	25	4	4	3	6	1	8														
		441C	10	3	2	25	4	4	3	1	1	8														
		442	9	5	9	25	4	4	2	2	2	2														
		443	1	8	12	1																				
		540A	8	1	40	1																				
		540B	7	7	36	1																				
		541A	19	2	18	1																				
		541B	16	5	18	1																				
		640A	9	11	3	1																				
		640B	4	6	3	1																				
		1040A	47	0	4	4			45	2	1	10														43
		1040B	60	0	4	1																				
		1040C	47	9	4	6			45	2	0	6	1	10	0	0									0	44

BRIDGE NO. 5

THE LPA GROUP
A UNIT OF MICHAEL BAKER CORPORATION

THE LPA GROUP INCORPORATED
TRANSPORTATION CONSULTANTS
3995 ENGINEERING DRIVE
NORCROSS, GEORGIA 30092
(770) 263-9118

GEORGIA
DEPARTMENT OF TRANSPORTATION
ENGINEERING DIVISION-OFFICE OF BRIDGES AND STRUCTURES

REVISIONS | DATE | BY

REINFORCEMENT SCHEDULE
JIMMY DELOACH CONNECTOR
OVER TRIBUTARY TO ST. AUGUSTINE CREEK
CHATHAM COUNTY CSMSL-0008-00(690)

DRAWING NO. 35-053
BRIDGE SHEET 16 OF 16

SCALE: NONE JULY 2013

DESIGNED JCW | CHECKED JPS/ANZ | REVIEWED DLC/WMD
DRAWN JCW/BSB | DESIGN GROUP SKG | APPROVED BFR

1 INCH WHEN PRINTED FULL SIZE

8/6/2013 1:40:38 PM R:\126379\Bridge\WETLANDS\final\B0516-RB.dgn