GEORGIA 811 Utilities Protection Center, Inc.
Know what's below. Call before you dig.

REVISION SUMMARY SHEET

DATE	SHEET NO.	DESCRIPTION

SUMMARY OF QUANTITIES

ITEM NO.	ITEM DESCRIPTION	QTY	UNITS
150-1000	TRAFFIC CONTROL	LS	LS
163-0232	TEMPORARY GRASSING	0.9	AC
163-0240	MULCH	3	TONS
165-0030	MAINT OF TEMPORARY SILT FENCE, TP C	450	LF
171-0030	TEMPORARY SILT FENCE, TYPE C	900	LF
207-0203	FOUND BKFILL MATL, TP II	10	CY
210-0100	GRADING COMPLETE	LS	LS
441-0104	CONC SIDEWALK, 4 IN	1475	SY
441-0303	CONC SPILLWAY, TP 3	1	EA
441-4030	CONC VALLEY GUTTER, 8 IN	75	SY
441-6222	CONC CURB & GUTTER, 8 IN X 30 IN,TP 2	2200	LF
500-9999	CLASS B CONC, BASE OR PVMT WIDENING	5	CY
550-1180	STORM DRAIN PIPE, 18 IN, H 1-10	328	LF
550-1240	STORM DRAIN PIPE, 24 IN, H 1-10	60	LF
550-1300	STORM DRAIN PIPE, 30 IN, H 1-10	12	LF
550-4218	FLAIRED END SECTION 18 IN, STORM DRAIN	1	EA
550-4224	FLAIRED END SECTION 24 IN, STORM DRAIN	1	EA
636-1033	HIGHWAY SIGNS, TP I MATL, REF SHEETING, TP 9	18	SF
636-2070	GALV STEEL POSTS, TP 7	28	LF
652-2501	SOLID TRAFFIC STRIPE, 5 IN, WHITE	0.42	LM
652-2502	SOLID TRAFFIC STRIPE, 5 IN, YELLOW	0.02	LM
653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	45	LF
653-1804	THERMOPLASTIC SOLID TRAF STRIPE, 8 IN, WHITE	1700	LF
668-1100	CATCH BASIN, GP1	5	EA
668-2100	DROP INLET, GP1	2	EA
668-5000	JUNCTION BOX	1	EA
706-1003	TURF ESTABLISHMENT, TP C	0.75	AC