

**PROJECT NOTES**

- A NOTICE OF INTENT IS NOT REQUIRED FOR THIS PROJECT. THE DISTURBED AREA IS: SR 124/SCENIC HWY 0.25 ACS., STONE MOUNTAIN ST. 0.70 ACS., SR 8/US 29/CROGAN ST. 0.42 ACS., AND LANGLEY DR. 0.03 ACS. TOTAL IS 1.40 ACRES. THE PROJECT INVOLVES INSTALLATION OF SIDEWALKS AND CURB RAMPS, AND STRIPING CROSSWALKS.
- ALL DRIVEWAYS THAT ARE TO BE RECONSTRUCTED SHALL BE PLACED IN KIND (I.E. ASPHALT FOR ASPHALT, CONCRETE FOR CONCRETE, AND ASPHALT FOR DIRT DRIVES). DRIVEWAYS ABOVE 15 PERCENT GRADE SHOULD BE REPLACED AS CONCRETE. DRIVEWAY RELOCATIONS ARE SHOWN FROM THE BEST AVAILABLE DATA. THE CONTRACTOR SHALL CONSTRUCT NEW DRIVEWAYS TO MATCH THE ACTUAL FIELD LOCATION OF EXISTING DRIVEWAYS OR AS LOCATED IN THE PLANS. RESIDENTIAL DRIVES SHALL BE 14 FEET WIDE AT THE THROAT UNLESS NOTED OTHERWISE IN THE PLANS. COMMERCIAL DRIVES SHALL BE 24 FEET WIDE UNLESS NOTED OTHERWISE IN THE PLANS. THE CONTRACTOR SHALL OBTAIN THE APPROVAL FROM THE ENGINEER PRIOR TO MAKING ANY REVISIONS TO LOCATION, WIDTH, AND/OR NUMBER OF DRIVES TO BE CONSTRUCTED. DRIVES SHALL BE CONSTRUCTED USING:  
 ASPHALT - RESIDENTIAL - ASPH CONC 9.5mm SUPERPAVE (165 LB/SY)  
 GRADED AGGREGATE BASE, 6"  
 ASPHALT - COMMERCIAL - ASPH CONC 9.5mm SUPERPAVE (165 LB/SY)  
 ASPH CONC 19mm SUPERPAVE (220 LB/SY)  
 GRADED AGGREGATE BASE, 8"  
 CONCRETE - RESIDENTIAL - DRIVEWAY CONCRETE, 6"  
 GRADED AGGREGATE BASE, 6"  
 CONCRETE - COMMERCIAL - DRIVEWAY CONCRETE, 8"  
 GRADED AGGREGATE BASE, 8"
- THERE IS NO SUITABLE PLACE TO BURY EXISTING CONSTRUCTION DEBRIS WITHIN THE PROJECT'S LIMITS. THE CONTRACTOR SHALL PROVIDE AN ENVIRONMENTALLY APPROVED SITE TO DISPOSE OF EXISTING CONSTRUCTION DEBRIS AT NO ADDITIONAL COST TO THE DEPARTMENT.
- ALL BORROW AND WASTE SITES FOR THIS PROJECT SHALL BE ENVIRONMENTALLY APPROVED PRIOR TO CONSTRUCTION ACTIVITIES OCCURRING IN THEM. ALL COMMON FILL OR EXCESS MATERIAL DISPOSED OUTSIDE THE PROJECT RIGHT OF WAY SHALL BE PLACED IN EITHER A PERMITTED SOLID WASTE FACILITY, A PERMITTED INERT WASTE LANDFILL OR IN AN ENGINEERED FILL. SEE SECTION 201 OF THE STANDARD SPECIFICATION AND SUPPLEMENTS THERETO FOR ADDITIONAL INFORMATION.
- ALL DETECTABLE WARNING SURFACES ARE TO BE THE COLOR YELLOW.
- REMOVAL OF EXISTING PAVEMENT MARKINGS SHALL BE DONE BY HYDROBLASTING. THE COST FOR THIS WORK TO BE INCLUDED IN THE PRICE BID FOR GRADING COMPLETE.
- SAFE, CLEARLY MARKED PEDESTRIAN AND VEHICULAR ACCESS TO ALL ADJACENT PROPERTIES MUST BE MAINTAINED THROUGHOUT THE DEMOLITION AND CONSTRUCTION PROCESS.
- LOCATIONS OF EXISTING BURIED UTILITY LINES SHOWN ON THE PLANS ARE BASED UPON BEST AVAILABLE INFORMATION AND ARE TO BE CONSIDERED APPROXIMATE. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE LOCATIONS OF UTILITY LINES IN AND ADJACENT TO THE WORK AREA. THE CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITY LINES AND APPURTENANCES DURING CONSTRUCTION.
- ALL EXISTING STORM DRAIN PIPES ARE TO REMAIN UNLESS OTHERWISE NOTED ON THE PLANS.

UTILITY OWNERS	
FACILITY	OWNER
PHONE	BELLSOUTH
PHONE	MC1 VERIZON
ELECTRIC	CITY OF LAWRENCEVILLE ELECTRIC
WATER	CITY OF LAWRENCEVILLE WATER
GAS	CITY OF LAWRENCEVILLE GAS
ELECTRIC	GEORGIA POWER DISTRIBUTION
ELECTRIC	GEORGIA POWER TRANSMISSION
WATER	GCDWR
PHONE	LEVEL 3 COMMUNICATIONS

**ENVIRONMENTAL RESOURCES IMPACT TABLE**

Resource Name/Type	Location	Side	Construction Activity	Permitted Activity	Controlling Criteria	Special Provision?	Comments including any permit expiration dates
Eligible Historic Resource - Baggett Residential Historic District	W Crogan St/US 29 Sta. 405+90 to Sta. 411+35	Left	Sidewalk construction, erosion control	None	Section 106	N/A	See Below Note 1
Environmental Resource- Intermittent Stream 1	Stone Mountain Street Sta. 320+85 to Sta. 320+90	Left/ Right	None	None	Section 404 of the Clean Water Act	N/A	See Below Note 2
Environmental Resource- Intermittent Stream 1 Buffer	Stone Mountain Street Sta. 320+60 to Sta. 321+21	Left/ Right	Sidewalk construction, erosion control	None	E&S Act (OCGA 12-7)	N/A	See Below Note 2
Environmental Resource- Intermittent Stream 2	Stone Mountain Street Sta. 320+85 to Sta. 322+32	Right	None	None	Section 404 of the Clean Water Act	N/A	See Below Note 2
Environmental Resource- Intermittent Stream 2 Buffer	Stone Mountain Street Sta. 320+60 to Sta. 322+36	Right	Sidewalk construction, erosion control	None	E&S Act (OCGA 12-7)	N/A	See Below Note 2

**Notes:**

- The contractor shall ensure that no land disturbing activities, including staging, construction, vehicular use, borrow or waste activities shall take place outside of the existing right-of-way within the boundaries of the Baggett Residential Historic District.
- The contractor shall ensure that no land disturbing activities, including staging, construction, vehicular use, borrow or waste activities shall take place within the boundaries of the IS 1 and IS 2.



Know what's below.  
Call before you dig.



**REVISION DATES**


STATE OF GEORGIA  
DEPARTMENT OF TRANSPORTATION  
OFFICE: PROGRAM DELIVERY  
**GENERAL NOTES**

DRAWING No. 04-001