

SUMMARY OF QUANTITIES

150-1000

TRAFFIC CONTROL
PI NO. 0009447 LUMP SUM

210-0100

GRADING COMPLETE
PI NO. 0009447 LUMP SUM

FOR PAVEMENT PATCHIGN ALONG NEW CURB AS DIRECTED BY ENGINEER

402-3130

RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP2 ONLY INCL BITUM MATL & H LIME
TOTAL 10 TN

441-0104

CONC SIDEWALK, 4 IN
TOTAL 100 SY

FOR INSTALLATION OF NEW SIDEWALK OR REPLACEMENT OF EXISTING SIDEWALK AS SHOWN ON THE PLANS OR AS DIRECTED BY ENGINEER

441-0108

CONC SIDEWALK, 8 IN
TOTAL 350 SY

FOR ADA RAMPS

441-0748

CONCRETE MEDIAN, 6 IN
TOTAL 72 SY

LUMPKIN STREET AT WILLEGE CIRCLE

441-5001

CONCRETE HEADER CURB, 4 IN, TP 1
TOTAL 150 LF

FOR MINOR PATCHING AROUND CURB RAMP INSTALLATIONS AS DIRECTED BY ENGINEER

441-5002

CONCRETE HEADER CURB, 6 IN, TP 2
TOTAL 150 LF

FOR MINOR PATCHING AROUND CURB RAMP INSTALLATIONS AS DIRECTED BY ENGINEER

441-6216

CONC CURB & GUTTER, 8 IN X 24 IN, TP 2
TOTAL 150 LF

FOR MINOR PATCHING AROUND CURB RAMP INSTALLATIONS AS DIRECTED BY ENGINEER

441-6222

CONC CURB & GUTTER, 8 IN X 30 IN, TP 2
TOTAL 150 LF

FOR MINOR PATCHING AROUND CURB RAMP INSTALLATIONS AS DIRECTED BY ENGINEER

500-3200

CLASS B CONCRETE
TOTAL 75 CY

653-1704

THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE
TOTAL 600 LF

653-1804

THERMOPLASTIC SOLID TRAF STRIPE, 8 IN, WHITE
TOTAL 3570 LF

653-6004

THERMOPLASTIC SOLID TRAF STRIPE, WHITE
TOTAL 36 SY

999-1500

INTEGRALLY COLORED HOT APPLIED SYNTHETIC ASPHALT (STAMPED ASPHALT)
TOTAL 970 SY

LOOP/PEL LEAD IN WIRE (SHIELDED, TWISTED/
1000 FT)*

TOTAL 4 REELS
--

*COST FOR THIS ITEM TO BE PAID FOR AS TRAFFIC SIGNAL INSTALLATION (647-1000). QUANTITY TO BE AS DIRECTED BY ENGINEER.

611-4001

RECONSTR MINOR DRAINAGE STR
TOTAL 1 EA

CHASE STREET AT BOULEVARD

611-8120

ADJUST WATER METER BOX TO GRADE
TOTAL 5 EA

AS SHOWN ON PLANS OR AS DIRECTED BY ENGINEER

163-0232

TEMPORARY GRASSING
TOTAL 1 AC

700-9300

SOD
TOTAL 150 SY

700-7000

AGRICULTURAL LIME
TOTAL 1 TN

700-8000

FERTILIZER MIXED GRADE
TOTAL 1 TN

700-8100

FERTILIZER NITROGEN CONTENT
TOTAL 5 LB

163-0240

MULCH
TOTAL 5 TN

171-0010

TEMPORARY SILT FENCE, TYPE A
TOTAL 1040 LF

165-0010

MAINTENANCE OF TEMPORARY SILT FENCE, TP A
TOTAL 520 LF

643-8200

BARRIER FENCE (ORANGE), 4 FT
TOTAL 715 LF

716-2000

EROSION CONTROL MAT, SLOPES
TOTAL 100 SY