

PROJECT SPECIFIC NOTES

1. PRIOR TO CLEARING AND CONSTRUCTION ACTIVITIES COMMENCING, THE CONTRACTOR SHALL PLACE THE ORANGE CONSTRUCTION/SAFETY BARRIER FENCE IN AREAS NOTED IN THE PLANS AS ENVIRONMENTALLY SENSITIVE AREAS (ESA) TO ENSURE THAT THE ESA IS NOT ADVERSELY IMPACTED DURING PROJECT CONSTRUCTION.

2. THIS PROJECT REQUIRES A NOTICE OF INTENT (NOI).

3. ALL BORROW AND WASTE SITES FOR THIS PROJECT SHALL BE ENVIRONMENTALLY APPROVED PRIOR TO CONSTRUCTION ACTIVITIES. ALL COMMON FILL OR EXCESS MATERIAL DISPOSED OUTSIDE THE PROJECT RIGHT OF WAY SHALL BE PLACED IN EITHER A PERMITTED SOLID WASTE FACILITY, A PERMITTED INERT WASTE LANDFILL OR IN AN ENGINEERED FILL.

4. ALL EXISTING DRAINAGE PIPES/STRUCTURES TO REMAIN UNLESS NOTED OTHERWISE.

5. ALL EXISTING DRAINAGE STRUCTURES WITHIN THE PROJECT LIMITS THAT ARE CLOGGED WITH DEBRIS WILL BE CLEANED OUT ACCORDING TO SPECIAL PROVISION SECTION 161.3.06 QUALITY ACCEPTANCE.

6. ANY LIMIT OF ACCESS FENCE IMPACTED BY CONSTRUCTION WILL BE REPLACED IN KIND.

1. AGL RESOURCES (AGL) - GAS  
CONTACT: MARTIN MAREK  
TELEPHONE: 404-584-3226  
NOTE: LOCATED THROUGHOUT (ROF)

6. DEKALB COUNTY WATERSHED MANAGEMENT (DCWM) - WATER & SEWER  
CONTACT: PAUL WEST  
TELEPHONE: 770-621-7290  
NOTE: LOCATED THROUGHOUT

2. AT&T (ATT) - TELEPHONE  
CONTACT: DOUG BOND  
TELEPHONE: 770-493-3718  
NOTE: ALL TELEPHONE IS ATT UNLESS OTHERWISE NOTED (ROF)

7. MEAG POWER (MP) - TRANSMISSION  
CONTACT: LAURA SCARBOROUGH  
TELEPHONE: 770-952-5445  
NOTE: LOCATED ALONG SNAPFINGER RD CROSSING 1-20 (ROF)

3. COMCAST (CC) - CATV  
CONTACT: VICTOR BRANNAN  
TELEPHONE: 770-559-2158  
NOTE: LOCATED THROUGHOUT (ROF)

8. DEKALB COUNTY TRAFFIC & SAFETY (DCTS) - TRAFFIC CONTROL  
CONTACT: VINCE COPPER  
TELEPHONE: 404-297-3946  
NOTE: LOCATED AT WESLEY CHAPEL RD AND PANOLA RD, AERIAL FACILITIES ONLY (RNA)

4. GEORGIA POWER (GP) - DISTRIBUTION  
CONTACT: JARRETT DAVIS  
TELEPHONE: 404-506-6597  
NOTE: LOCATED THROUGHOUT

9. GEORGIA D.O.T. (GDOT) - TRAFFIC CONTROL  
CONTACT: YANCY BACHMANN  
TELEPHONE: 404-635-8129  
NOTE: LOCATED ALONG 1-20 AND MILLER RD (RNA)

5. AGL NETWORKS (AGLN) - TELEPHONE  
CONTACT: GARY SWAFFORD  
TELEPHONE: 770-713-6451  
NOTE: LOCATED 200 FT EAST OF WESLEY CHAPEL RD CROSSING 1-20 (ROF)

PIPE CULVERT MATERIAL ALTERNATES FOR PIEDMONT/BLUE RIDGE REGION								
TYPE OF PIPE INSTALLATION	C O N C R E T E	CORRUGATED STEEL AASHTO M-36		CORRUGATED ALUMINUM AASHTO M-196	PLASTIC			
		ALUMINUM COATED (TYPE 2) CORR. STEEL	PLAIN ZINC COATED	PLAIN UNCOATED ALUMINUM	CORR. POLY-ETHYLENE AASHTO M-252	CORR. POLY-ETHYLENE SMOOTHED LINED AASHTO M-294 TYPE 'S'	POLY VINYL CHLORIDE (PVC) PROFILE WALL AASHTO M-304	POLY VINYL CHLORIDE (PVC) CORRUGATED SMOOTH INTERIOR AASHTO F-949
LONGITUDINAL INTERSTATE AND TRAVEL BEARING	X							
LONGITUDINAL NON-INTERSTATE AND NON-TRAVEL BEARING	X				X	X	X	
CROSS GRADE ≤ 10%	ADT < 250	X			X	X	X	
	250 < ADT < 1500	X			X	X	X	
	1500 < ADT < 15,000	X			X	X	X	
CROSS GRADE > 10%	ADT > 15,000	X						
	ADT < 250				X	X	X	
	ADT > 250				X	X	X	
SIDE DRAIN	X				X	X	X	
PERMANENT SLOPE DRAIN		X	X	X	X	X	X	
PERFORATED UNDERDRAIN		X	X	X	X	X	X	

NOTE:  
 1. ALLOWABLE MATERIALS ARE INDICATED BY AN "X".  
 2. STRUCTURAL REQUIREMENTS OF STORM DRAIN PIPE WILL BE IN ACCORDANCE WITH GEORGIA STANDARD 1030-D OR 1030-P, WHICHEVER IS APPLICABLE, AND THE STANDARD SPECIFICATIONS.  
 3. GRADED AGGREGATE BACKFILL SHALL BE USED IN CROSS DRAIN APPLICATIONS FOR ALL PLASTIC PIPES (AASHTO M-294, HDPE PIPE; AASHTO M-304, PVC PIPE; ASTM F-949, PVC PIPE).  
 4. THE CONTRACTOR SHALL PROVIDE ADDITIONAL STORM SEWER CAPACITY CALCULATIONS IF A PIPE MATERIAL OTHER THAN CONCRETE IS SELECTED.

REV. 09-03-08

AS-BUILT PLANS - 08/30/13



Know what's below.  
Call before you dig.



REVISION DATES			STATE OF GEORGIA DEPARTMENT OF TRANSPORTATION OFFICE: INNOVATIVE PROGRAM DELIVERY GENERAL NOTES	

DRAWING No. 04-001