

PROJECT SPECIFIC NOTES

1. PRIOR TO CLEARING AND CONSTRUCTION ACTIVITIES COMMENCING, THE CONTRACTOR SHALL PLACE THE ORANGE CONSTRUCTION/SAFETY BARRIER FENCE IN AREAS NOTED IN THE PLANS AS ENVIRONMENTALLY SENSITIVE AREAS (ESA) TO ENSURE THAT THE ESA IS NOT ADVERSELY IMPACTED DURING PROJECT CONSTRUCTION.

2. THIS PROJECT REQUIRES A NOTICE OF INTENT (NOI).

3. ALL BORROW AND WASTE SITES FOR THIS PROJECT SHALL BE ENVIRONMENTALLY APPROVED PRIOR TO CONSTRUCTION ACTIVITIES. ALL COMMON FILL OR EXCESS MATERIAL DISPOSED OUTSIDE THE PROJECT RIGHT OF WAY SHALL BE PLACED IN EITHER A PERMITTED SOLID WASTE FACILITY, A PERMITTED INERT WASTE LANDFILL OR IN AN ENGINEERED FILL.

4. ALL EXISTING DRAINAGE PIPES/STRUCTURES TO REMAIN UNLESS NOTED OTHERWISE.

5. ALL EXISTING DRAINAGE STRUCTURES WITHIN THE PROJECT LIMITS THAT ARE CLOGGED WITH DEBRIS WILL BE CLEANED OUT ACCORDING TO SPECIAL PROVISION SECTION 161.3.06 QUALITY ACCEPTANCE.

6. ANY LIMIT OF ACCESS FENCE IMPACTED BY CONSTRUCTION WILL BE REPLACED IN KIND.

1. AGL RESOURCES (AGL) - GAS
CONTACT: MARTIN MAREK
TELEPHONE: 404-584-3226
NOTE: LOCATED THROUGHOUT (ROF)

6. DEKALB COUNTY WATERSHED MANAGEMENT (DCWM) - WATER & SEWER
CONTACT: PAUL WEST
TELEPHONE: 770-621-7290
NOTE: LOCATED THROUGHOUT

2. AT&T (ATT) - TELEPHONE
CONTACT: DOUG BOND
TELEPHONE: 770-493-3718
NOTE: ALL TELEPHONE IS ATT UNLESS OTHERWISE NOTED (ROF)

7. MEAG POWER (MP) - TRANSMISSION
CONTACT: LAURA SCARBOROUGH
TELEPHONE: 770-952-5445
NOTE: LOCATED ALONG SNAPPINGER RD CROSSING I-20 (ROF)

3. COMCAST (CC) - CATV
CONTACT: VICTOR BRANNAN
TELEPHONE: 770-559-2158
NOTE: LOCATED THROUGHOUT (ROF)

8. DEKALB COUNTY TRAFFIC & SAFETY (DCTS) - TRAFFIC CONTROL
CONTACT: VINCE COPPER
TELEPHONE: 404-297-3946
NOTE: LOCATED AT WESLEY CHAPEL RD AND PANOLA RD, AERIAL FACILITIES ONLY (RNA)

4. GEORGIA POWER (GP) - DISTRIBUTION
CONTACT: JARRETT DAVIS
TELEPHONE: 404-506-6597
NOTE: LOCATED THROUGHOUT

9. GEORGIA D.O.T. (GDOT) - TRAFFIC CONTROL
CONTACT: YANCY BACHMANN
TELEPHONE: 404-635-8129
NOTE: LOCATED ALONG I-20 AND MILLER RD (RNA)

5. AGL NETWORKS (AGLN) - TELEPHONE
CONTACT: GARY SWAFFORD
TELEPHONE: 770-713-6451
NOTE: LOCATED 200 FT EAST OF WESLEY CHAPEL RD CROSSING I-20 (ROF)

PIPE CULVERT MATERIAL ALTERNATES FOR PIEDMONT/BLUE RIDGE REGION

TYPE OF PIPE INSTALLATION	C O N C R E T E	CORRUGATED STEEL AASHTO M-36		CORRU- GATED ALUMINUM AASHTO M-196	PLASTIC			
		ALUMINUM COATED (TYPE 2) CORR. STEEL	PLAIN ZINC COATED	PLAIN UNCOATED ALUMINUM	CORR. POLY- ETHYLENE AASHTO M-252	CORR. POLY- ETHYLENE SMOOTHED LINED AASHTO M-294 TYPE "S"	POLY VINYL CHLORIDE (PVC) PROFILE WALL AASHTO M-304	POLY VINYL CHLORIDE (PVC) CORRUGATED SMOOTH INTERIOR AASHTO F-949
LONGITUDINAL INTERSTATE AND TRAVEL BEARING	X							
LONGITUDINAL NON-INTERSTATE AND NON-TRAVEL BEARING	X					X	X	X
CROSS DRAIN	GRADE ≤ 10%	ADT < 250	X			X	X	X
		250 < ADT < 1500	X			X	X	X
		1500 < ADT < 15,000	X			X	X	X
DRAIN	GRADE > 10%	ADT > 15,000	X					
		ADT < 250				X	X	X
ADT > 250					X	X	X	
SIDE DRAIN	X					X	X	X
PERMANENT SLOPE DRAIN		X	X	X		X	X	X
PERFORATED UNDERDRAIN		X	X	X	X	X		X

NOTE:

- ALLOWABLE MATERIALS ARE INDICATED BY AN 'X'.
- STRUCTURAL REQUIREMENTS OF STORM DRAIN PIPE WILL BE IN ACCORDANCE WITH GEORGIA STANDARD 1030-D OR 1030-P, WHICHEVER IS APPLICABLE, AND THE STANDARD SPECIFICATIONS.
- GRADED AGGREGATE BACKFILL SHALL BE USED IN CROSS DRAIN APPLICATIONS FOR ALL PLASTIC PIPES (AASHTO M-294, HDPE PIPE; AASHTO M-304, PVC PIPE; ASTM F-949, PVC PIPE).
- THE CONTRACTOR SHALL PROVIDE ADDITIONAL STORM SEWER CAPACITY CALCULATIONS IF A PIPE MATERIAL OTHER THAN CONCRETE IS SELECTED.

REV. 09-03-08

RELEASED FOR CONSTRUCTION - 12/05/11



Know what's below.
Call before you dig.



A UNIT OF MICHAEL BAKER CORPORATION
3595 ENGINEERING DRIVE
NORCROSS, GEORGIA 30092
(770) 263-9118

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: INNOVATIVE PROGRAM DELIVERY
GENERAL NOTES

DRAWING No.
04-001