

RELEASED FOR CONSTRUCTION - 12/05/11

<p>TYPE A WOOD POST (FOR "W" BEAM GUARDRAIL)</p> <p>NOTE: WOOD POST ARE ALLOWABLE ONLY WHERE SPECIFIED.</p> <p>FRONT SIDE</p> <p>SCALE 0' 6' 1 FT.</p> <p>NOTE: OFFSET FROM TOP OF POST TO CENTER OF 3/4" DIA. HOLE(S) WILL BE DETERMINED BY LENGTH OF OFFSET BLOCK: I.E., 7" FOR 14" LENGTH BLOCKS AND 6 3/8" FOR 13 1/4" LENGTH BLOCKS.</p> <p>NOTE: OFFSET BLOCK AND RAIL (SEE STD. 4010).</p> <p>27" (+/- 1") (TOP OF RAIL HEIGHT)</p> <p>HOLE(S) IF BREAKAWAY POSTS ARE SPECIFIED (SEE STANDARDS FOR ANCHORAGE.)</p> <p>SEE SEPARATE STANDARD OR DETAIL FOR POSTS IN TUBE SLEEVE.</p>	<p>TYPE D STEEL POST (FOR "W" BEAM GUARDRAIL)</p> <p>FRONT SIDE</p> <p>SCALE 0' 6' 1 FT.</p> <p>NOTE: OFFSET FROM TOP OF POST TO CENTER OF 3/4" DIA. HOLE(S) WILL BE DETERMINED BY LENGTH OF OFFSET BLOCK: I.E., 7" FOR 14" LENGTH BLOCKS AND 6 3/8" FOR 13 1/4" LENGTH BLOCKS.</p> <p>NOTE: OFFSET BLOCK AND RAIL (SEE STD. 4270).</p> <p>27" (+/- 1") (TOP OF RAIL HEIGHT)</p> <p>HOLE(S) IF BREAKAWAY POSTS ARE SPECIFIED (SEE STANDARDS FOR ANCHORAGE.)</p> <p>SEE SEPARATE STANDARD OR DETAIL FOR POSTS IN TUBE SLEEVE.</p>	<p>TYPE D-T STEEL POST (FOR "T" BEAM GUARDRAIL)</p> <p>FRONT SIDE</p> <p>SCALE 0' 6' 1 FT.</p> <p>NOTE: OFFSET FROM TOP OF POST TO CENTER OF 3/4" DIA. HOLE(S) WILL BE DETERMINED BY LENGTH OF OFFSET BLOCK: I.E., 7" FOR 14" LENGTH BLOCKS AND 6 3/8" FOR 13 1/4" LENGTH BLOCKS.</p> <p>NOTE: OFFSET BLOCK AND RAIL (SEE STD. 4270).</p> <p>27" (+/- 1") (TOP OF RAIL HEIGHT)</p> <p>HOLE(S) IF BREAKAWAY POSTS ARE SPECIFIED (SEE STANDARDS FOR ANCHORAGE.)</p> <p>SEE SEPARATE STANDARD OR DETAIL FOR POSTS IN TUBE SLEEVE.</p>																				
<p>GENERAL NOTES:</p> <ol style="list-style-type: none"> SPECIFICATIONS GEORGIA STANDARD, CURRENT EDITION AND SUPPLEMENTS THERETO. STEEL POSTS MAY BE EITHER ROLLED OR WELDED STRUCTURAL SHAPES. STEEL OFFSET BLOCKS SHALL BE ROLLED, WELDED POSTS SHALL BE SEAL WELDED BETWEEN WEB AND FLANGE BEFORE GALVANIZING. WHERE WOOD POST OR WOOD OFFSET BLOCKS ARE PERMITTED, THE WOOD SHALL BE TREATED IN ACCORDANCE WITH GEORGIA STANDARD SPECIFICATIONS. ALL BOLTS USED FOR FASTENING THE RAIL AND OFFSET BLOCKS TO WOOD POSTS SHALL HAVE SUFFICIENT LENGTH TO EXTEND AT LEAST 1/4" BEYOND THE FULL NUT, UP TO 3" BEYOND. (a) "W" BEAM GUARDRAIL: ALL OFFSET BLOCKS SHALL BE 8" DEPTH PLASTIC BLOCKS EXCEPT FOR (d) BELOW. (b) "T" BEAM GUARDRAIL: STANDARD INSTALLATION WILL USE 8" DEPTH PLASTIC BLOCKS UNLESS OTHERWISE APPROVED. (c) 13 3/4" DEPTH MODIFIED STEEL OFFSETS MAY BE SPECIFIED WHERE JUSTIFIED FOR MORE SEVERE CONDITIONS. PAY ITEM IS --GUARDRAIL, TP, T, MODIFIED OFFSET BLOCK-- PER LIN. FT. (d) WOOD OFFSET BLOCKS MAY BE USED ONLY AT AN ISOLATED LOCATION WITHIN A RUN OF GUARDRAIL, WHERE OTHER BLOCK TYPES WOULD NOT PROVIDE PROPER FIT, AS DETERMINED BY THE ENGINEER OR SHOWN IN THE PLANS. POSTS WILL BE SPACED AT 6'-3" C. TO C., UNLESS OTHERWISE NOTED. ADDITIONAL LENGTH POSTS, WHERE SPECIFIED, SHALL BE 7'-0" AND 7'-6" LONG FOR "W" BEAM AND "T" BEAM GUARDRAILS RESPECTIVELY, WITH HOLES DIMENSIONED FROM THE POST-TOP THE SAME AS SHOWN. 																						
<p>MODIFIED STEEL OFFSET BLOCK FOR "T" BEAM GUARDRAIL</p> <p>NOTE: MODIFIED STEEL OFFSET BLOCKS ARE USED ONLY WHERE SPECIFIED SEE NOTE 5(c)</p> <p>FRONT SIDE BACK</p> <p>SCALE 0' 6' 1 FT.</p> <p>WOOD POSTS AND WOOD OFFSET BLOCKS MAY BE ROUGH OR SURFACED.</p> <p>WOOD POSTS AND WOOD OFFSET BLOCKS DIMENSIONS FOR WOOD POSTS AND WOOD OFFSET BLOCKS ARE NOMINAL IN ACCORDANCE WITH ACCEPTED LUMBER INDUSTRY STANDARDS.</p>																						
<p>BACK-UP PLATE (FOR "T" BEAM GUARDRAIL)</p> <p>NOTE: BACK-UP PLATES ARE REQUIRED WITH ALL STEEL OFFSET BLOCKS EXCEPT AT RAIL SPLICES OR WHERE ONE RAIL SECTION IS NESTED INSIDE ANOTHER RAIL SECTION. BACK-UP PLATE WILL BE LOCATED BACK OF RAIL ADJACENT TO OFFSET BLOCKS (INSIDE MAIN RAIL).</p> <p>FRONT</p> <p>SCALE 0' 6' 1 FT.</p>																						
<p>WOOD OFFSET BLOCKS (WHERE PERMITTED, SEE NOTE 5(d))</p> <p>FRONT OR BACK (FOR "W" BEAM) FRONT OR BACK (FOR "T" BEAM)</p> <p>SCALE 0' 6' 1 FT.</p> <p>(PLAN VIEW IS SAME AS SHOWN FOR WOOD POST ABOVE)</p>																						
<p>STANDARD PLASTIC OFFSET BLOCKS</p> <p>NOTE: PLASTIC OFFSET BLOCKS SHALL BE OF TYPE LISTED IN GA. DOT OPL OF APPROVED PRODUCTS OR PER STANDARD SPECIFICATIONS.</p> <p>PLAN BACK VIEW (FOR "W" BEAM) BACK VIEW (FOR "T" BEAM)</p> <p>SCALE 0' 6' 1 FT.</p> <p>NOTE: DIMENSIONS ARE SUBJECT TO MANUFACTURER'S TOLERANCES.</p>																						
<p>HEIGHT CORRECTION IF NEEDED FOR RESURFACED PROJECTS</p> <p>STEPS: (a) REMOVE OFFSET BLOCKS FROM POSTS. (b) ELEVATE BLOCK TO PROVIDE REQ'D. RAIL HEIGHT AND RECONNECT WITH 2 BOLTS THRU SAME HOLES IN POST TO THE LOWER HOLES IN OFFSET BLOCKS.</p>																						
<p>CONCRETE FOUNDATION FOR POST IN SHALLOW FILLS OVER CULVERTS OR OTHER OBSTRUCTIONS</p> <p>(NOTE: PLATE MOUNTED POST MAY BE USED AS AN ALTERNATE, SEE SEPARATE SHEET.)</p>																						
<p>COMPOSITE OFFSET BLOCKS (FOR "W" BEAM)</p> <p>NOTE: 1. COMPOSITE OFFSET BLOCKS SHALL BE OF TYPE LISTED IN GA. DOT OPL OF APPROVED PRODUCTS OR PER STANDARD SPECIFICATIONS.</p> <ol style="list-style-type: none"> UNIFORM WALL THICKNESS OF 0.375". UNSPECIFIED CORNERS TO BE 0.050" MIN. UNSPECIFIED TOLERANCES TO BE 0.050". <p>FRONT PLAN SIDE</p> <p>SCALE 0' 6' 1 FT.</p> <p>NOTE: ADDITIONAL DEPTH OFFSETS BELOW ARE SHOWN FOR "W" BEAM. SIMILAR OFFSETS MAY BE APPLIED FOR "T" BEAM GUARDRAIL.</p> <p>NOTE: ADDITIONAL DEPTH OFFSETS ARE PERMITTED ONLY WHERE AN ISOLATED POST MUST BE PLACED AT A GREATER THAN NORMAL OFFSET.</p> <p>NOTE: FOR BLOCK CONNECTION TO POST AND TO RAIL SEE STD. 4010 OR 4270.</p>																						
<p>ADDITIONAL DEPTH OFFSET BLOCKOUTS (FOR USE WHERE GREATER THAN STANDARD OFFSET IS SPECIFIED)</p>																						
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 10%;"></td> <td style="width: 10%;">DATE</td> <td colspan="2" style="text-align: center;">DEPARTMENT OF TRANSPORTATION STATE OF GEORGIA</td> </tr> <tr> <td style="width: 10%;"></td> <td style="width: 10%;">REVISION</td> <td colspan="2" style="text-align: center;">STANDARD POSTS AND OFFSET BLOCKS FOR "W" & "T" BEAM GUARDRAIL (REPLACES STANDARDS 4011 & 4271)</td> </tr> <tr> <td style="width: 10%;"></td> <td style="width: 10%;">BY</td> <td style="width: 40%;">SCALE: AS SHOWN</td> <td style="width: 10%;">REVISED & REDRAWN DEC., 1999</td> </tr> <tr> <td style="width: 10%;"></td> <td style="width: 10%;">DATE</td> <td style="width: 40%;">(SUBMITTED) <i>James H. Kneel</i> STATE ROAD & AIRPORT DESIGN ENGINEER</td> <td style="width: 10%;">NUMBER</td> </tr> <tr> <td style="width: 10%;"></td> <td style="width: 10%;">DATE</td> <td style="width: 40%;">(APPROVED) <i>Carol L. Frazier</i> CHIEF ENGINEER</td> <td style="width: 10%;">4011A</td> </tr> </table>				DATE	DEPARTMENT OF TRANSPORTATION STATE OF GEORGIA			REVISION	STANDARD POSTS AND OFFSET BLOCKS FOR "W" & "T" BEAM GUARDRAIL (REPLACES STANDARDS 4011 & 4271)			BY	SCALE: AS SHOWN	REVISED & REDRAWN DEC., 1999		DATE	(SUBMITTED) <i>James H. Kneel</i> STATE ROAD & AIRPORT DESIGN ENGINEER	NUMBER		DATE	(APPROVED) <i>Carol L. Frazier</i> CHIEF ENGINEER	4011A
	DATE	DEPARTMENT OF TRANSPORTATION STATE OF GEORGIA																				
	REVISION	STANDARD POSTS AND OFFSET BLOCKS FOR "W" & "T" BEAM GUARDRAIL (REPLACES STANDARDS 4011 & 4271)																				
	BY	SCALE: AS SHOWN	REVISED & REDRAWN DEC., 1999																			
	DATE	(SUBMITTED) <i>James H. Kneel</i> STATE ROAD & AIRPORT DESIGN ENGINEER	NUMBER																			
	DATE	(APPROVED) <i>Carol L. Frazier</i> CHIEF ENGINEER	4011A																			

THE LPA GROUP

TRANSPORTATION CONSULTANTS

A UNIT OF MICHAEL BAKER CORPORATION

3595 ENGINEERING DRIVE
NORCROSS, GEORGIA 30092
(770) 263-9118

<p>STATE OF GEORGIA DEPARTMENT OF TRANSPORTATION OFFICE: INNOVATIVE PROGRAM DELIVERY GEORGIA STANDARDS</p>	<p>REVISION DATES</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 5%;">NO.</td> <td style="width: 15%;">DATE</td> <td style="width: 80%;">DESCRIPTION</td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> </table>	NO.	DATE	DESCRIPTION									
NO.	DATE	DESCRIPTION											
DRAWING No. 41-016													