

ATMS NOTES

1. THE CONTRACTOR SHALL LOCATE ALL UTILITIES BEFORE DIGGING TO ELIMINATE ANY CONFLICTS. TO OBTAIN HIGHWAY LIGHTING PLANS, THE CONTRACTOR SHALL CONTACT THE DEPARTMENT AT (404) 631-1642. TO OBTAIN DRAINAGE PLANS, THE CONTRACTOR SHALL CONTACT THE DEPARTMENT'S FILE PLANS ROOM AT (404) 631-1531. FOR GDOT ATMS FACILITIES THAT MAY BE IMPACTED, THE CONTRACTOR SHALL CONTACT THE GDOT ITS MANAGER AT (404) 694-6613.

2. WITHIN 24 HOURS, THE CONTRACTOR SHALL REPAIR ANY EXISTING CONDUIT, CABLE, OR PIPE THAT IS DAMAGED BY ANY WORK PERFORMED AS PART OF THIS PROJECT AT NO ADDITIONAL COST TO THE DEPARTMENT.

3. THE CONTRACTOR SHALL REPLACE IN LIKE KIND AND SIZE, AT NO ADDITIONAL COST TO THE DEPARTMENT, ANY PAVEMENT MARKINGS, BARRIER WALL, FENCE, DITCH PAVING, CURBING, SIDEWALK, GUTTER, SLOPE PAVEMENT, SIGNS, GUARDRAIL, LANDSCAPING (IN ACCORDANCE WITH GEORGIA SPECIFICATIONS SECTION 702), GRASSING (IN ACCORDANCE WITH GEORGIA SPECIFICATIONS SECTION 700), UTILITY SERVICE LINES, STORM DRAIN PIPES, RUMBLE STRIPS, ROADWAY, AND ANY RETAINING WALLS THAT ARE DAMAGED OR DESTROYED BY ANY WORK PERFORMED AS PART OF THIS PROJECT. THE CONTRACTOR WILL NOT BE REQUIRED TO MAINTAIN LANDSCAPING AS SPECIFIED IN SECTION 702.3.07 OF THE GEORGIA SPECIFICATIONS.

4. THE CONTRACTOR SHALL REMOVE PAVEMENT BY SAW CUT TO PROVIDE A NEAT LINE. WHERE CONDUIT IS INSTALLED, THE CONTRACTOR SHALL INLAY TO MATCH EXISTING SURFACE TYPE AFTER CONDUIT IS INSTALLED. PAVEMENT REMOVAL AND PAVEMENT INLAY SHALL BE INCLUDED IN THE BID PRICE FOR CONDUIT DUCT BANK OR CONDUIT.

5. PAYMENT FOR TYPE 2 CONDUIT FOR ELECTRIC POWER SERVICE INCLUDES ALL MATERIALS AND LABOR TO PROVIDE A CONNECTION BETWEEN THE SERVICE POINTS AND THE EQUIPMENT CABINETS.

6. ALL PROPOSED STRAIN POLES SHALL BE INSTALLED A MINIMUM OF 6 FEET BEHIND EXISTING OR PROPOSED GUARDRAIL WHERE SHOWN ON THE PLANS.

7. CABINETS, CAMERAS, CONTROLLERS AND OTHER ELECTRONIC DEVICES THAT ARE REMOVED AS PART OF THIS PROJECT SHALL BE RETURNED TO THE GDOT TRAFFIC SIGNALS AND ELECTRICAL FACILITIES BUILDING AT 935 EAST CONFEDERATE AVENUE, BUILDING 5, ATLANTA, GA 30316 AT NO ADDITIONAL COST TO THE DEPARTMENT. THE CONTRACTOR SHALL CALL THE STATE SIGNAL ENGINEER AT (404) 624-7119 AT LEAST 72 HOURS IN ADVANCE TO ARRANGE DELIVERY OF THESE COMPONENTS.

8. WHERE NEW FIBER OPTIC CABLE IS INSTALLED IN EXISTING ELECTRICAL COMMUNICATION BOXES, CONTRACTOR SHALL INSTALL CABLE RACKS AT NO EXTRA COST IF THERE ARE NONE EXISTING.

9. UPON COMPLETION OF CONSTRUCTION ACTIVITIES THE CONTRACTOR WILL PROVIDE AS-BUILT PLANS THAT INCLUDE THE LOCATION OF INSTALLED FIBER, ELECTRICAL COMMUNICATION BOXES (ECBS), PULL BOXES, CONDUIT LOCATION AND DEPTH, AND POWER LEADS.