SUMMARY OF QUANTITIES

150-1000 TRAFFIC CONTROL - 0010291	
UNIT	QUANTITY
LUMP	LUMP

210-0100 GRADING COMPLETE - 0010291	
UNIT	QUANTITY
LUMP	LUMP

615-1200 DIRECTIONAL BORE, 3 IN	
UNIT	QUANTITY
LF	125

615-1200 DIRECTIONAL BORE, 6 IN	
UNIT	QUANTITY
LF	78219

639-3014 STEEL STRAIN POLE, TYPE IV, WITH 45 FT MAST ARM	
UNIT	QUANTITY
EACH	1

639-3014 STEEL STRAIN POLE, TYPE IV, WITH 50 FT MAST ARM	
UNIT	QUANTITY
EACH	1

639-4004 STRAIN POLE, TYPE IV	
UNIT	QUANTITY
EA	14

647-2141 PULL BOX, PB-4S	
UNIT	QUANTITY
EACH	21

647-2170 PULL BOX, PB-7	
UNIT	QUANTITY
EACH	102

653-1704 THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	
UNIT	QUANTITY
LF	66

653-3501 THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	
UNIT	QUANTITY
GLF	1100

682-6233 CONDUIT, NONMETL, TP 3, 2 IN	
UNIT	QUANTITY
LF	5441

682-6222 CONDUIT, NONMETL, TP 2, 2 IN	
UNIT	QUANTITY
LF	130

682-6236 CONDUIT, NONMETL, TP 2, 2 IN*	
UNIT	QUANTITY
LF	25319

* CONDUIT FOR ELECTRIC POWER SERVICE. INCLUDES ALL WORK AND MATERIALS NECESSARY FOR POWER SERVICE FROM THE UTILITY DEMARCATION POINT TO THE EQUIPMENT CABINET(S).

682-7062 CONDUIT, DUCT BANK, TYPE 3	
UNIT	QUANTITY
LF	72778

935-1111 OSP F/O CABLE, LOOSE TUBE, SM, 6 FIBER	
UNIT	QUANTITY
LF	4757

935-1113 OSP F/O CABLE, LOOSE TUBE, SM, 24 FIBER	
UNIT	QUANTITY
LF	383

935-1118 OSP F/O CABLE, LOOSE TUBE, SM, 144 FIBER	
UNIT	QUANTITY
LF	85011

935-1512 OSP F/O CABLE, DROP, SM, 12 FIBER	
UNIT	QUANTITY
LF	975

935-3101 F/O CLOSURE, UNDERGROUND, 6 FIBER	
UNIT	QUANTITY
EA	13

935-3102 F/O CLOSURE, UNDERGROUND, 12 FIBER	
UNIT	QUANTITY
EA	17

935-3103 F/O CLOSURE, UNDERGROUND, 24 FIBER	
UNIT	QUANTITY
EA	1

935-3108 F/O CLOSURE, UNDERGROUND, 144 FIBER	
UNIT	QUANTITY
EA	18

935-3602 F/O CLOSURE, FDC, PRE-TERMINATED, TYPE A, 6-FIBER	
UNIT	QUANTITY
EA	3

935-3603 F/O CLOSURE, FDC, PRE-TERMINATED, TYPE A, 12-FIBER	
UNIT	QUANTITY
EA	12

935-4010 F/O SPLICE, FUSION	
UNIT	QUANTITY
EA	942

935-8000 TESTING - 0010291	
UNIT	QUANTITY
LUMP	LUMP

936-1001 CCTV SYSTEM, TYPE B	
UNIT	QUANTITY
EA	3

936-8000 TESTING - 0010291	
UNIT	QUANTITY
LUMP	LUMP

937-6000 MICROWAVE RADAR DETECTION ASSEMBLY	
UNIT	QUANTITY
EA	10

937-6050 INTERSECTION VIDEO DETECTION SYSTEM ASSEMBLY, TYPE A	
UNIT	QUANTITY
EA	3

937-8030 TESTING - 0010291	
UNIT	QUANTITY
LUMP	LUMP

937-8530 TESTING - 0010291	
UNIT	QUANTITY
LUMP	LUMP

939-1191 VIDEO ENCODER TYPE B	
UNIT	QUANTITY
EA	3

939-2237 GBIC, TYPE D	
UNIT	QUANTITY
EA	1

939-2240 GBIC, TYPE E	
UNIT	QUANTITY
EA	1

GEORGIA
DEPARTMENT OF TRANSPORTATION

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY
SUMMARY OF QUANTITIES

DRAWING No. 6-001

3/1/2007 GQUANT