

SIGN AND STRIPING GENERAL NOTES

1. All standard highway signs shall be fabricated and erected in accordance with the details shown in the plans, the Manual on Uniform Traffic Control Devices, Current Edition, and the Georgia Specifications, supplemental specifications, and/or special provisions.
2. Sign erection stations are approximate and may be adjusted to meet field conditions where necessary, but shall be within the limitations set forth in the Manual on Uniform Traffic Control Devices, Current Edition. No sign location shall be changed by the contractor or by the project engineer without prior approval from the Office of Traffic Safety and Design.
3. All standard highway signs shall be erected at a height of 7 feet above the normal edge of pavement to the bottom of the sign or assembly.
- 4a. Horizontal clearance for standard highway signs on interstate highways shall be 32 feet from the normal edge of pavement to the nearer edge of the sign(s), unless specified otherwise in the plans. Horizontal clearance for standard highway signs on ramps shall be 2 feet from the normal edge of paved shoulder or edge of graded shoulder when present.
- 4b. Horizontal clearance for standard highway signs on all other roadways shall be 6 feet from the edge of the paved shoulder or 12 feet from the normal edge of pavement to the nearer edge of the sign(s), whichever is greater. The horizontal clearance in non-mountable curb sections shall be at least 2 feet from the curb face to the nearer edge of the sign(s).
- 4c. Horizontal clearance for standard highway signs mounted behind guardrail shall be 6 feet from the face of the guardrail to the nearer edge of the sign(s).
5. Single plate, horizontal rectangular signs over 48 inches in width shall be mounted on two posts with 2 each, 2 inch x 1/2 inch x (width of sign) aluminum or galvanized steel straps. The straps shall be flush with the back of the sign with one each across the top and bottom of the sign. The centerline of each post shall be inset 1/6th of the sign width from the edge of the sign. Sign plate bolt holes shall be 3/8 inch diameter, drilled or punched, as shown on the sign plate details.
6. Each 42 inch or 48 inch wide x 18 inch or 24 inch high sign requires one 2 inch x 1/2 inch x (width of sign) aluminum or galvanized steel strap located in the center of the sign and flush with the back of the sign.
7. Sign assemblies shall be mounted on aluminum or galvanized steel strap frames. For details and strap specifications, refer to sign assembly typical framing details.
8. Type 3 (High Intensity) reflective sheeting shall be used for all standard highway signs requiring reflectorized backgrounds except as specified below or specified otherwise in the plans. Either class 1 or class 2 adhesive backing is permissible.
9. Type 11 (Very High Intensity) reflective sheeting shall be used for all red series signs (R1-1, R1-2, R1-3p, R5-1, R5-1a, and R5-1b).
10. Type 9 (Very High intensity) fluorescent yellow green reflective sheeting shall be used for school zone (S1-1, S2-1, S3-1, S4-3, and the top portion of the S5-1) signs, bicycle crossing (W11-1) signs, and pedestrian crossing (W11-2 and W1A-2) signs. Signs within the same assembly as the school zone signs specifically listed above and all regulatory signs placed as part of the school zone signing shall have Type IX (Very High Intensity) reflective sheeting backgrounds of the appropriate color.
11. Type 9 (Very High Intensity) fluorescent yellow reflective sheeting shall be used for all warning signs.
12. A 1/2 inch minimum air space shall be required between all sign plates within an assembly.
13. Where signs within an assembly extend below the standard mounting holes on the post(s), additional 3/8 inch diameter hole(s), drilled or punched, shall be required to properly mount the assembly.
14. Interstate shields shall contain the word Georgia. All interstate, U.S. and Georgia shields requiring Alt, Bus, Conn, Loop or Spur shall use 4 inch series "D" letters. Refer to the Manual on Uniform Traffic Control Devices, Current Edition, for details.
15. For details of special design highway signs, see details of miscellaneous signs.
16. The Contractor will, as requested by District Traffic Operations Engineer, be required to remove any existing signs that are duplicated or are contrary to these sign plans.

		 <p style="font-size: small;">400 NORTHPARK TOWN CENTER 1000 ABERNATHY ROAD, N.E., SUITE 900 ATLANTA, GEORGIA 30328 TEL: (678) 808-8800 FAX: (678) 808-8400</p>	<table border="1" style="width:100%; border-collapse: collapse;"> <tr><th colspan="2">REVISION DATES</th></tr> <tr><td> </td><td> </td></tr> </table>	REVISION DATES												<p style="font-size: small;">STATE OF GEORGIA DEPARTMENT OF TRANSPORTATION</p> <p>OFFICE: PROGRAM DELIVERY</p> <p>GENERAL NOTES</p> <p style="font-size: small;">SR 8 (Ponce de Leon Avenue) Pedestrian Safety Improvement</p>
REVISION DATES																
6/20/2011 GPLM				DRAWING No. 04-003												