

1. A NOTICE OF INTENT (NOI) FOR STORMWATER DISCHARGE IS REQUIRED FOR THIS PROJECT.
2. ALL EXISTING PIPES SHALL BE RETAINED UNLESS OTHERWISE NOTED.
3. NO CONSTRUCTION OR GROUND DISTURBING ACTIVITY SHALL OCCUR BEYOND THE ORANGE BARRIER FENCE OR IN ANY ENVIRONMENTALLY SENSITIVE AREA DESIGNATED ON THE PLANS.
4. ALL AREAS THAT ARE NOT IMPERVIOUS SHOULD BE GRADED TO DRAIN AND GRASSED.
5. THE CONTRACTOR IS REQUIRED TO PROVIDE A LEVEL IA CERTIFIED WORKSITE EROSION CONTROL SUPERVISOR (WECS) WHO SHALL BE ONSITE AT ALL TIMES DURING LAND DISTURBING ACTIVITIES. STATE WATERS MAY OR MAY NOT BE IDENTIFIED IN THESE CONTRACTS. THIS CERTIFIED INDIVIDUAL SHALL BE ABLE TO IDENTIFY THESE WATERS AND USE SOUND CONSERVATION AND ENGINEERING PRACTICES, ALONG WITH SAFE AND EFFECTIVE CHANGES TO OPERATION, IN ORDER TO REDUCE AND MINIMIZE EROSION AND IMPACT TO THESE WATERS AND SURROUNDING ENVIRONMENT. ANY REQUIRED CLEARING IN CLOSE PROXIMITY TO A STATE WATER SHALL NOT INVOLVE GRUBBING AND SHALL BE LIMITED TO TRIMMING OF BRANCHES.
6. THE TOTAL PROJECT SIZE IS 5.304 ACRES.
7. THE TOTAL DISTURBED AREA SIZE IS 3.89 ACRES.
8. ALL BORROW AND WASTE SITES FOR THIS PROJECT SHALL BE ENVIRONMENTALLY APPROVED PRIOR TO CONSTRUCTION ACTIVITIES OCCURRING IN THEM. ALL COMMON FILL OR EXCESS MATERIAL DISPOSED OUTSIDE THE PROJECT RIGHT OF WAY SHALL BE PLACED IN EITHER A PERMITTED SOLID WASTE FACILITY, A PERMITTED INERT WASTE LANDFILL, OR IN AN ENGINEERED FILL. : SEE SECTION 201 OF THE STANDARD SPECIFICATION AND SUPPLEMENTS THERTO FOR ADDITIONAL INFORMATION
9. ALL SIGNS/POSTS/STUBS REMOVED AS PART OF THIS PROJECT SHALL BE RETURNED TO THE DISTRICT 5 BULLOCH COUNTY ROUTINE MAINTENANCE HEADQUARTERS AT 622 EAST OLLIFF STREET IN STATESBORO, GEORGIA 30458 AT NO ADDITIONAL COST TO THE DEPARTMENT. THE CONTRACTOR SHALL CALL THE STATESBORO AREA OFFICE AT (912) 871-1103 AT LEAST 72 HOURS IN ADVANCE TO ARRANGE DELIVERY OF THESE COMPONENTS.
10. THERE IS NO SUITABLE PLACE TO BURY EXISTING CONSTRUCTION DEBRIS WITHIN THE PROJECT LIMITS. THE CONTRACTOR SHALL PROVIDE AN ENVIRONMENTALLY APPROVED SITE TO DISPOSE OF EXISTING CONSTRUCTION DEBRIS AT NO ADDITIONAL COST TO THE DEPARTMENT.

11. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE FUNCTIONALITY OF ALL DRAINAGE STRUCTURES WITHIN THE LIMITS OF THE PROJECT THROUGHOUT THE DURATION OF THE PROJECT. ANY DEBRIS THAT GOES IN A DRAINAGE STRUCTURE AS A RESULT OF THE CONTRACTOR'S OPERATIONS SHALL BE CLEANED OUT BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE DEPARTMENT.
12. THE EXISTING RUMBLE STRIPS ALONG BURKHALTER ROAD LOCATED APPROXIMATELY 750 FEET IN ADVANCE OF THE SR 26 MAINLINE SIGN WITH FLASHING BEACONS SHALL BE REMOVED. THE COST FOR REMOVAL AND RESURFACING THE ROADWAY SHALL BE INCLUDED IN GRADING COMPLETE.
13. WCR's WITHIN THE RADII SHALL BE 8" CONCRETE.

**DRIVEWAYS**

All driveways that are to be reconstructed shall be replaced in kind, i.e. asphalt for asphalt and concrete for concrete. All driveways are to be paved to Right-of-Way line. The contractor shall construct new driveways to match the actual field location of existing driveways or as located in the plans. Residential drives shall be 14 feet wide at the throat unless otherwise noted in the plans. The contractor shall obtain the approval from the engineer prior to making any revisions to location, width, and/or numbers of drives to constructed.

ASPHALT AND EARTH DRIVES RESIDENTIAL: 165 lb/sy RECYCLED ASPH. CONC. 12.5 mm, SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME  
 6" GRADED AGGREGATE BASE, INCL MATL

COMMERCIAL: 165 lb/sy RECYCLED ASPH. CONC. 12.5 mm, SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME  
 220 lb/sy RECYCLED ASPH. CONC. 19 mm, SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME  
 6" GRADED AGGREGATE BASE, INCL MATL



UTILITY OWNER	SERVICE
GEORGIA POWER DISTRIBUTION	ELECTRICAL
EXCELSIOR EMC	POWER
BULLOCH RURAL TELEPHONE	TELEPHONE
FRONTIER COMMUNICATIONS	COMMUNICATIONS
NORTHLAND CABLE VISION	CABLE TV

ENVIRONMENTAL RESOURCES IMPACT TABLE						
These resources and the restrictions listed are governed by state and federal law.						
RESOURCE NAME (from Section A of the ECT)	LOCATION		SIDE	PERMITTED CONSTRUCTION ACTIVITY (from Section A of the ECT)	SPECIAL PROVISION? (from Section B of the ECT)	COMMENTS (from Section C of the ECT, comments only)
	BEGINING STA	ENDING STA				
FALLOW FARM FIELDS	111+90.97	114+50.00	LT	NONE	NONE	POTENTIAL GOPHER TORTOISE HABITAT

<b>GEORGIA</b> DEPARTMENT OF TRANSPORTATION	REVISION DATES <table border="1" style="width: 100px; height: 40px;"> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> </table>									STATE OF GEORGIA DEPARTMENT OF TRANSPORTATION OFFICE: ROADWAY DESIGN <b>GENERAL NOTES</b>
0010364 BULLOCH COUNTY	DRAWING No. <b>04-001</b>									