

SUMMARY OF QUANTITIES

SUMMARY OF DRIVEWAY QUANTITIES ASPHALT CONCRETE DRIVEWAY					
STATION, SIDE & LOCATION	WIDTH	12.5 MM SUPERPAVE	19 MM SUPERPAVE	6" G. A. B.	BITUM TACK COAT
	FEET	TN	TN	SY	GAL
SR 26/US 80 108+85.69 LT	48	10	13	113.11	36
SR 26/US 80 110+12.48 RT	28	9	11	98.89	32
BURKHALTER RD 21+50.00 RT	72	15	19	171.67	55
TOTAL		34	43	383.67	123

STRUCTURE *	ROADWAY	STATION	SIDE	18" STORM DRAIN	FILL HEIGHT	HEIGHT	DROP INLET GROUP 1 GA STD. 1035	FLARED END SECTION GROUP 1 GA STD 1120	RIP RAP TYPE 3, 24 IN	FILTER FABRIC
				FT		FT	EA	EA	SY	SY
A-1	SR 26/US 80 AS DIRECTED	108+21.00	LT	322	1-10		1	1	3	3
									7	7
TOTAL				322			1	1	10	10

TRAFFIC CONTROL	
0010364	LUMP SUM

GRADING COMPLETE	
0010364	LUMP SUM

AREAS	GRASSING	AGRICULTURAL LIME	FERTILIZER MIXED GRADE	FERTILIZER NITROGEN CONTENT	MULCH
	ACRES	TON	TON	LB	TON
PERMANENT	2.00	6	1	100	5
TEMPORARY	1.00		1		3
ADJ. TOTAL DISTURBED	2.52				25
TOTAL	5.52	6	2	100	33

DRIVEWAY SIDE DRAIN PIPE (LF)			
STATION, SIDE & LOCATION	18 IN. H 1-10	FLARED END SECTION (EA) 18 IN	SAFETY END SECTION (EA) 18 IN H 1-10
SR 26/US 80 110+12.48 RT	67	2	
BURKHALTER RD 17+00.00 RT			2
TOTAL	67	2	2

CONCRETE HEADER CURB, 8 IN, TP 3	
TOTAL	160 LF

CONCRETE SIDEWALK 6 IN	
TOTAL	110 SY

CLASS B CONCRETE	
AS DIRECTED	10 CY

RIGHT OF WAY MARKERS	
TOTAL	21 EA

EROSION CONTROL MATS, SLOPES	
AS DIRECTED	3000 SY

TEMPORARY EROSION CONTROL		
ITEM	UNIT	TOTAL
CONSTRUCTION EXIT	EACH	2
MAINTENANCE OF CONSTRUCTION EXIT	EACH	4
CONSTRUCT AND REMOVE TEMPORARY SILT FENCE, TYPE C	LF	920
MAINTENANCE OF TEMPORARY SILT FENCE, TYPE C	LF	460
CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EACH	1
MAINTENANCE OF INLET SEDIMENT TRAP	EACH	1
CONSTRUCT AND REMOVE HAY BALE STRAW CHECK DAMS	LF	1134
MAINTENANCE OF CHECK DAMS - ALL TYPES	LF	1134

CONCRETE MEDIAN, 6 IN	
TOTAL	180 SY

ORANGE BARRIER FENCE	
TOTAL	260 LF