

PROJECT NOTES

1. A NOTICE OF INTENT IS NOT REQUIRED FOR THIS PROJECT. THE DISTURBED AREA IS: WALT STEPHENS RD. 0.35 ACS, FAIRVIEW RD. 0.10 ACS, MAYS RD. 0.56 ACS, McDONOUGH PKWY. 0.22 ACS, LEMON ST. 0.19 ACS. TOTAL IS 1.42 ACRES. THE PROJECT INVOLVES INSTALLATION OF SIDEWALKS AND CURB RAMP, AND STRIPING CROSSWALKS.
2. ALL DRIVEWAYS THAT ARE TO BE RECONSTRUCTED SHALL BE PLACED IN KIND (I.E. ASPHALT FOR ASPHALT, CONCRETE FOR CONCRETE, AND AGGREGATE SURFACE COURSE FOR DIRT DRIVES). DRIVEWAY RELOCATIONS ARE SHOWN FROM THE BEST AVAILABLE DATA. THE CONTRACTOR SHALL CONSTRUCT NEW DRIVEWAYS TO MATCH THE ACTUAL FIELD LOCATION OF EXISTING DRIVEWAYS OR AS LOCATED IN THE PLANS. RESIDENTIAL DRIVES SHALL BE 14 FEET WIDE AT THE THROAT UNLESS NOTED OTHERWISE IN THE PLANS. COMMERCIAL DRIVES SHALL BE 24 FEET WIDE UNLESS NOTED OTHERWISE IN THE PLANS. THE CONTRACTOR SHALL OBTAIN THE APPROVAL FROM THE ENGINEER PRIOR TO MAKING ANY REVISIONS TO LOCATION, WIDTH, AND/OR NUMBER OF DRIVES TO BE CONSTRUCTED. DRIVES SHALL BE CONSTRUCTED USING:
 CONCRETE - RESIDENTIAL - DRIVEWAY CONCRETE, 6" GRADED AGGREGATE BASE, 6"
 CONCRETE - COMMERCIAL - DRIVEWAY CONCRETE, 8" GRADED AGGREGATE BASE, 8"
 ASPHALT - RESIDENTIAL - ASPH CONC 12.5mm SUPERPAVE (165 LB/SY) GRADED AGGREGATE BASE, 6"
3. ALL BORROW AND WASTE SITES FOR THIS PROJECT SHALL BE ENVIRONMENTALLY APPROVED PRIOR TO CONSTRUCTION ACTIVITIES OCCURRING IN THEM. ALL COMMON FILL OR EXCESS MATERIAL DISPOSED OUTSIDE THE PROJECT RIGHT OF WAY SHALL BE PLACED IN EITHER A PERMITTED SOLID WASTE FACILITY, A PERMITTED INERT WASTE LANDFILL OR IN AN ENGINEERED FILL. SEE SECTION 201 OF THE STANDARD SPECIFICATION AND SUPPLEMENTS THERETO FOR ADDITIONAL INFORMATION.
4. THERE IS NO SUITABLE PLACE TO BURY EXISTING CONSTRUCTION DEBRIS WITHIN THE PROJECT'S LIMITS. THE CONTRACTOR SHALL PROVIDE AN ENVIRONMENTALLY APPROVED SITE TO DISPOSE OF EXISTING CONSTRUCTION DEBRIS AT NO ADDITIONAL COST TO THE DEPARTMENT.
5. REMOVAL OF EXISTING PAVEMENT INCLUDING SAWCUTTING, CURB AND GUTTER, AND CONCRETE SIDEWALK AS SHOWN IN PLANS SHALL BE INCLUDED IN PRICE BID FOR GRADING COMPLETE.
6. AT ALL LOCATIONS WHERE EXISTING CURB OR PAVEMENT ABUT NEW CONSTRUCTION, THE EDGE OF THE EXISTING CURB OR PAVEMENT SHALL BE SAWCUT TO A CLEAN, SMOOTH EDGE IN ACCORDANCE WITH SECTION 411 AND 444. THE COST FOR THIS WORK SHALL BE INCLUDED IN THE PRICE BID FOR GRADING COMPLETE.
7. ALL ADA RAMPS AND SIDEWALK WITHIN THE INTERSECTION RADI1 ARE TO BE 8 INCH CONCRETE. THE COST FOR ADA RAMPS AND DETECTABLE WARNINGS SHALL BE INCLUDED IN THE PRICE BID FOR CONC SIDEWALK, 8 IN.
8. ALL DETECTABLE WARNING SURFACES ARE TO BE THE COLOR YELLOW.
9. ALL REMOVAL OF EXISTING STRIPING IS TO BE INCLUDED IN THE PRICE BID FOR TRAFFIC CONTROL.
10. THE COST FOR REMOVAL AND RESETTING OF SIGNS IS TO BE INCLUDED IN THE PRICE BID FOR TRAFFIC CONTROL.
11. PORTIONS OF THIS PROJECT HAVE BEEN PREPARED USING THE HORIZONTAL GEORGIA COORDINATE SYSTEM OF 1984 (NAD 1983) WEST ZONE, AND THE NORTH AMERICAN VERTICAL DATUM (NAVD) OF 1988. ADDITIONAL PORTIONS OF THIS PROJECT HAVE BEEN PREPARED USING AERIAL PHOTOGRAPHY AND HENRY COUNTY TAX MAPS.
12. THE CONTRACTOR SHALL PROVIDE A WORK SCHEDULE TO THE HENRY COUNTY BOARD OF EDUCATION PRIOR TO BEGINNING WORK.
13. ALL SAWCUTS AND CONSTRUCTION JOINTS SHALL BE INCLUDED IN THE PRICE BID FOR CLASS A CONCRETE.

UTILITY OWNERS

FACILITY	OWNER
ELECTRIC	GEORGIA POWER (DISTRIBUTION)
ELECTRIC	CITY OF HAMPTON
ELECTRIC	SNAPPING SHOALS EMC
PHONE	BELLSOUTH dba AT&T
GAS	ATLANTA GAS LIGHT
CABLE	CHARTER COMMUNICATIONS
WATER	CITY OF HAMPTON
WATER	CITY OF MCDONOUGH
WATER	CLAYTON COUNTY WATER AUTHORITY
WATER	HENRY COUNTY WATER AND SEWER AUTHORITY
SEWER	CITY OF HAMPTON
SEWER	CITY OF MCDONOUGH
SEWER	CLAYTON COUNTY WATER AUTHORITY
SEWER	HENRY COUNTY WATER AND SEWER AUTHORITY

SCHOOL CONTACTS

SCHOOL	CONTACT NUMBER
WESLEY LAKES ELEMENTARY SCHOOL	770-914-1889
HAMPTON ELEMENTARY SCHOOL	770-946-4345
RED OAK ELEMENTARY SCHOOL	770-389-1464
STOCKBRIDGE MIDDLE SCHOOL	770-474-5710
FAIRVIEW ELEMENTARY SCHOOL	770-474-8265
HENRY COUNTY HIGH SCHOOL	770-957-3943
SCHOOL SYSTEM	770-957-1891

*NOTE: THE CONTRACTOR SHALL CONTACT 72 HOURS PRIOR TO BEGINNING WORK ON THE SCHOOL PROPERTY.

ENVIRONMENTAL RESOURCES IMPACT TABLE

Resource Name/Type	Location	Side	Construction Activity	Permitted Activity	Controlling Criteria	Special Provision?	Comments including any permit expiration dates
Environmental Resource- Intermittent Stream I	Mays Rd. Sta. 400+25 to 401+84	Left	None	None	Section 404 of the Clean Water Act	N/A	See Note 1 below
Environmental Resource- Intermittent Stream I Buffer	Mays Rd. Sta. 400+25 to 401+84	Left	Sidewalk/drainage construction, erosion control, gas line relocation	None	Section 404 of the Clean Water Act	N/A	See Note 1 below
Historical Resource- Britt House	Sr. 81 / Keys Ferry Street Sta. 100+00.00	Left	None	None	E&S Act (OCGA 12-7)	N/A	See Note 2 below
Historical Resource- McDonough High School	Lemon Street Sta. 104+70 to 107+04.77	Left	None	None	E&S Act (OCGA 12-7)	N/A	See Note 2 below
Environmental Resource- Red Oak United Methodist Cemetery	Walt Stephens Rd. Sta. 304+40 to 307+05	Right	None	None	E&S Act (OCGA 12-7)	N/A	See Note 3 below

Note:

1. The contractor shall ensure that no land disturbing activities, including staging, construction, vehicular use, borrow or waste activities shall take place within the boundaries of IS-1 or its associated buffer.
2. The contractor shall ensure that no land disturbing activities, including staging, construction, vehicular use, borrow or waste activities shall take place within the boundaries of McDonough High School or Britt House.
3. The contractor shall ensure that no land disturbing activities, including staging, construction, vehicular use, borrow or waste activities shall take place within the boundaries of Red Oak United Methodist Cemetery.



Know what's below.
Call before you dig.

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY
GENERAL NOTES



DRAWING No.
04-001