



NOTE: REMOVE FORMWORK AS SOON AS POSSIBLE. TOP SLAB MAY BE CAST IN PLACE OR PRECAST. IF SLAB IS CAST IN PLACE, BUILDERS PAPER IS TO BE PLACED BETWEEN THE TOP SLAB AND BOTTOM SUPPORT OF SPILLWAY.

GENERAL NOTE  
 1. SEE GEORGIA STANDARD I033D AND I034D FOR ADDITIONAL INFORMATION ON CATCH BASIN TOP AND FORMING THE TRANSITION OF THE GUTTER.  
 2. CAST IRON MANHOLE RING AND COVER NOT REQUIRED.  
 3. CLASS "A" CONCRETE REQUIRED FOR ALL REINFORCED TOP SLABS. BOTTOM SECTION MAY BE CLASS "B" OR CLASS "A".

MEASUREMENT: SPECIAL DESIGN SPILLWAY UNDER SIDEWALK WILL BE MEASURED BY THE UNIT.  
 PAYMENT: SPECIAL DESIGN SPILLWAY UNDER SIDEWALK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR EACH.  
 PAYMENT WILL BE MADE UNDER: ITEM NO. 441, CONC. SPILLWAY, SPEC DES.

DATE	DEPARTMENT OF TRANSPORTATION STATE OF GEORGIA	
REVISION	SPECIAL DESIGN SPILLWAY UNDER SIDEWALK	
BY	NO SCALE	FEB. 2005



**GEORGIA**  
DEPARTMENT  
OF  
TRANSPORTATION

REVISION DATES

STATE OF GEORGIA  
DEPARTMENT OF TRANSPORTATION  
OFFICE: INNOVATIVE DELIVERY  
**SPECIAL CONSTRUCTION DETAIL**  
SRTS - COBB  
CHEATHAM HILL ELEMENTARY

DRAWING No.  
**38-001**