ENVIRONMENTAL RESOURCES IMPACT TABLE

These resources and the restrictions limited are governed by state and federal law

RESOURCE NAME/TYPE	LOCATION		SIDE	PERMITTED CONSTRUCTION ACTIVITY	SPECIAL PROVISION?	COMMENTS INCLUDING ANY PERMIT EXPIRATION DATES
	APPROX BEGIN STA	APPROX END STA				
STREAM S-1	STA 51+60 SCHOOL ENTRANCE	STA 51+75 SCHOOL ENTRANCE	BOTH	NO IMPACT TO STREAM	NA	THE CONTRACTOR WILL ENSURE THAT NO CONSTRUCTION-RELATED ACTIVITIES OCCUR BEYONDTHE ORANGE BARRIER FENCING PROTECTING S1 AND THE 25 FOOT BUFFER OF S1.
	STA 71+28 OLD CARRIAGE DRIVE	STA 71+44 OLD CARRIAGE DRIVE	BOTH	NO IMPACT TO STREAM	NA	THE CONTRACTOR WILL ENSURE THAT NO CONSTRUCTION-RELATED ACTIVITIES OCCUR BEYONDTHE ORANGE BARRIER FENCING PROTECTING S1 AND THE 25 FOOT BUFFER OF S1.
STREAM S-1 BUFFER	STA 51+35 SCHOOL ENTRANCE	STA 52+00 SCHOOL ENTRANCE	BOTH	ACTIVITIES WITHIN 50 FT OF THE PROPOSED CULVERT ARE EXEMPT. NO IMPACT TO BUFFER.	NA	THE CONTRACTOR WILL ENSURE THAT NO CONSTRUCTION-RELATED ACTIVITIES OCCUR BEYONDTHE ORANGE BARRIER FENCING PROTECTING S1 AND THE 25 FOOT BUFFER OF S1.
	STA 71+03 OLD CARRIAGE DRIVE	STA 71+69 OLD CARRIAGE DRIVE	BOTH	ACTIVITIES WITHIN 50 FT OF THE PROPOSED CULVERT ARE EXEMPT. NO IMPACT TO BUFFER.	NA	THE CONTRACTOR WILL ENSURE THAT NO CONSTRUCTION-RELATED ACTIVITIES OCCUR BEYONDTHE ORANGE BARRIER FENCING PROTECTING S1 AND THE 25 FOOT BUFFER OF S1.

THE CONTRACTOR WILL SUBMIT A NOI TO THE NPDES GENERAL PERMIT FOLLOWING AWARD OF THE CONTRACT BUT PRIOR TO CONSTRUCTION.