ITEMS TO BE PAID FOR UNDER P.I.# 0010884

STATION	INSTL NO	SIGN CODE	HIGHWAY SIGNS: TP 1 MATL, REFL SHEETING, TP 3			TP 2 MATL, REFL SHEETING, TP 3			TP 1 MATL, REFL SHEETING, TP 9			TP 2 MATL, REFL SHEETING, TP 9			SQUARE TUBE POST: TYPE 7			TYPE 8			TYPE 9			BREAKAWAY SIGN SUPPORT (EACH)
			SIGN SIZE	QUAN	AREA (SQ. FT.)	SIGN SIZE	QUAN	AREA (SQ. FT.)	SIGN SIZE	QUAN	AREA (SQ. FT.)	SIGN SIZE	QUAN	AREA (SQ. FT.)	LENGTH (FT.)	QUAN	TOTAL (FT.)	LENGTH (FT.)	QUAN	TOTAL (FT.)	LENGTH (FT.)	QUAN	TOTAL (FT.)	
BUFORD HIGHWAY (S.R. 13) SURVEY (CONT'D.)																								
18+40	31	R1-1(36)							36 " OCT	1	7.46				13	1	13							
19+03	32	I-2(42)				42 " x 48 "	1	14.00										14	1	14				
19+63	33	I-2(42)	42 " x 24 "	1	7.00													17	1	17				
		D10-4(0)	18 " x 54 "	1	6.75																			
20+05	34	USE EXIST. SIGNS																14	2	28				2
21+35	35	I550-1(30)	30 " x 36 "	1	7.50										13	1	13							
22+78	36	R2-1(36)(45)				36 " x 48 "	1	12.00													14	1	14	
24+00	37	M3-1(24)	24 " x 12 "	1	2.00										13	1	13							
		M1-5(24)(13)	24 " x 24 "	1	4.00																			
24+17	38	R560-5	18 " x 24 "	1	3.00										12	1	12							
25+80	39	R560-5	18 " x 24 "	1	3.00										12	1	12							
28+00	40	W11-2(36)							36 " x 36 "	1	9.00							16	1	16				
		W16-9p(30)							30 " x 18 "	1	3.75													
30+01	41	R10-6aR	24 " x 30 "	1	5.00										13	1	13							
30+02	42	R10-6aL	24 " x 30 "	1	5.00										13	1	13							
31+04	43	R10-6aL	24 " x 30 "	1	5.00										13	1	13							
31+64	44	R1-1(36)							36 " OCT	1	7.46				13	1	13							
33+08	45	W11-2(36)							36 " x 36 "	1	9.00							16	1	16				
		W16-9p(30)							30 " x 18 "	1	3.75													
33+69	46	R1-1(36)							36 " OCT	1	7.46				13	1	13							
34+45	47	R5-1(30)							30 " x 30 "	1	6.25				13	1	13							
34+46	48	R560-5	18 " x 24 "	1	3.00										12	1	12							
34+56	49	R4-7	24 " x 30 "	1	5.00										13	1	13							
36+45	50	R5-1a(36)							36 " x 24 "	1	6.00				12	1	12							
38+27	51	R5-1a(36)							36 " x 24 "	1	6.00				12	1	12							
39+49	52	R1-1(36)							36 " OCT	1	7.46				13	1	13							
39+92	53	R5-1(30)							30 " x 30 "	1	6.25				13	1	13							
40+27	54	R5-1(30)							30 " x 30 "	1	6.25				13	1	13							
42+29	55	W8-13(30)							30 " x 30 "	1	6.25				14	1	14							
44+21	56	R1-1(36)							36 " OCT	1	7.46				13	1	13							
46+37	57	W11-2(36)							36 " x 36 "	1	9.00							16	1	16				
		W16-9p(30)							30 " x 18 "	1	3.75													
46+96	58	R5-1(30)							30 " x 30 "	1	6.25				13	1	13							
47+15	59	R560-5	18 " x 24 "	1	3.00										12	1	12							
47+16	60	R5-1(30)							30 " x 30 "	1	6.25				13	1	13							
47+73	61	R6-2R(24)	24 " x 30 "	1	5.00										13	1	13							
47+80	62	R1-1(36)							36 " OCT	1	7.46				13	1	13							
SUB-TOTAL #2					64.25			26.00			132.51						320			107			14	2

*TYPE 9 POST AN INSERT FOR TYPE 8 POST

ATKINS

REVISION DATES
7/13/12

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

SUMMARY QUANTITIES
STANDARD HIGHWAY SIGNS

BUFORD HIGHWAY STREETSCAPES

DRAWING No. 6-13

GPLN