ITEMS TO BE PAID FOR UNDER P.I.# 0010884

STATION	INSTL NO	SIGN CODE	HIGHWAY SIGNS												SQUARE TUBE POST									BREAKAWAY SIGN SUPPORT (EACH)
			TP 1 MATL, REFL SHEETING, TP 3			TP 2 MATL, REFL SHEETING, TP 3			TP 1 MATL, REFL SHEETING, TP 9			TP 2 MATL, REFL SHEETING, TP 9			TYPE 7			TYPE 8			TYPE 9			
			SIGN SIZE	QUAN	AREA (SQ. FT.)	SIGN SIZE	QUAN	AREA (SQ. FT.)	SIGN SIZE	QUAN	AREA (SQ. FT.)	SIGN SIZE	QUAN	AREA (SQ. FT.)	LENGTH (FT.)	QUAN	TOTAL (FT.)	LENGTH (FT.)	QUAN	TOTAL (FT.)	LENGTH (FT.)	QUAN	TOTAL (FT.)	
BUFORD HIGHWAY (S.R. 13) SURVEY (CONT'D.)																								
76+36	116	R10-6aL	24" x 30"	1	5.00										13	1	13							
77+39	117	R10-6aL	24" x 30"	1	5.00										13	1	13							
77+40	118	R10-6aR	24" x 30"	1	5.00										13	1	13							
77+42	119	R1-1(36)							36" OCT	1	7.46				13	1	13							
79+27	120	W11-2(36)							36" x 36"	1	9.00							16	1	16				
		W16-9p(30)							30" x 18"	1	3.75													
79+29	121	R1-1(36)							36" OCT	1	7.46				13	1	13							
79+40	122	W11-2(36)							36" x 36"	1	9.00							16	1	16				
		W16-9p(30)							30" x 18"	1	3.75													
84+14	123	R1-1(36)							36" OCT	1	7.46				13	1	13							
86+27	124	W11-2(36)							36" x 36"	1	9.00							16	1	16				
		W16-9p(30)							30" x 18"	1	3.75													
86+28	125	W11-2(36)							36" x 36"	1	9.00							16	1	16				
		W16-9p(30)							30" x 18"	1	3.75													
88+27	126	R10-6aR	24" x 30"	1	5.00										13	1	13							
88+28	127	R10-6aL	24" x 30"	1	5.00										13	1	13							
89+26	128	R10-6aL	24" x 30"	1	5.00										13	1	13							
89+27	129	R10-6aR	24" x 30"	1	5.00										13	1	13							
89+84	130	R1-1(36)							36" OCT	1	7.46				13	1	13							
89+94	131	R6-2R(24)	24" x 30"	1	5.00										13	1	13							
90+52	132	R5-1(30)							30" x 30"	1	6.25				13	1	13							
91+26	133	W11-2(36)							36" x 36"	1	9.00							16	1	16				
		W16-9p(30)							30" x 18"	1	3.75													
91+27	134	W11-2(36)							36" x 36"	1	9.00							16	1	16				
		W16-9p(30)							30" x 18"	1	3.75													
98+75	135	R2-1(36)(45)				36" x 48"	1	12.00													14	1	14	
98+00	136	R2-1(36)(45)				36" x 48"	1	12.00													14	1	14	
98+19	137	R5-1a(36)							36" x 24"	1	6.00				12	1	12							
99+54	138	M3-2(24)	24" x 12"	1	2.00										13	1	13							
		M1-5(24)(13)	24" x 24"	1	4.00																			
100+12	139	R5-1(30)							30" x 30"	1	6.25				13	1	13							
101+38	140	R5-1(30)							30" x 30"	1	6.25				13	1	13							
102+65	141	R1-1(36)							36" OCT	1	7.46				13	1	13							
102+82	142	W11-2(36)							36" x 36"	1	9.00							16	1	16				
		W16-9p(30)							30" x 18"	1	3.75													
103+04	143	W11-2(36)							36" x 36"	1	9.00							16	1	16				
		W16-9p(30)							30" x 18"	1	3.75													
SUB-TOTAL *5					46.00			24.00			164.05						233			128			28	

*TYPE 9 POST AN INSERT FOR TYPE 8 POST

ATKINS

REVISION DATES
7/13/12

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

SUMMARY QUANTITIES
STANDARD HIGHWAY SIGNS
BUFORD HIGHWAY STREETSCAPES

DRAWING No. 6-16

GPLN