

UTILITY LEGEND

UTILITY LINECODES

	EXISTING	TO BE REMOVED	PROPOSED	TYPE OF UTILITY	
OVERHEAD	---W---E---W---E-	-E-X-W-X-E-X-W-X-E-	---W---E---W---E-	ELECTRIC	
	---W---E-T---W---	-X-E-T-X-W-X-E-T-X-	---W---E-T---W---	ELECTRIC/TELECOMMUNICATIONS	
	---W---E-TV---W---	-X-E-TV-X-W-X-E-TV	---W---E-TV---W---	ELECTRIC/CABLE TV	
	---W---E-T-TV---W---	-W-X-E-T-TV-X-W-X-	---W---E-T-TV---W---	ELECTRIC/TELECOMMUNICATIONS/CABLE TV	
	---W---GW---W---	-X-GW-X-W-X-GW-X-V	---W---GW---W---	GUY WIRE	
	---W---T---W---	-T-X-W-X-T-X-W-X-T-	---W---T---W---	TELECOMMUNICATIONS	
	---W---T-TV---W---	-X-T-TV-X-W-X-	---W---T-TV---W---	TELECOMMUNICATIONS/CABLE TV	
	---W---TV---W---	-X-TV-X-W-X-TV-X-W-	---W---TV---W---	CABLE TV	
	UNDERGROUND	-----E-----E	---X---E---X---	-----E-----E	ELECTRIC
		-----T-----T	---X---T---X---	-----T-----T	TELECOMMUNICATIONS
-----TV-----T		---X---TV---X---	-----TV-----T	CABLE TV	
-----W-----W		---X---W---X---	-----W-----W	WATER	
-----**W-----E		---X---**W---X---	=====**W=====	WATER FOR LABELED PIPE SIZES	
-----NW-----NW		---X---NW---X---	-----NW-----NW	NON-POTABLE WATER	
-----**NW-----		---X---**NW---X---	=====**NW=====	NON-POTABLE WATER FOR LABELED PIPE SIZES	
-----STM-----		---X---STM---X---	-----STM-----	STEAM	
-----**STM-----		---X---**STM---X---	=====**STM=====	STEAM FOR LABELED PIPE SIZES	
----->SS----->		---X--->SS---X---	----->SS----->	SANITARY SEWER WITH FLOW DIRECTION	
-----**SS-----		---X---**SS---X---	=====**SS=====	SANITARY SEWER WITH FLOW DIRECTION FOR LABELED PIPE SIZES	
----->SFM-----		---X--->SFM---X---	----->SFM-----	SANITARY SEWER FORCE MAIN WITH FLOW DIRECTION	
-----**SFM-----		---X---**SFM---X---	=====**SFM=====	SANITARY SEWER FORCE MAIN WITH FLOW DIRECTION FOR LABELED PIPE SIZES	
-----G-----		---X---G---X---	-----G-----	GAS	
-----**G-----		---X---**G---X---	=====**G=====	GAS FOR LABELED PIPE SIZES	
-----P-----	---X---P---X---	-----P-----	PETROLEUM		
-----**P-----	---X---**P---X---	=====**P=====	PETROLEUM FOR LABELED PIPE SIZES		

UTILITY SYMBOLS

EXISTING	PROPOSED	TEMPORARY	DESCRIPTION
			UTILITY POLE/GUY POLE
			LIGHT POLE
			GUY ANCHOR
			MARKER
			SPLICE BOX
			CABINET
			VENT
			ELECTRIC MANHOLE
			HAND HOLE
			TRANSFORMER
			ELECTRIC METER
			ELECTRIC BOX
			TELECOMMUNICATIONS MANHOLE
			TELECOMMUNICATIONS PEDESTAL
			SUBSCRIBER LOOP CARRIER (aka "SLICK")
			PHONE BOOTH
			CABLE TV PEDESTAL
			CABLE TV MANHOLE
			WATER VALVE
			WATER METER
			WATER MANHOLE
			FIRE HYDRANT ASSEMBLY (INCLUDES ASSOCIATED VALVE)
			BACKFLOW PREVENTER
			PRESSURE INDICATOR VALVE
			AIR RELEASE VALVE
			WELL
			WATER VAULT
			WATER VALVE MARKER
			STAND PIPE
			CLEANOUT
			SANITARY SEWER MANHOLE
			AIR RELEASE VALVE
			GREASE TRAP
			SANITARY SEWER FORCE MAIN VALVE
			GAS VALVE
			GAS METER
			GAS MANHOLE
			GAS PRESSURE REGULATOR
			GAS VAULT
			GAS TEST STATION
			PETROLEUM VALVE



REVISION DATES		

UTILITY LEGEND	
INTERCHANGE CONSTRUCTION	
SR 316/US 29 AT SR 81	
BARROW COUNTY, GEORGIA	
SEWER RELOCATION PLAN	DRAWING No. 44-0027