SUMMARY OF QUANTITIES - STANDARD SIGNS

PAVEMENT MARKERS (EACH)

LOCATION	REFLECTIVE-RAISED			REFLECTIVE-RECESSED			OPAQUE		JIGGLE BAR		CHANNEL MKR	
	YELLOW	CLEAR	CLEAR/ RED	YELLOW	CLEAR	CLEAR/ RED	WHITE	YELLOW				
	TYPE 1	TYPE 2	TYPE 3	TYPE 1	TYPE 2	TYPE 3	TYPE 5	TYPE 6	TYPE 7	TYPE 8	TYPE 9	TYPE 10
SR17												
	18		964									
OLD MILL BRIDGE RD												
	6											
EASTANOLLEE RD												
	16		12									
EASTANOLLEE BYPASS												
	25		12									
DAVIS RD												
	15											
WHISPERING PINES RD												
	20											10
MOORE CIRCLE												
	10											10
CLARY CONN/NORTH AVE												
	6											20
MEADOWBROOK DR												
	10											10
FIELDCREST DR												
	14		14									
SR 17 ALT/ TOCCOA BYP												
	8		14									
TOTAL	148	---	1016	---	---	---	---	---	---	---	---	50

NOTES: 1. TYPE 1,2, AND 3 PAVEMENT MARKERS SHALL BE SPACED AS SPECIFIED ON THE RAISED PAVEMENT MARKERS LOCATION DETAILS.

VOID

TRAFFIC STRIPE

DESCRIPTION	UNIT	QUANTITY			
		PAINT	THERMOPLASTIC	POLYUREA	PREFORMED
5"SOLID WHITE	LIN FEET	6,711	37,762	---	---
5"SOLID YELLOW	LIN FEET	---	34,910	---	---
24"SOLID WHITE	LIN FEET	---	312	---	---
6"SOLID WHITE	LIN FEET	12,350	---	---	---
8"SOLID WHITE	LIN FEET	---	3,704	---	---
5"SKIP WHITE	GLF	3,917	37,616	---	---
5"SKIP YELLOW	GLF	---	1,432	---	---
6"SKIP WHITE	GLF	3,917	---	---	---
PREFORMED PLASTIC SOLID PVMT MKG, 8 IN	LIN FEET	---	---	---	1,200
PREFORMED PLASTIC SKIP PVMT MKG, 8 IN	GLF	---	---	---	1,000
PREFORMED PLASTIC SOLID PVMT MKG, 8 IN	LIN FEET	---	---	---	1,000

SYMBOLS (EACH)

DESCRIPTION	QUANTITY	
	PAINT	THERMOPLASTIC
PAVEMENT MARKING, SYMBOL, TP 4	33	---

ARROWS (EACH)

DESCRIPTION	QUANTITY	
	PAINT	THERMOPLASTIC
TYPE 1	33	---
TYPE 2	---	144
TYPE 7	---	36

NOTE: ALL ARROWS SHALL BE WHITE UNLESS OTHERWISE SPECIFIED, SEE PLANS FOR LOCATION.

THERMO TRAF STRIPE (SQ YD)

QUANTITY	
WHITE	YELLOW
10,683	847

NOTE: SEE PLANS FOR LOCATION AND DETAIL REFERENCE.

SUMMARY OF QUANTITIES-OVERHEAD WIRE SPAN

STATION	SPAN WIDTH	LANE	SIGNS-TYPE 1 MAT'L (0.08) (REFL SHEETING TP 3)				SIGNS-TYPE 2 MAT'L (0.10) (REFL SHEETING TP 9)				GALV. SEIMANS-MARTIN GUY STRAND MESSENGER CABLE (lin. ft.)-(including 3-bolt r galv. clamps with ½" galv. bolts)	STRAIN POLES (CONCRETE OR STEEL) EACH			TREATED TIMBER POLES, CLASS 2, 30 FT.
			CODE	SIZE	QUAN.	SQ. FT.	CODE	SIZE	QUAN.	SQ. FT.	½" DIA. CABLE LIN. FT.	TYPE I	TYPE II	TYPE III	EACH
540+85	135'	NB-1					R3-5L	30" X 36"	1	7.5	270			2	
		NB-1,2					M-SPEC #1	30" X 36"	1	7.5					
		NB-2					R3-5L	30" X 36"	1	7.5					
		NB-3,4					R3-5A	30" X 36"	1	7.5					
							M-SPEC #2	30" X 36"	1	7.5					

NOTES: 1. FOR CABLE AND STRAIN POLES REFER TO SECTION 639 GA.STD. SPECIFICATIONS.
2. LANE NUMBERS ASSIGNED FROM CENTER LINE OUT IN DIRECTION OF SURVEY.
3. WHEN TWO OR MORE SIGN FACING THE SAME DIRECTION ARE TO BE MOUNTED OVER THE SAME LANE(S), THE SIGNS SHALL BE CENTERED OVER THE LANE(S) WITH A 2" SPACE BETWEEN SIGNS.
4. FOR ERECTION DETAILS SEE "TYPICAL ERECTION DETAILS-OVERHEAD LANE MARKERS".

M-SPECIAL SIGNS SHALL HAVE WHITE LEGEND AND BORDERS ON GREEN REFLECTORIZED BACKGROUND. GEORGIA AND U.S. SHIELDS SHALL HAVE A WHITE REFLECTORIZED BACKGROUND WITH BLACK LEGEND. INTERSTATE SYMBOLS SHALL BE PER THE M.U.T.C.D..

ARCADIS
Infrastructure · Water · Environment · Buildings

REVISION DATES

GEORGIA
DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
PROJECT EDS00-0545-00(037)
COUNTY STEPHENS

DRAWING NO. 6-017