STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA	APD-00-0056-01(063)	28	406

SUMMARY OF QUANTITIES-STANDARD SIGNS

STATION	INSTL. NO.	SIGN CODE	HIGHWAY SIGNS (REFLECTIVE SHEETING TYPE III)						HIGHWAY SIGNS (REFLECTIVE SHEETING TYPE IX)						HIGHWAY SIGNS (REFLECTIVE SHEETING TYPE XI)						SQUARE TUBE POST									BREAKAWAY SIGN SUPPORT (EACH)
			TP 1 MATL. REFL SHEETING TP 3			TP 2 MATL. REFL SHEETING TP 3			TP 1 MATL. REFL SHEETING TP 9			TP 2 MATL. REFL SHEETING TP 9			TP 1 MATL. REFL SHEETING TP 11			TP 2 MATL. REFL SHEETING TP 11			TYPE 7			TYPE 8			TYPE 9			
			SIZE	EACH	SQ FT	SIZE	EACH	SQ FT	SIZE	EACH	SQ FT	SIZE	EACH	SQ FT	SIZE	EACH	SQ FT	SIZE	EACH	SQ FT	LENGTH (FEET)	QUANTITY	TOTAL LENGTH	LENGTH (FEET)	QUANTITY	TOTAL LENGTH	LENGTH (FEET)	QUANTITY	TOTAL LENGTH	
STA. 134+00	46	R3-2	24" X 24"	1	4.00																14	2	28				12	1	12	
		R5-1													30" X 30"	1	6.25													
STA. 135+43	47	R6-2R	24" X 30"	1	5.00																13	1	13							
STA. 135+45	48	R1-2													36" TRI	1	4.50										12	1	12	
STA. 135+87	49	R5-1A													36" X 24"	1	6.00				12	1	12							
STA. 136+00	50	M3-1	24"X12"	1	2.00																13	1	13							
		M1-5	24" X 24"	1	4.00																									
STA. 138+00	51	R5-1A													36" X 24"	1	6.00				12	1	12							
STA. 138+50	52	D1-2										78"X30"	1	16.25							12	2	24							
STA. 139+00	53	R5-1A													36" X 24"	1	6.00				12	1	12							
STA. 139+08	54	R1-2													36" TRI	1	4.50										12	1	12	
STA. 139+23	55	R1-2													36" TRI	1	4.50										12	1	12	
STA. 139+47	56	R6-2R	24" X 30"	1	5.00																13	1	13							
STA. 139+47	57	R6-2L	24" X 30"	1	5.00																13	1	13							
STA. 139+88	58	R1-2													36" TRI	1	4.50										12	1	12	
STA. 139+95	59	R1-2													36" TRI	1	4.50										12	1	12	
STA. 140+00	60	R6-2R	24" X 30"	1	5.00																13	1	13							
STA. 141+00	61	D2-1										66" X 18"	1	8.25							11	1	11							
STA. 143+00	62	M2-1	15"X21"	1	2.19																14	2	28							
		M1-5	24" X 24"	1	4.00																									
STA. 144+00	63	R6-2	24" X 30"	1	5.00																13	1	13							
STA. 141+32	64	R1-2													36" TRI	1	4.50										12	1	12	
STA. 150+00	65	R2-1	30" X 36"	1	7.50																						12	1	12	
SR 53																														
STA. 201+57	66	R3-7R							30" X 30"	1	6.25										13	1	13							
STA. 203+07	67	R3-7R							30" X 30"	1	6.25										13	1	13							
STA. 204+57	68	R3-7R							30" X 30"	1	6.25										13	1	13							
STA. 205+50	69	W6-1										36"X36"	1	9.00							12	2	24							
STA. 209+50	70	M2-1	15"X21"	1	2.19																14	2	28							
		M1-5	24" X 24"	1	4.00																									
STA. 210+36	71	R1-1													36" OCT	1	7										12	1	12	
STA. 210+85	72	R1-1													36" OCT	1	7										12	1	12	
STA. 211+38	73	R2-1	30" X 36"	1	7.50																						12	1	12	
STA. 211+40	74	R4-7	24"X30"	1	5.00																12	1	12							
STA. 212+57	75	R1-1													36" OCT	1	7										12	1	12	
STA. 212+82	76	R3-7R							30" X 30"	1	6.25										13	1	13							
STA. 212+92	77	R6-2R	24" X 30"	1	5.00																13	1	13							
STA. 214+20	78	D2-2										78"X30"	1	16.25							12	2	24							
STA. 214+24	79	R3-7R							30" X 30"	1	6.25										13	1	13							
STA. 215+00	80	W6-1										36"X36"	1	9.00							12	2	24							
STA. 215+37	81	R1-1													36" OCT	1	7										12	1	12	
STA. 216+77	82	D1-2										78"X30"	1	16.25							12	2	24							
STA. 218+25	83	R560-5							18" x 24"	1	3										11	1	11							
STA. 218+60	84	R4-7	24"X30"	1	5.00																12	1	12							
STA. 218+66	85	M3-4	24"X12"	1	2.00																13	1	13							
		M1-5	24" X 24"	1	4.00																									
STA. 222+00	86	R1-2													36" TRI	1	4.5										12	1	12	
STA. 222+39	87	R560-5							18" x 24"	1	3										11	1	11							
STA. 222+47	88	R4-7C	24"X30"	1	5.00																12	1	12							
STA. 225+25	89	R6-2R	24" X 30"	1	5.00																13	1	13							
STA. 225+34	90	R1-1													36" OCT	1	7										12	1	12	
STA. 226+54	91	D1-2										78"X30"	1	16.25							12	2	24							
STA. 227+25	92	R4-7	24"X30"	1	5.00																12	1	12							
STA. 228+50	93	R4-7C	24"X30"	1	5.00																12	1	12							
STA. 228+50	94	R3-7R							30" X 30"	1	6.25										13	1	13							
TOTAL				23	103.38					8	43.50		7	91.25		16	90.75					44	552.00					15	180.00	

3/1/2007 GPLN

GEORGIA
DEPARTMENT OF TRANSPORTATION

- NOT TO SCALE -

REVISION DATES
10/14/14

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: ROADWAY DESIGN
SUMMARY QUANTITIES
STANDARD SIGNS 2 OF 3

DRAWING No. 06-011