STATE	PROJECT NUMBER	SHEET NO.	TOTAL
GA.	STP-056-1(67)SPUR	13	152

DETAILED ESTIMATE

SR 400 AT CR 176

PROJECT NO: STP-056-1(67)SP

ITEM NO.	ITEM DESCRIPTION	UNITS	QUANTITY
	ROADWAY		
150-1000	TRAFFIC CONTROL - STP-056-1(67)SPUR	LS	LUMP
210-0100	GRADING COMPLETE - STP-056-1(67)SPUR	LS	LUMP
310-1101	GR AGGR BASE CRS, INCL MATL	TN	7000
318-3000	AGGR SURF CRS	TN	200
400-3206	ASPH CONC 12.5 MM OGFC, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	TN	520
402-1812	RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	TN	1000
402-3121	RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	1600
402-3131	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	620
402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	1800
402-4510	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	TN	1300
413-1000	BITUM TACK COAT	GL	2300
432-0209	MILL ASPH CONC PVMT, 2 1/4 IN DEPTH	SY	7200
441-0016	DRIVEWAY CONCRETE, 6 IN TK	SY	160
441-0104	CONC SIDEWALK, 4 IN	SY	320
441-0754	CONCRETE MEDIAN, 7 1/2 IN	SY	64
441-6222	CONC CURB & GUTTER, 8 IN X 30 IN, TP 2	LF	990
444-1000	SAWED JOINTS IN EXIST PAVEMENTS - PCC	LF	24
446-1002	PVMT REINF FABRIC STRIPS, TP 2, INCL BITUM BINDER	LF	5100
500-3800	CLASS A CONCRETE, INCL REINF STEEL	CY	5
550-1180	STORM DRAIN PIPE, 18 IN, H 1-10	LF	780
550-1300	STORM DRAIN PIPE, 30 IN, H 1-10	LF	400
550-2180	SIDE DRAIN PIPE, 18 IN, H 1-10	LF	140
550-2240	SIDE DRAIN PIPE, 24 IN, H 1-10	LF	52
550-3518	SAFETY END SECTION 18 IN, STORM DRAIN, 6:1 SLOPE	EA	1
550-3618	SAFETY END SECTION 18 IN, SIDE DRAIN, 6:1 SLOPE	EA	6
550-3624	SAFETY END SECTION 24 IN, SIDE DRAIN, 6:1 SLOPE	EA	2
550-4230	FLARED END SECTION 30 IN, STORM DRAIN	EA	1
632-0003	CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	2
634-1200	RIGHT OF WAY MARKER	EA	37
641-1200	GUARDRAIL, TP W	LF	1200
641-5001	GUARDRAIL ANCHORAGE, TP 1	EA	3
641-5012	GUARDRAIL ANCHORAGE, TP 12	EA	3
643-0010	FIELD FENCE WOVEN WIRE	LF	690
643-8001	GATE, GALVENIZED METAL - 12 FT X 4 FT	EA	1
668-1100	CATCH BASIN, GP 1	EA	3
668-1110	CATCH BASIN, GP 1, ADDL DEPTH	LF	6
668-2100	DROP INLET, GP 1	EA	6
668-4300	STORM SEWER MANHOLE, TP 1	EA	1
668-4311	STORM SEWER MANHOLE, TP 1, ADDL DEPTH, CL 1	LF	4
668-8011	SAFETY GRATE, TP 1	SF	63
	PERMANENT EROSION CONTROL		
163-0240	MULCH	TN	110
441-0204	PLAIN CONC DITCH PAVING, 4 IN	SY	100
603-2180	STN DUMPED RIP RAP, TP 3, 12 IN	SY	50
603-2182	STN DUMPED RIP RAP, TP 3, 24 IN	SY	50
603-7000	PLASTIC FILTER FABRIC	SY	100
700-6910	PERMANENT GRASSING	AC	6
700-7000	AGRICULTURAL LIME	TN	25
700-7010	LIQUID LIME	GL	21
700-8000	FERTILIZER MIXED GRADE	TN	4
700-8100	FERTILIZER NITROGEN CONTENT	LB	280
710-9000	PERMANENT SOIL REINFORCING MAT	SY	310
715-2200	BITUMINOUS TREATED ROVING, WATERWAYS	SY	1700
716-2000	EROSION CONTROL MATS, SLOPES	SY	6800
	TEMPORARY EROSION CONTROL		
163-0232	TEMPORARY GRASSING	AC	3
163-0300	CONSTRUCTION EXIT	EA	4
163-0503	CONSTRUCT AND REMOVE SILT CONTROL GATE, TP 3	EA	3
163-0520	CONSTRUCT AND REMOVE TEMPORARY PIPE SLOPE DRAIN	LF	170
163-0530	CONSTRUCT AND REMOVE BALED STRAW EROSION CHECK	LF	270
163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EA	10
165-0010	MAINTENANCE OF TEMPORARY SILT FENCE, TP A	LF	2300
165-0030	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	LF	720
165-0070	MAINTENANCE OF BALED STRAW EROSION CHECK	LF	140
165-0087	MAINTENANCE OF SILT CONTROL GATE, TP 3	EA	3
165-0101	MAINTENANCE OF CONSTRUCTION EXIT	EA	4
165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	EA	10
167-1000	WATER QUALITY MONITORING AND SAMPLING	EA	2
167-1500	WATER QUALITY INSPECTIONS	MO	12
171-0010	TEMPORARY SILT FENCE, TYPE A	LF	4600

Jordan Jones & Goulding

GEORGIA DEPARTMENT OF TRANSPORTATION

NO.	DATE	DESCRIPTION OF REVISION
	2/25/04	ADDED ITEM NO. 167-1500 WATER QUALITY INSPECTIONS
	2/23/04	CHANGED ITEM NO. 402-3502 TO 402-4510

SR 400/US 19 AT CR 176/SETTINGDOWN ROAD

DETAILED ESTIMATE

DESIGNED: MW	CHECKED: LJH	DATE:	9.01	
DRAWN: KMD	JOB NO. 2077-758	SCALE:	SHEET	REV

THIS LINE IS ONE INCH LONG WHEN PLOTTED FULL SCALE

3/20/2008 10:04:25 AM \\GDOT-DSN1\GOPLOT\OCF\Road Design Tiff-18x12_to_Tiff-36x24.acf asanford Y:\132940-\Construction\DOT 132940-013.tif GO-RD14