DATE$$ TIME$$ $USER$ | PRF $$PENTABLE$$ | DGN

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA	STP00-2348-00(003)	64	264

VOID

E-14
BETHELVIEW RD. STA 115+10 LT. 40'
C.B. GA STD 1033D
TOP EL = 1227.47
H=4.91'
I.E. = 1223.08
180 LF 18" @ 3.794%
I.E. = 1216.25

E-13
BETHELVIEW RD. STA 117+43 LT 38.5'
C.B. GA STD 1033D
TOP EL = 1219.11
H=5.00'
31 LF 18" @ 2.566%
43 LF 18" @ 1.000%
I.E. = 1214.63
I.E. = 1213.86
I.E. = 1212.44

E-15
BETHELVIEW RD. STA 117+68 RT 38.5'
C.B. GA STD 1033D
TOP EL = 1217.32
H=5.00'
I.E. = 1212.86

E-12
BETHELVIEW RD. STA 117+54 LT. 6.0'
MH GA STD 1011A
TOP EL = 1218.71
H=6.94'
I.E. = 1212.44
185 LF 18" @ 3.389%
I.E. = 1206.13

E-11
BETHELVIEW RD. STA 119+00 LT. 5.5'
C.B. GA STD 1033D MODIFIED
TOP EL = 1212.63
H=8.00'
I.E. = 1205.13

E-11
BETHELVIEW RD. STA 119+00 RT. 50.5'
C.B. GA STD 1033D
TOP EL = 1211.58
H=6.50'
BETHELVIEW RD. CONSTR CL
E-16
I.E. = 1205.58
56 LF 18" @ 0.8036%
I.E. = 1205.13

BETHELVIEW RD. STA 120+75 LT. 5.5'
C.B. GA STD 1033D MODIFIED
TOP EL = 1206.50
H=5.00'
E-10
175 LF 18" @ 1.789%
I.E. = 1202.00

PKWY NORTH BLVD CONSTR CL
REQUIRED MH
SEE DATA ON SHEET 22-02
E-9
158 LF 18" @ 2.646%
I.E. = 1197.62

BETHELVIEW RD.
STA 126+87 RT 98'
PROP CB BY OTHERS
TOP EL = 1198.03
AY-1

BETHELVIEW RD.
STA 127+02 RT 68'
D.I. GA STD 1019A TP E
TOP EL = 1195.81
H=4.79'
AY-2

BETHELVIEW RD.
STA 127+42 RT 66'
D.I. GA STD 1019A TP E
TOP EL = 1195.65
H=4.29'
AY-3
AY-4

BETHELVIEW RD.
STA 127+55 RT 75'
PROP CB BY OTHERS
TOP EL = 1198.79
32 LF 18" @ 1.000%
35 LF 18" @ 1.000%
I.E. = 1192.16
I.E. = 1191.69
I.E. = 1191.69
13 LF 18" @ 1.000%
I.E. = 1192.04
I.E. = 1192.04
I.E. = 1190.61

BETHELVIEW RD. STA 138+40 LT. 38.5'
C.B. GA STD 1033D
TOP EL = 1205.32
H=5.50'
C-2
BETHELVIEW RD. CONSTR CL
C-3
BETHELVIEW RD. STA 138+44. RT. 5.5'
C.B. GA STD 1033G
TOP EL = 1206.67
H=5.00'

BETHELVIEW RD.
STA 138+34 LT. 64.5'
REQ'D F.E.S. GA STD 1120
C-1
RIP RAP, TYP 3.
18 SY
I.E. = 1200.00
25 LF 18" @ 1.280%
I.E. = 1200.32
I.E. = 1200.82
44 LF 18" @ 3.068%
I.E. = 1202.17

SYSTEM C

SCALE:
1" = 20' HORZ.
1"=5' VERT.

Moreland Altobelli Associates, Inc.
2211 Beaver Ruin Road
Suite 190
Norcross, Georgia 30071
Telephone (770) 263-5945

SCALE IN FEET
0 20 40 80

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE:

DRAINAGE PROFILES
BETHELVIEW ROAD

DRAINAGE PROFILES
SYSTEM A, AY, C & E

DRAWING No. 22-01

3/1/2007 GPLN

...\141880\Plans\141880drpro1.dgn 5/3/2012 9:32:19 AM