DATE$$ TIME$$ $USER$ | PRF $$PENTABLE$$ | DGN

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA	STP00-2348-00(003)	67	264

VOID

D-5
BETHELVIEW RD. STA 143+25 LT. 38.5'
C.B. GA STD 1033D
TOP EL = 1201.03
H=10.50'

D-6
BETHELVIEW RD. STA 144+00 LT. 6.5'
C.B. GA STD 1033D MODIFIED
TOP EL = 1198.94
H=5.00'

80 LF 18" @ 1.000%
I.E. = 1194.44
18" OUT - SEE BELOW
I.E. = 1193.64
I.E. = 1191.03
MATCHLINE

BETHELVIEW RD
CONSTR CL

F-4
BETHELVIEW RD. STA 147+10 RT. 50.5'
C.B. GA STD 1033D
TOP EL = 1186.88
H=6.00'

BETHELVIEW RD. STA 146+90 RT. 73'
D.I. GA STD 9031-S
TOP EL = 1185.10
H=4.00'

F-5
I.E. = 1181.60
30 LF 18" @ 0.733%
I.E. = 1181.38

REQUIRED MH
SEE DATA ON SHEET 22-05

F-3
F-4
I.E. = 1181.38
56 LF 18" @ 0.768%
I.E. = 1180.95

WESTCROFT LANE
CONSTR CL

F-6
I.E. = 1180.13
48 LF 18" @ 1.417%
I.E. = 1179.45
I.E. = 1178.95

F-6
WESTCROFT LANE STA 501+12 LT. 16.5'
C.B. GA STD 1034D
TOP EL = 1184.63
H=5.00'

F-7
WESTCROFT LANE STA 501+32 LT. 16.0'
C.B. GA STD 1033D
TOP EL = 1184.70
H=4.90'
I.E. = 1180.30
20 LF 18" @ 0.850%
I.E. = 1180.13

SYSTEM F

D-3
STEEPLECHASE BLVD. STA 402+18 ON CL
M.H. GA STD 1011A
TOP EL = 1188.95
H=11.80'

D-4
BETHELVIEW RD. STA 145+25 LT. 38.5'
C.B. GA STD 1033D
TOP EL = 1193.05
H=5.00'

198 LF 18" FROM D-5 @ 1.415%
I.E. = 1188.55
86 LF 18" @ 5.500%
I.E. = 1183.82
I.E. = 1177.82
139 LF 18" @ 1.000%

STEEPLECHASE BLVD
CONSTR CL

D-2
BETHELVIEW RD. STA 147+50 LT. 50.5'
C.B. GA STD 1033D
TOP EL = 1186.43
H=10.50'
I.E. = 1176.43
I.E. = 1176.43
30 LF 18" @ 1.433%

D-1
BETHELVIEW RD.
STA 147+50 LT. 81'
REQ'D F.E.S.
GA STD 1120
RIP RAP, TYP 3.
13 SY
I.E. = 1176.00

D-3
I.E. = 1176.00
50 LF 18" @ 1.000%
I.E. = 1177.82

D-7
STEEPLECHASE BLVD STA 401+80 RT. 1.5'
C.B. GA STD 1033G
TOP EL = 1187.18
H=9.50'

STEEPLECHASE BLVD STA 401+20 LT. 30.9'
C.B. GA STD 1033D
TOP EL = 1183.43
H=5.00'

D-8
68 LF 18" @ 0.897%
I.E. = 1178.32
I.E. = 1178.93

SYSTEM D

1200 1195 1190 1185 1180 1175 1170

SCALE:
1" = 20' HORZ.
1"=5' VERT.

3/1/2007 GPLN

...\141880\Plans\141880drpro1.dgn 5/3/2012 9:33:37 AM

Moreland Altobelli Associates, Inc.
2211 Beaver Ruin Road
Suite 190
Norcross, Georgia 30071
Telephone (770) 263-5945

SCALE IN FEET
0 20 40 80

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE:

DRAINAGE PROFILES
BETHELVIEW ROAD

DRAINAGE PROFILE
SYSTEM D & F

DRAWING No. 22-04