DETAILED ESTIMATE

NH-IM-520-1(15)

PAY ITEM	DESCRIPTION	UNIT	QUANTITY
	****LIGHTING****		
682-1510	CABLE, TP RHH/RHW, AWG NO. 1	LF	1100
682-1511	CABLE, TP RHH/RHW, AWG NO. 1/0	LF	210
682-1519	CABLE, TP RHH/RHW, AWG NO. 500 MCM	LF	420
682-3424	MULTICONDUCTOR CABLE, TP RHW, 2 - #2 - 1 - #4	LF	30200
682-6110	CONDUIT, RIGID, 1"	LF	1500
682-6120	CONDUIT, RIGID, 2"	LF	180
682-6130	CONDUIT, RIGID, 3"	LF	1400
682-6140	CONDUIT, RIGID, 4"	LF	130
682-6222	CONDUIT, NONMETALLIC, TP 2, 2"	LF	23500
682-6223	CONDUIT, NONMETALLIC, TP 2, 3"	LF	5300
682-6400	CONDUIT, FLEXIBLE - 1"	LF	290
682-9010	SERVICE POLE RISER - INCL. WOOD POLE	EA	5
682-9020	ELECTRICAL JUNCTION BOX	EA	12
682-9021	ELECTRICAL JUNCTION BOX, CONCRETE GROUND MOUNTED	EA	80
683-1101	LIGHTING TOWER, STEEL, 100 FT. MH, INCL. LOWERING EQUIPMENT	EA	49
683-6566	HIGH LEVEL LUMINAIRE, SYMMETRICAL DISTRIBUTION, (TP 5) 400 WATT HPS	EA	132
	MSE WALLS		
	WALL NO 1		
627-1000	MSE WALL FACE, 0 - 10 FT HT, WALL NO 1	SF	560
627-1010	MSE WALL FACE, 10 - 20 FT HT, WALL NO 1	SF	9600
627-1020	MSE WALL FACE, 20 - 30 FT HT, WALL NO 1	SF	10800
627-1100	COPING A, WALL NO 1	LF	7
627-1140	TRAFFIC BARRIER V, WALL NO 1	LF	1100
	WALL NO 2		
627-1000	MSE WALL FACE, 0 - 10 FT HT, WALL NO 2	SF	1400
627-1010	MSE WALL FACE, 10 - 20 FT HT, WALL NO 2	SF	16300
627-1020	MSE WALL FACE, 20 - 30 FT HT, WALL NO 2	SF	11100
627-1100	COPING A, WALL NO 2	LF	8
627-1120	COPING B, WALL NO 2	LF	610
627-1140	TRAFFIC BARRIER TP V, WALL NO 2	LF	330
627-1160	TRAFFIC BARRIER TP H, WALL NO 2	LF	740
	WALL NO 3		
627-1000	MSE WALL FACE, 0 - 10 FT HT, WALL NO 3	SF	340
627-1010	MSE WALL FACE, 10 - 20 FT HT, WALL NO 3	SF	4700
627-1100	COPING A, WALL NO 3	LF	300
627-1180	ADDITIONAL MSE BACKFILL	CY	1200
	WALL NO 4		
627-1010	MSE WALL FACE, 10 - 20 FT HT, WALL NO 4	SF	3000
627-1100	COPING A, WALL NO 4	LF	170
627-1180	ADDITIONAL MSE BACKFILL	CY	860
	WALL NO 7		
627-1000	MSE WALL FACE, 0 - 10 FT HT, WALL NO 7	SF	1700
627-1010	MSE WALL FACE, 10 - 20 FT HT, WALL NO 7	SF	8200
627-1020	MSE WALL FACE, 20 - 30 FT HT, WALL NO 7	SF	9000
627-1140	TRAFFIC BARRIER, TP V, WALL NO 7	LF	1100
627-1100	COPING A, WALL NO 7	LF	160
627-1180	ADDITIONAL MSE BACKFILL	CY	4000

GREENHORNE & O' MARA
GO PROJECT NO. 0085
2211 NEWMARKET PARKWAY
SUITE 104
MARIETTA, GA. 30067
(770) 988-9555

DATE	REVISIONS
11-17-06	GENERAL REVISIONS.

DATE	REVISIONS

GEORGIA
DEPARTMENT OF TRANSPORTATION
DETAILED ESTIMATE
PROJECT: NH-IM-520-1(15)
COUNTY: RICHMOND/COLUMBIA
DATE:
DRAWING 4-07

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NH-IM-520-1(15)	61	132

11/12/2008 9:53:41 AM \\ATLFS2\JOBS\CIVIL\CADNET\DGF\98TOlcoF atlpolotsxs JAYT-cex\0085\PLOT\mxsc\2184586ds.07.pcf